

OPEN TECHNICAL  
WRITING  
AN OPEN-ACCESS TEXT  
FOR INSTRUCTION IN  
TECHNICAL AND  
PROFESSIONAL  
WRITING



*Adam Rex Pope*  
University of Arkansas, Fayetteville

Open Technical Writing  
An Open-Access Text for Instruction in  
Technical and Professional Writing

Adam Rex Pope

University of Arkansas, Fayetteville

This text is disseminated via the Open Education Resource (OER) LibreTexts Project (<https://LibreTexts.org>) and like the thousands of other texts available within this powerful platform, it is freely available for reading, printing, and "consuming."

The LibreTexts mission is to bring together students, faculty, and scholars in a collaborative effort to provide an accessible, and comprehensive platform that empowers our community to develop, curate, adapt, and adopt openly licensed resources and technologies; through these efforts we can reduce the financial burden born from traditional educational resource costs, ensuring education is more accessible for students and communities worldwide.

Most, but not all, pages in the library have licenses that may allow individuals to make changes, save, and print this book. Carefully consult the applicable license(s) before pursuing such effects. Instructors can adopt existing LibreTexts texts or Remix them to quickly build course-specific resources to meet the needs of their students. Unlike traditional textbooks, LibreTexts' web based origins allow powerful integration of advanced features and new technologies to support learning.



LibreTexts is the adaptable, user-friendly non-profit open education resource platform that educators trust for creating, customizing, and sharing accessible, interactive textbooks, adaptive homework, and ancillary materials. We collaborate with individuals and organizations to champion open education initiatives, support institutional publishing programs, drive curriculum development projects, and more.

The LibreTexts libraries are Powered by [NICE CXone Expert](#) and was supported by the Department of Education Open Textbook Pilot Project, the California Education Learning Lab, the UC Davis Office of the Provost, the UC Davis Library, the California State University Affordable Learning Solutions Program, and Merlot. This material is based upon work supported by the National Science Foundation under Grant No. 1246120, 1525057, and 1413739.

Any opinions, findings, and conclusions or recommendations expressed in this material are those of the author(s) and do not necessarily reflect the views of the National Science Foundation nor the US Department of Education.

Have questions or comments? For information about adoptions or adaptations contact [info@LibreTexts.org](mailto:info@LibreTexts.org) or visit our main website at <https://LibreTexts.org>.

This text was compiled on 11/24/2025

# TABLE OF CONTENTS

## Licensing

### 1: What is Technical Writing?

- 1.0: What is Technical Writing?
- 1.1: Ethical Stakes in Technical Writing
- 1.2: Professional Voice and Technical Communication
- 1.3: Signposting and Taxonomy

### 2: The User

- 2.0: Introduction
- 2.1: Technical Writing and the Audience
- 2.2: Users and the Drafting Process
- 2.3: Technical Writing Research and Writing Process
- 2.4: Usability, Use, and Participatory Design
- 2.5: Institutional Writing

### 3: Visual Communication and Technical Writing

- 3.0: Introduction
- 3.1: How does visual communication work?
- 3.2: Using visual conventions
- 3.3: Signs, Safety, and Visual Rhetoric
- 3.4: Data Visualization and Infographics

### 4: Document Design in Technical Writing

- 4.0: Introduction
- 4.1: Document Design Essentials is Essential
- 4.2: Layout and Document Design
- 4.3: Typography
- 4.4: Attributes of Fonts
- 4.5: Font Availability and Ethics
- 4.6: Remembering those signposts

### 5: Writing in Genres

- 5.0: Introduction
- 5.1: Genre Research
- 5.2: Popular Genres in Technical Writing

### 6: Managing a Project

- 6.0: Introduction
- 6.1: Ideas, Audience, and Goals
- 6.2: Working with Others (Inside and Outside the Team)
- 6.3: Prototypes and Iteration
- 6.4: Rights and Images

- [6.5: Editing for Publication](#)
- [6.6: Publication](#)
- [6.7: Closing it Out](#)

## [7: Research Methods for Technical Writing](#)

- [7.0: Introduction](#)
- [7.1: Doing Research with People](#)
- [7.2: Interviews](#)
- [7.3: Talk-Aloud Protocols](#)
- [7.4: Card Sorting](#)
- [7.5: Participatory Design](#)
- [7.6: Observation](#)

### [Front Matter](#)

- [TitlePage](#)
- [InfoPage](#)

### [Index](#)

### [Glossary](#)

### [Detailed Licensing](#)

### [Sources](#)

### [Back Matter](#)

- [Index](#)

## Licensing

---

A detailed breakdown of this resource's licensing can be found in [Back Matter/Detailed Licensing](#).

## CHAPTER OVERVIEW

### 1: What is Technical Writing?

- 1.0: What is Technical Writing?
- 1.1: Ethical Stakes in Technical Writing
- 1.2: Professional Voice and Technical Communication
- 1.3: Signposting and Taxonomy

---

This page titled [1: What is Technical Writing?](#) is shared under a [CC BY-SA 4.0](#) license and was authored, remixed, and/or curated by [Adam Rex Pope](#) via [source content](#) that was edited to the style and standards of the LibreTexts platform.

## 1.0: What is Technical Writing?

---

### What is Technical Writing

This is a textbook about technical writing. But, what is technical writing exactly? There are any number of definitions of what exactly should or should not be technical writing, just like there are any number of definitions of what should or should not be just about anything that people care about.

Some definitions are different because they are used by folks doing wildly different things. For example, what I consider running might be drastically different than what you consider running. For me, it's going 2-6 miles at a pace of around 12 minutes per mile. You might run considerably slower or faster, shorter or longer, meaning that your definition of running and my definition of running differ because we are simply doing things differently.

Other definitions are different because the folks behind them have an agenda that they're looking to push. For example, some people will stick to their position that pineapple is not a legitimate pizza topping. They stick to that definition because it is meaningful to them. For them to win out and have their definition win out is to win widespread acceptance of their position that pineapple on a pizza is an abomination. (As your author, I have no strong feelings on the subject. Pizza can have a lot of toppings. However, crockpot pizza is not pizza and never will be. You have to draw the line somewhere).

So, since definitions differ wildly, our definition of technical writing either needs to be oddly specific to the type of work we're going to be doing in this textbook, or it needs to be fairly broad to encompass as many of technical writing's use cases as possible. Now, either direction is going to leave some folks feeling a bit disappointed in what we've come up with, but I think that the most productive approach is to define technical writing in a broad way that maximizes the types of work and people that can use the term productively. This textbook is after all being designed for a course that serves any number of majors, and it makes no sense for us to play favorites.

### Getting at Technical Writing

Technical writing, as we will be defining it, is writing that conveys information that has to be accurate in order to be of use. This may seem like an overly broad approach to defining the subject, but bear with me and we'll tackle what exactly this means and how to unpack it, as well as some traditional competing definitions of technical writing you may have heard of or may eventually encounter.

Let's start with an example to show how our definition can work. If I'm going to be baking a pizza crust recipe that you've shared with me, there are some things that simply have to be conveyed properly or you'll end up with a terrible pizza. If I tell you to bake the pizza at 550 degrees for 10 minutes, that is one thing. But, if you end up with a copy of the recipe that says to bake at 250 degrees for 10 minutes, you will not end up with my pizza at all. I doubt your pizza would even be edible. In this example, the technical information of how long and what temperature to bake the pizza was crucial. It could not be altered in any significant way without altering the outcome of the baking. It simply can't work without being accurate. In short, the recipe was technical writing.


Going beyond our example, we can expect that almost any cooking recipe would also be technical writing since you have to get things together as the recipe requests for the results to be what you're expecting. Yes, you can alter things here or there (or make substitutions), but in doing so you are altering the final outcome away from the expected one. You simply can't toss the recipe out the window and expect it to work. In fact, you'll find that most folks that skillfully alter recipes are able to do so because they understand what is happening in the original and understand what their modifications are doing and how they are interacting with the original set of instructions and ingredients.

Now, before I go further, it should be pointed out that you can take our definition of technical writing and think about things the wrong way. One common mistake that folks make with technical writing is to assume that since technical writing is about the finicky details that you simply need to convey those details as plainly as possible and you're doing the best possible technical writing. In their mind, you're going to be doing the best job when you simply give someone "the facts," and nothing more. It is akin to packing something in a box and then sending it to someone else. You only put "the facts" in the box, and when they open the box, all they get is "the facts."

Unfortunately, this idea is not only wrong-headed—it can cause us to be terrible technical writers. The issue with a "just the facts" approach to technical writing is that the approach makes it seem that the only thing that ever matters is the facts. You can simply

package them up and send them along to another person and as long as you managed to get those facts in there, everything is alright. The problem is that this example breaks down whenever you start to question it in the slightest.

To explain what is wrong this mindset, we can actually use the same example from above with a few tweaks. For one, the way a message is packaged impacts how we respond to it. Let's say that you package up your facts in a box and send it to someone. If we take this example literally, then we need to think about what the box looks like. Is it a plain brown box like this:




**A PLAIN BOX**

If it is a plain brown box, does that impact your way of thinking? Do you normally get a certain type of thing in a plain brown box? I actually do associate plain brown boxes with a particular vendor I use for one of my hobbies!

If you get a box that is wrapped in pretty paper with a bow on it, what do you think about the contents? Do you expect to get a bill for \$1250 from your last emergency room visit when you open that box? Probably not. And if you did get that, you'd likely be really upset and have trouble handling that information because the box was sending one message while the contents sent another. And you'd likely get kind of mad at whoever sent the box to you this way:

(This is what happens when you get to write an open-access book but can't draw a bow to save your life)



**A DECORATIVE BOX**

In the same way, the delivery mechanism of a message also impacts our perceptions. If we get a box that is wrapped up in a bow from a friend or relative, we expect that it is a present and likely take it gladly. If we're given the same box by someone we've

never seen in our lives, it might not get the same reception. We might ask, “Who is this person? Why are they handing me this gift box?” We definitely wouldn’t accept the box without some leeriness, and we might not trust whatever was inside, if we even open it at all. The sender of a message matters as much as the packaging.

Now, if we map these examples back onto technical writing, note that the same principles apply to “the facts.” If you get a technical document from someone that you know and trust, you’re likely going to treat those “facts” with more trust and confidence because you know the text comes from a reliable source. At the same time, if you get something from someone you don’t trust, you may double-check all the information they’ve given you because you simply don’t trust them. This can also apply to the way something is packaged. If you get a document that proclaims to be super-serious and the contents aren’t, you may ignore what is included. At the same time, an official document that looks overdone or fake may get discounted as junk! Both the sender and the way contents are presented matter a great deal! (For example, awful box drawings like the one above may well get some folks to discount open-access textbooks without reading them).

Before we move on to competing definitions of technical writing, I have one more point I want to make, because even with our examples above it could be possible that you have a few misconceptions about technical writing. In our examples below, we’re always conveying “the facts,” in our messages or our boxes. And, in those examples, it would seem that no matter what we’re still conveying “just the facts” once we cut out all the extra cruft. The essential facts never change in those examples, but when we do technical writing they very well can!

Think about it for a moment: do you explain how to use a new app the same way when you talk to a friend and when you talk to an elderly person in your family? The answer is most likely no. There are extra steps involved in one situation, and some steps are omitted entirely in the other. The “facts” of the matter change depending on how well they’re going to be understood. You can’t simply say “this is how it is” and let things end there with someone who is so wholly unprepared to understand your instructions that they don’t even know where to begin. You have to supplement things, add content, and perhaps even alter the way you convey your points. You can’t just rely on “the facts” as a stable entity because you’ll alter their contents depending on what your audience can understand and what they know and don’t know about a given situation.

With that cleared up, let’s return to our definition of technical writing: it is writing and communication that conveys essential information that can’t be changed without causing damage to the outcome of using that information. But, we take that with the caveat that who shares that information, the way they share that information, and who they share it to, all of these things will have an impact on the final reception of the technical information. Technical writing then, is an act of translation. We may have to alter a great many things so that our reader/recipient properly understands what we’re getting at, but we’re still trying to get them to understand the same thing we started with. It just may look a lot different after we’ve translated it for them, and they may treat it differently than they would if someone else had shared it with them.

There is a fundamental shared value we’re all working off of—we’re not veering into total relativism here. But, we’re working with the understanding that what we know and how we use what we know is colored by who we are and how we internalize information. For example, we can all operate with the same cookie recipe, but depending on the person we cooked it with and the way they operated their kitchen and the memories we associate with them, our own mental image of that recipe can be much different than anyone else’s. The same recipe may be Grandma’s Secret Recipe, the recipe on the back of the flour bag, and that recipe you found online. Same fundamental recipe, totally different treatment of the recipe and use of it depending on your context and how you met the recipe.

As you maybe can tell, technical writing gets intense pretty fast—I mean, we’re talking about cookies and relativism in the first chapter...heavy stuff. But, that’s what makes it so much fun to study and practice—it isn’t simple and it definitely isn’t static!

### Competing Technical Writings

At this point, I should note that the way we’re defining technical writing may be different from other ways you’ve seen it defined or will see it defined. In my experience, our definition is perhaps overly broad compared to other versions of technical writing, but there is a reason for that broadness.

Some folks like to say that technical writing is something that only belongs to technical fields like engineering or medicine. They might snort if you told them your grandmother’s cookie recipe is technical writing just like their specs for a bridge under

construction are technical writing. That's a problem because it limits the scope of what technical writing is and what we can study and who can study within the field. It closes off avenues of practice as much as it opens them up.

Historically, folks have used definitions of what is or is not technical writing to control who has a seat at the table, so to speak, in the field. When someone wants to tell you what is or is not technical writing, they're making a power play. They are attempting to define the field in a particular way, usually one that makes sense to them and gives them an advantage. Often times in history this has been used to keep, for example, the work of woman out of technical writing. We may at times be amazed (or maybe not so amazed) at the extent that people would go to in order to keep women or some other group out of a particular field, but it has happened time and time again. Again, definitions are powerful.

So, our broad definition serves a definite purpose—to make sure that we're not excluding anyone or anything that should/could be part of technical writing. An added advantage to that move is that we get a lot more cool stuff to study that we'd be missing out on if we limited ourselves to engineering and closely related fields. Instead, we get to look at any number of texts that are conveying technical information, often in very sophisticated ways, that have been historically overlooked by rather narrow definitions of the field. (Video game theory-crafting comes to mind as one interesting example).

---

This page titled [1.0: What is Technical Writing?](#) is shared under a [CC BY-SA 4.0](#) license and was authored, remixed, and/or curated by [Adam Rex Pope](#) via [source content](#) that was edited to the style and standards of the LibreTexts platform.

## 1.1: Ethical Stakes in Technical Writing

### Ethical Stakes in Technical Writing

Having talked about what technical writing is and what it studies, I want to focus on perhaps the most important aspect of technical writing that we could possibly discuss—the ethical stakes of technical writing and communication. To examine the ethical stakes, we’re going to first define ethical stakes, then look at the way those stakes manifest in the people that use our writing, the laws and regulations that govern our writing, and finally by looking at how ethical stakes operate in institutions and organizations.

#### What are ethical stakes anyway?

When we talk about ethics, it is worth taking a moment to address the elephant in the room—how do we differentiate morals and ethics? Aren’t they the same thing? Why is a course on writing trying to get into moral behavior with me? Look below for my response.

Ethics are rules or regulations that govern behavior. They are usually part of a professional organization’s code of conduct, the rules that govern a particular industry or profession, or even the laws of the land. They can also extend into rules and practices in religious texts. But, in each of these cases, the key to ethics is that they are codified—they’re written down and standardized for practical application.

Morals, on the other hand, are your own internal compass of right and wrong. They are that little voice in the back of your head that tells you that eating your roommate’s donuts while they oversleep breakfast might not be the nicest thing to do. They are individualized and aren’t something you can always expect everyone to agree on. Some folks feel strongly about eating certain foods, using certain words, or doing certain things. Those feelings are part of their own moral compass and not something open to universal application or critique.

So, when we’re doing technical writing we’re mainly concerned with discussing ethical stakes—those rules and regulations that govern what is appropriate behavior and actions in professional or organized settings. Just like with our definition of technical writing, our definition of professional or organized settings can be very broad. After all, we have to account for folks swapping recipes or swapping talent builds and folks who are passing along specs for the material tolerances of a new bridge. In each case, people are being impacted and are working with, ideally, a shared understanding of what ethical behavior is and what is expected of each participant.

Now, with that said I do want to return to morals for one moment. We aren’t going to be diving into morals much in this text, but I do want to lay out thing out very clearly—morals do matter in technical writing practice. You should stay true to your moral compass in your professional life. If something make you uneasy or feels wrong, there is a very good chance it is! Technical writing has been used for some very unsavory and downright evil activities simply due to how and where it works—in institutional settings. Just because someone you’re working with claims something is ethical and alright doesn’t make it so. Ethical codes change over time and evolve, and sometimes they’re just wrong. Use common sense and your own morals to guide you. Don’t buy into the idea that if the organization or boss says it’s alright, it’s alright.

#### Technical Writing and People

Technical writing at its core is writing that helps people do stuff, and doing stuff involves some level of risk and responsibility. If you’re writing instructions on how to fold an origami boat, then the risk is that you may mess up a piece of paper—relatively low stakes. But, what if you’re doing something much more dangerous and involved? If you’re operating a heavy piece of farming equipment, good technical documentation could be the difference between a harvested field and a funeral service— stakes that are life or death.

Since our writing is being used to help folks do stuff, we have to always keep those folks in mind and keep in mind our impact on them. A little bit later in the text we’ll get into the business of audience analysis—understanding who we are writing to and what their needs are. Having a firm idea of who our audience is and what they are going to need from our text and what they’re already going to know is an important starting point for any good technical writing—even a good cookie recipe!

Suffice it to say for now that ethical writing regarding people hinges on matching up our text to those individuals’ needs and expectations. Good and ethical technical writing makes things easy for folks to safely carry out whatever activity the technical

writing is mediating. Unethical technical writing puts up barriers for the sake of creating barriers or simply doesn't take into account the user at all. (Often times this comes from writing for the writer and not the reader—you make choices that are easy for you, but not easy for the person using your text, a production-centered mindset that we'll talk about later).

Unethical technical writing can be sneaky, so we have to keep an eye out for it. Sometimes you could do some of the above things without setting out to be unethical—you just aren't thinking or you are just taking the easy way out. In other cases, you may encounter folks with an open agenda to disenfranchise or impede others through technical writing. Keep your eyes open and think about what a text looks like from multiple points of view.

### Technical Writing and Laws and Regulations

Laws and regulations are a huge part of technical writing, and for good reason. Technical writing is only useful if it can be understood, and a large part of how we write is regulated with that in mind. Regulations and laws serve different purposes for technical writing, but both have ethical components that impact the way that we write and work.

Regulations and standards are one way that we impose order on the work we do. Standards can be as basic and universal as making sure that your kilogram and my kilogram are the same weight, but they can be much more idiosyncratic. For example, you have the ASTM standards for skateboard helmets that are different than the standard certification for bicycle helmets due to the different level of impact and types of impacts involved. Someone cruising on their bike is going to have a different set of impacts than someone trying to rock-to-fakie in a massive bowl; the standard recognizes that.

Standards also exist for materials that are used in construction and industry. In fact, a lot of the traditional technical writing associated with engineering came about from the process of standardization! When the steel industry, among other industries, was first coming into its own, you had a lot of mystery behind what made for good or bad steel. If one batch failed and another batch was fine, no one could be sure why that happened. Wanting to maintain consistency and avoid bad steel that could get people killed, engineers took to documenting their processes and measuring their products to develop a durable standard. All of the documentation around this crucial process was technical writing, and it was one of the ways that technical writing and engineering became closely linked.

When we write as technical writers, we have to take into account any relevant regulations and laws that might impact our practice and make changes accordingly. For example, if you're working in a real estate setting and you're listing a house, there are regulations from the U.S. government that you have to follow in order to have a legal listing. Let's say the person that you're working for wants to list their house as great for families with young kids. That's all well and good, but it's also illegal to put into a listing. Housing regulations prevent sellers from promoting a particular type of buyer or avoiding a particular type of buyer for their property. (Though, they haven't always...and the impact of those past choices are still shaping where we live and who we know). If you're writing for real estate, you simply can't talk about the type of family/person that would be a good fit for a home in your listing; it's against the law.

Another example of regulations coming into play would be financial products. You could be writing ad copy for a particular financial product and think, "This is such a great fund—you'll never lose money with this!" That is great and all, but you can't legally say that. Any type of non-guaranteed product in the financial market can't be sold to potential buyers as risk-free when it actually isn't. You can't guarantee things without having a mechanism to ensure what you're guaranteeing.

As writers, we need to be aware of the industries we are writing in and their particular rules and relevant legal regulations. Every industry will be different, but we're required to know the rules of the road when we're writing professionally. For example, if you're teaching you need to have a strong understanding of FERPA regulations. If you're a nurse or medical professional, you need to understand how HIPAA works and what your employer interprets as a violation. (And yes, each of these rules are open to interpretation by specific employers). If you don't make yourself aware of these rules and regulations, you risk opening up your employer or yourself to legal action or fines while simultaneously sharing private information without permission, something that often has serious personal consequences.

Now, some of these regulations and laws may seem burdensome. Sometimes they can be burdensome. But, they are in place for a reason. FERPA exists so that your grades and records are protected. Does it make sharing information about grades more difficult? Yes, yes it does. But, that is the price that we pay to make sure your educational records are safe. Privacy and information security aren't free or automatic. As you work through writing that has burdensome legal regulations around it, try to keep in mind that the

extra writing you're doing does have a purpose and that in fulfilling your legal and ethical duties you're likely making the world a safer or better place for the folks being protected by the regulations and laws you're following.

### Technical Writing and Organizations

When you're writing in an organizational setting, be aware that you may have yet another level of scrutiny and regulation put onto your work. Organizations have their own standards and their own processes to make sure that things come out the door in a way that is consistent with their desired public-facing image. For example, you might end up using a visual or editorial style guide when you write copy for marketing purposes to make sure that your visuals and your language sync up with the newest campaign that your company/organization is making use of.

With that said, one thing you need to be aware of is that within organizations there can be situations where you may be asked to cut corners or ignore ethical guidelines. You might wonder why in the world someone would create technical writing about an unethical choice or series of actions, but the history of technical writing is littered with corporate scandals that were unearthed via mundane technical writing. From the Ford Pinto to the Challenger explosion to the Volkswagen Emissions Scandal, technical writing and communication goes hand in hand with unethical choices as often as it does ethical ones. Like any tool, you can use it for good or evil.

When you're writing in an organization, there can be enormous pressure to do what's right by the company rather than what's the legal and ethical choice. As a technical writer, and as an individual, it is up to you to make the right choice in these situations. History is full of folks that said, "Okay, I'll do it," in the face of an unethical ask. Be one of the folks that say no. They sleep better at night.

---

This page titled [1.1: Ethical Stakes in Technical Writing](#) is shared under a [CC BY-SA 4.0](#) license and was authored, remixed, and/or curated by [Adam Rex Pope](#) via [source content](#) that was edited to the style and standards of the LibreTexts platform.

## 1.2: Professional Voice and Technical Communication

### Professional Voice and Technical Communication

Another fundamental aspect of being a good professional and technical writer is developing a professional voice. One of the things that I tell all my students, graduate and undergraduate, is that there is a clear and fundamental difference between knowing what you're talking about and sounding like you know what you're talking about. The difference between these two is often the presence or lack of a professional persona or professional voice.

What exactly is a professional voice? Well, we could probably spend an entire semester working on just that. Entire books have been written and will be written on style, but for our purposes I define professional voice thus: writing with appropriate authority, allowing sources to back you up rather than speak for you. That may seem subtle, and in a way it is, but placing yourself in the position of authority is a cornerstone of both coming across as a professional as well as owning up to your responsibilities in a professional setting.

Often times when we're writing as grade school or even high school students, we're put into a position with research where the research itself becomes the focus of our writing. You write a term paper that needs 10 sources, and those sources are the term paper; you're simply creating a vessel for them to be shared with the world. While that type of investigative writing can be useful, the presentation that it lends itself to is not.

When we present ourselves as professionals, we are the ones who have done the research, who know the relevant background information and sources need. If you know it, write and talk that way! (And if you don't, do that work so that you don't end up being one of those folks that sound like they know what they're talking about when they are in fact clueless). Below you'll find a couple of example sentences that lay out the differences I'm conveying. See if you can guess which is professional voice:

#### ✓ Example 1

There are a couple of things that apply when we decide whether to build a coal or natural gas plant. According to the Guide to Greenhouse Emissions by Lora Fitts (2015), "there is a large difference between the emissions generated by coal and by natural gas production" (p. 159). Elsewhere, Boris Johnson (2017) writes in Energy Choices for the Future that "building for coal at this point in history is a backwards point of view for any forward-facing organization" (p. 257).

#### ✓ Example 2

The research available does not support the choice to build a coal-powered plant on campus. Recent work studying emissions shows that coal has a much more aggressive pollution profile vs. natural gas (Fitts 2015), and the general consensus among experts is that coal is at best a backwards choice for any new construction (Johnson 2017).

Looking at these two examples, you should be able to see a marked difference in the way that the author tackles the subject matter at hand and its presentation. The first example maps to the classic "this is what I read" approach where you simply repeat the wording of your sources verbatim, often while naming the exact book/journal/article that you're drawing on. Now, that is not to say there is not a place for this type of research (there is), but for the most part when you put all of this information in the text, you're overloading the reader with content they really don't need. The Works Cited page of your text is the place for most of this information in a normal setting, and what you're doing is taking the decision-making process and offloading it to experts rather than owning the choice yourself. Even in situations where your job is simply to inform, you should own the collection and presentation of the data you've found!

Notice that in example 2, the author makes a clear point (we should not build a coal plant) and then backs it up with strong statements that are supported by relevant citations. The author isn't hiding behind sources and isn't asking the reader or the sources to make a decision. Instead, the author has decided what they want to say and is simply telling you what they've found out from research. This is the essence of professional voice—doing the homework and the research and then presenting your point of view accordingly. Instead of talking about your sources, you talk for them and let them back you up. Note that the author doesn't go beyond the sources quoted in the first example, but simply uses them as the backing for their own representation.

Metaphorically speaking, Example 1 represents you, the author, hiding behind your sources. Instead of showing your work and what you think, you throw up the sources and hope for the best. Example 2 takes a different course, using the sources as a backing to make a statement that you feel is correct. In Example 2, you're the one making a firm statement, and if someone wants to question that choice, they can go to the sources you've cited. You've done the homework and now you're telling folks what you think.

For professional settings, Example 2 is often the way to go. One of the more common complaints about student writing is that it often doesn't communicate clearly and directly. Taking ownership of the text and the points, allowing sources to back you up rather than hiding behind them, tackles that problem head-on. Now, that isn't to say that you will never need to write the way Example 1 is framed, but that isn't going to be as common.

Even in a literature review setting, you're being asked to take ownership of the text in a way that simply repeating sources doesn't. A literature review, if you think about it, is the product of you reading all of the relevant literature on a subject and then presenting that research to an audience. You are the one making the call on what belongs and doesn't, and you are the one that is naming the various camps, setting up their arguments, and explaining how they interrelate. That's a lot of work for you, the author, even though you're primarily telling someone what other people have said! It is your literature review after all, and you need to own that for better or worse.

So, when it comes to professional voice and technical writing and communication, keep in mind that you're the expert, the one doing the research and the presentation. Own that role, and make your points with your sources doing the backing. Don't use them as a shield, but use them instead as backup when you make your points. One day, you may not need to use them at all, once you've become the expert in a given area. Think about someone like the late Neil Armstrong—who would realistically question his description of walking on the moon? In a situation where he has explained what that is like, he is the source. He's the expert because an ever-shrinking number of people are primary sources that have actually been on the moon and returned to tell us about it! And eventually, you may be in a similar position in your own niche area of study and professional practice. Until then, use other sources to make your points with appropriate authority.

---

This page titled [1.2: Professional Voice and Technical Communication](#) is shared under a [CC BY-SA 4.0](#) license and was authored, remixed, and/or curated by [Adam Rex Pope](#) via [source content](#) that was edited to the style and standards of the LibreTexts platform.

## 1.3: Signposting and Taxonomy

### Signposting and Taxonomy

For our final subject in Chapter 1, I want to mention a crucial duo central to effective technical writing: signposting and taxonomy. These two subjects are closely related, in that signposting relies on a taxonomy of sorts to operate, and is an expression of taxonomy, but they are worth treating individually as well as jointly. In a nutshell, these two tools are used to shape your text so that it has a definite structure that can be seen, ideally, at a glance. We'll get more into the idea of taxonomy a bit later in the text, and in many ways the Cardsorting resource in the back of the text is entirely about these two subjects, viewed through the lens of potential users. We'll look at signposting first before moving to taxonomy and then back between the two.

#### Basic Textual Signposting

Signposting is at its core telling your reader what is happening in your text. This signposting happens at two different levels, and both are important to readers in their own ways. The first way that signposting happens is via the text itself. When you use terms like “firstly,” “second,” “next,” and “finally,” you are using signposting embedded within the text in a basic way. In addition to this basic approach, you can also do higher level signposting, but let's unpack the basic approach first before adding complexity.

Basic signposting with order-based terms tells your readers a few things, and you need to be aware that you're telling your reader those things! Nothing is worse than when someone is signaling something while not realizing they're signaling anything at all, or when they think they're signaling something else entirely. If you've learned a foreign language, you've run into this issue with the subject of false cognates, terms that sound like words in your home language that mean something drastically different in the language you're now speaking.

When you say something like “next” to your reader, you are indicating that you're working through a series of steps or ideas, and that you are now transitioning from one such idea/step to another. Being aware of this transition and taking advantage of it makes you a more effective technical writer and communicator. These terms are crucial in technical writing because many times the information we are conveying is quite complex. We don't want to be adding to that complexity with even more complexity in our text. When we do so, we're in effect creating two levels of understanding the reader needs to master: they need to master our text and our odd dialect/presentation and they need to master the actual information we're presenting to them. For example, attempting to learn how to put together a set of furniture with instructions written in Middle English presents two challenges at the same time.

Now, I'm mentioning the two levels of understanding that readers have to deal with as separate entities to make a point, but in reality they are not so simple to break apart. Your “facts” can't be separated from your presentation. “Just the facts” as an approach to technical writing, as we discussed previously, leads to a situation where you simply ignore the impact of your position as the author, of the format you choose for your facts, and even the impact of the medium you've chosen.

To use a metaphor, think about your signposting and textual decisions as one ingredient to a text or recipe. You also have outside information you're including in the text as well, and these different ingredients react to each other while also having their own preparations that impact the way they are expressed. You can simply insert a table of data into a paper in the same way you add a stick of cold butter to a recipe. This impacts the way it works and how you will proceed and how your reader will proceed. You can also take the data from that table and instead of simply pasting the table, you can explain one bit at a time to the reader in paragraph form. This might be the equivalent of melting butter down and clarifying it before use. You have the same ingredient, but it's being processed in different ways with different effects.

The signposts you add are like yet another ingredient, something perhaps like salt or yeast in a dough. To an extent, they are simply altering the way the recipe is going to be operate. More yeast, more rising. But, at the same time, they impart a flavor to the recipe. Yeast bread tastes fundamentally different than non-yeast bread. The same works with signposting in that terms like “next” impact the overall flow of the text and how someone reads it, but at the same time they add a distinct flavor to the text, signaling that this is going to be the sort of text where you get these types of aids, and that in the future you should look for them and depend on them.

Simple, order-based signposts are also an authorial aid—they help you think through your own series of steps and content. You need to know when you're transitioning to use “next” effectively. You need to have an idea of steps to be able to assign points one,

two, and three. In thinking about these, ideally you do so through the dual lenses of what you intend to say and who you intend to read your content, tailoring your choices based on those two elements at a minimum.

### Advanced Signposting and Document Maps

To make the most out of simple signposting, you need to have a larger level of signpost that you can sync up with at the section level as well as at the document level. This is where signposting really shines!

Top-level signposting usually involves a section or document map of some sort. A document map functions just like the name suggests—it provides readers with a list of topics that will be covered or sections that will be present, and it usually does so while mirroring the order found in the text. You may have noticed a few maps in this document already, and if not, look for something with the following format:

In the next section, we'll be looking at the shape of the material, the properties of the alloys that make up the material, and the relationship between these two elements and the friction forces the material creates.

In this example, you have a basic map that is connected to a larger map while also containing a section-specific map. First, you have the connection to a larger map with the terms, "In the next section." This phrase lets us know that we're moving from one major section to another, likely linking up to a larger list of sections that was introduced at the start of the text or the start of this series of sections. Next, you have the specific map for this section of text with the list of different aspects of the material that will be discussed. This list allows readers to know what will be coming up next, and as they transition through each of these steps, they'll be able to mentally check their progress through the section based on this map. At the same time, they also realize this progression is the next in a larger series of progressions that make up the entirety of a given text.

Don't underestimate the power of this approach! Document maps are essential for almost all technical writing that is more than a couple of paragraphs (and even then, I'd argue they are useful). Using a map, you provide the reader with a clear expectation of what content will be found and what order it will be found in. You can then use this in concert with basic signposting to move between sections/ points, or you can combine it with maps in each section listed to provide even more detail to the reader.

And, in larger documents that have a table of contents, all of this can sync up to that table and provide the reader a global view of the document map and the section maps.

### Signposting Format or Why Headings Are Important

Having discussed basic and advanced signposting, I need to pause for a moment to discuss what this can look like in a visual sense. You could, and many people do, simply do all of this work in the text itself. You can locate the maps and the directional signposts in the text and when the reader encounters those maps, they can then use them accordingly. With that said, if you want your reader to get the most out of all your work creating maps of sections and sub-sections, you need to use headings.

Headings like the numerous headings you've encountered in this text already, are the key to making signposts really work for the reader. It is one thing to run into a map and to be able to then identify through the text when the next section has arrived. It is something entirely different to be able to see sections change by browsing through the text and noting the various textual landmarks the map has identified via bolded or italicized or colored headings and subheadings. These headings allow the reader to skim through your text to quickly locate a section they may want to read alone or reread.


In the context of usage, headings can help someone find content in a text that isn't meant to be read as a narrative. Think about car manuals or recipe books. Neither of these texts really shines when you read them front-to-back. Yes, you can do that (and you might when you first get the text), but these texts are essentially a reference for someone who needs a slice of the data in the text. That's also true in report settings where someone only wants the highlights of your text, or they want to see one particular part because of their role in an organization. We'll discuss this more when we get to audience and use and again when we get to genre.

### Taxonomy and Signposting

When we use the term taxonomy in technical writing, we're referring to the way that we divide something in parts or sections. The study of taxonomy is really the study of how you divide something up and the impact of that division. You may wonder how that can be useful in a writing setting, or any setting at all, so let's dive into how taxonomy can be used in specific scenarios.

## How does taxonomy work?

One simple example of taxonomy you may not be aware of is the way that you organize apps on the home screen of your phone. A taxonomy requires items and it requires groupings of those items as well as depth to those groupings, something the interface on your phone provides via pages of apps as well as folders. Take a look at the example of the iPad Pro interface I'm currently using as I write this chapter:



In the example above, I've got a rather terrible taxonomy that needs some work. I have three major groupings, some are useful and some are not. The overall order of the page seems to have no real sense to it. Why does Tips come first? What is the significance of Messenger next to Create? To be honest, there is no purpose here to those choices. I've simply left them in the order they were installed. All of these form the top level of the taxonomy's hierarchy (we will ignore the shortcut bar for this example, though it does wonderfully compliment the discussion).

When I open up the iPad, these are my choices. I can navigate to the one I want via memory or via reading the various choices available. The advantage of the folders grouping things together is that I'm allowed to have more choices on the same page without muddling things up and at the same time I simplify the choices available. I can make the global choice, Office Tools, when I want to do something Office related. When I want to do something with Adobe, I can use that folder. This allows me to see those choices as a global choice alongside Tips and Messenger. It is a way of viewing and sorting the content on my iPad. As I said, it is not a very good way of doing this (I've not put a lot of thought and time into it), but it is a way of doing the content sorting.

Taxonomy really does come down to mundane things like my iPad Pro's interface—how do we organize things and how do we label them and the groups we put them into? When it comes to phones and other devices, this impacts the way we use things and the way we find things. The principle also applies to physical workplaces with idiosyncratic stacking and filing methods. Taxonomy is nearly universal, but for the most part we'll focus from this point onward on the impact it has on technical writing.

## Taxonomy and Documents

When you create sections and sub-sections in a text, you are creating a taxonomy in/for your document. You are saying that this major heading describes the content contained within, and that certain sub-sections make sense in certain places. Not everyone will agree with every taxonomy you create, but that isn't the point. The point is that you're putting a sense of structure and hierarchy into place. This can be enormously powerful!

One thing to keep in mind about taxonomies, especially the top level of a taxonomy, is what the taxonomy you've created makes visible and what it hides. Top-level choices are given a great deal of importance and they may be the only level someone ever really

reads or considers before diving into your text or passing on it altogether. You need to calculate what you say very carefully to make sure folks know what to find where and what to expect.

If you've ever tried to evaluate four or give different programs at the college level using the respective programs' websites, you know the pain of awful taxonomy choices. One school might choose to put the major plan under "Advising," while another will put it under "New Students," and another will place it under "Academics." Where you will find it on a given website is anyone's guess since the taxonomy is not regularized (this is one of the reasons the standards we discussed previously can be useful—a taxonomy can be universal) or is simply poorly thought out. In many cases with websites you can get to the information quicker by doing a web search with the terms and the university name than actually diving into the site. This isn't an ideal solution, but it is often one bad taxonomy forces on us. (Card Sorting research is one way to fix this, so take a peak at that section in our last chapter for more).

You may wonder how taxonomy and power interrelate. We are after all just naming categories—why would we care about the top level? Well, it comes down to representation and access. Taxonomies have an implicit power structure. Top level content is all of equal importance. Secondary content is less important than top level content, and in theory it is all of equal importance. If there is a tertiary level, it in theory is less important than the secondary level and all content at that level is ideally of the same importance. This is basically how an outline works with Roman numerals:

I. Topic 1

a. Sub-Topic 1

i. Sub-Sub-Topic 1

b. Sub-Topic 2

II. Topic 3

III. Topic

Because of the weight given to the top level, and it's immediately visibility, it provides a level of prestige that the sub-levels don't have. Think about how this can impact something as simple as an organizational chart. Does a unit deserve to stand alone as part of its own subdivision of the organization, or does it get nested under another unit? These are functional as well as political questions. (Office politics gets really interesting around these issues).

### Ethics and Taxonomy/Signposting

For us, we want to make sure that we're using a taxonomy system that both respects the subject matter and makes content easy to find. Doing both isn't always easy, but if effective communication was something that was relatively easy, everyone would be doing it! Writing and communication classes exist for a reason.

You want to group categories in a way that makes sense to your readers, even if it isn't your natural way to categorize. This sometimes involves research, and we'll cover that later in the text, but it is almost always worth the work. Connect research on how readers classify content with your signposts in the text, sync those road maps up with your document map, and the next thing you know you've got a text that will serve readers well.

Regarding respecting content, you want to make sure that you're treating content with the same level of respect as your readers, and that you're respecting the importance of content when viewing it through an ethical lens. Practically speaking, this often means making sure that you aren't tucking important information that might make your case less persuasive in hard-to-find places. You shouldn't have safety warnings or hidden price tags for projects in places folks are not likely to look or very likely to overlook. Doing so betrays your audience by actively preventing them from accessing the information they would want to see when they are making decisions about your text.

## Wrapping it Up

In short, this chapter has been about the big picture of technical writing. What is it? Why does it matter? What are some of the simple-yet-important things we need to keep in mind when writing texts on technical subject matter? From this point on, we'll be expanding our knowledge in particular areas regarding technical writing. But, we'll rely on this chapter and the content covered to move forward.

---

This page titled [1.3: Signposting and Taxonomy](#) is shared under a [CC BY-SA 4.0](#) license and was authored, remixed, and/or curated by [Adam Rex Pope](#) via [source content](#) that was edited to the style and standards of the LibreTexts platform.

## CHAPTER OVERVIEW

### 2: The User

- 2.0: Introduction
- 2.1: Technical Writing and the Audience
- 2.2: Users and the Drafting Process
- 2.3: Technical Writing Research and Writing Process
- 2.4: Usability, Use, and Participatory Design
- 2.5: Institutional Writing

---

This page titled [2: The User](#) is shared under a [CC BY-SA 4.0](#) license and was authored, remixed, and/or curated by [Adam Rex Pope](#) via [source content](#) that was edited to the style and standards of the LibreTexts platform.

## 2.0: Introduction

---

In the first chapter, we focused a great deal on big-picture questions about what technical writing is, how it works, where it comes from, and spent a bit of time on some solid tips to follow regarding organization. In the second chapter, we're going to move away from looking at technical writing as something the writer/author works on, and instead look at the folks who are actually being served by the technical writing we're doing. We'll start by looking at the idea of audience and use, before focusing specifically on use and questions of use and how users impact our drafting process. Next, we'll look at usability studies and participatory and user-centered design as a way to approach the question of use. After that, we'll talk about sources and research in technical writing and how those relate to our users and their expectations. Finally, we'll talk about writing in large organizations or institutions and how use differs in those cases.

---

This page titled [2.0: Introduction](#) is shared under a [CC BY-SA 4.0](#) license and was authored, remixed, and/or curated by [Adam Rex Pope](#) via [source content](#) that was edited to the style and standards of the LibreTexts platform.

## 2.1: Technical Writing and the Audience

---

### Technical Writing and The Audience

In many ways, the audience or user of technical writing is the most important facet of everything we do (if the first chapter didn't clue you into this fact already). Technical writing is all about conveying complex information to new environments and audiences, and being able to convey information to a new place involves knowing where it will be going and who will be using it there. It is fairly difficult to be an effective technical writer if you don't know who is going to be using your work. The idea that there is some ideal technical writing level that we can all use and understand at the most ideal level is absolutely wrong, as we've discussed before and will discuss again. The audience matters!

Now, you may have noticed that while I'm mentioning audience a lot, the title of this chapter is devoted to users. That may seem like a simple swap, a set of synonyms, but in reality the term user has important implications that audience doesn't always bring along for the ride. When we think about an audience, I would argue that our normal construction is a passive one. There is an audience for a play. There is an audience for a sporting event. There is an audience for a television show. In each of these cases, the audience primarily watches or reads (in the case of closet drama—a play meant to be read rather than acted) a text or event.

Users, however, are not passive. In comparison to an audience, a user is someone doing something. They are going to use whatever it is that they've been given. They're not going to just leisurely stroll through a text—they have a purpose behind their engagement with it. Users use and depending on what they're using, they may have an easy time or a not-so-easy time. For example, one of my best friends is color blind. He uses a lot of video game interfaces as he's playing. Those interfaces are essential to him because he gets information from them to plan his playing. For many years, however, those interfaces have not catered to his ability to see color, and that has caused a great deal of grief for him. Thankfully, more and more modern games cater to users with color blindness and offer different interface color schemes to help users access information clearly using the colors they can see and distinguish between with ease.

As may already be clear, viewing the folks who will be accessing our technical writer as users puts us in a better position to cater to their needs. When we think about users and use, we push ourselves past simply having someone read our text and think about how they might actually use our text to carry out some task or goal. Once we make that leap, we're suddenly asking a lot of really important questions we might not be asking otherwise if we just saw them as an audience. We're asking questions about how our text is going to be used!

Having said all of this, I'm a hopeless waffler when I write about users and use and audience. You'll likely see me using all of these terms and some more in the rest of this text. Unless I'm making a clear usage of a particular facet of one of the definitions, orient all discussions of audience and users around potential use. Hopefully in the future I'll rewrite all of this and remove my waffling from the equation.

---

This page titled [2.1: Technical Writing and the Audience](#) is shared under a [CC BY-SA 4.0](#) license and was authored, remixed, and/or curated by [Adam Rex Pope](#) via [source content](#) that was edited to the style and standards of the LibreTexts platform.

## 2.2: Users and the Drafting Process

---

### Users and the Drafting Process

Now that we've decided that use is going to be important in the way we treat our readers, now we need to dive into how to engage with users as we go through the process of drafting a text. First we'll look at the way that research goes into the drafting process before diving into the questions that we'll use to generate that research on use.

### Research and the Drafting Process

Good technical writing doesn't come from the nether. You don't sit under a tree and wait for inspiration to strike you in order to create that next bit of amazing technical writing. Now, that isn't to say that technical writing is not creative—it is incredibly creative. However, technical writing is not writing that is built off of the writer's fancy. It is writing that is situated around information and users and use.

In the writing process, this means that often your writing will be driven by research and directed by research. When asking yourself how you should write a given section, you won't simply be asking this question out loud and answering yourself with imaginary sequences of events. Instead, you should be basing your decisions in a good technical document based on what you know about the audience and how they plan on using your text.

In order to make use of information about the audience in our drafting process, we need to fundamentally integrate research into the way that we write. Anything less will result in an awful and inefficient process where we write what we think is needed, find out what is really needed, and then go back and try to reconcile the two before our pressing deadline is a missed deadline. In case you don't get the hint, that is not an ideal way to write.

Now, writing can be a very idiosyncratic sort of thing and everyone has a system that they've developed over time to do writing. Often the system is something like, "I'll do it tomorrow," "I'll do it tomorrow," "I'll do it tonight," "I'll do it in an hour," "I'm doing it now and have to beat the midnight deadline." This is a strategy that can sometimes work in college, but it is not conducive to ongoing professional success. Even if you do have a more evolved process of drafting, I would like to suggest a sequence of writing and research that may be useful. You don't have to adopt it entirely, but I'd ask that you at least consider some of the benefits to the approach and think about how it might be adapted to fit your system of writing.

---

This page titled [2.2: Users and the Drafting Process](#) is shared under a [CC BY-SA 4.0](#) license and was authored, remixed, and/or curated by [Adam Rex Pope](#) via [source content](#) that was edited to the style and standards of the LibreTexts platform.

## 2.3: Technical Writing Research and Writing Process

### Technical Writing Research and Writing Process

Below, I'll be discussing what I see as seven phases of the writing process for technical writing. I use the term phases because these are not really steps, but instead ways of viewing the project that you go through. In general, you go through these phases in order. However, you may jump back to the mindset of one phase or another without ever really leaving your current phase. (You might question purpose, for example, while identifying document goals). Or, you might decide once you reach a certain phase that you need to take what you've learned and revert to a previous phase or even the first phase. That might sound horrifying, but some of the best writing comes from those types of responsible decisions. Trust me, if you think it might be best to start over and you don't, someone else is going to eventually see your text and likely come to the exact same conclusion.

#### Writing Project Phases

- Phase 1: Coming to a Purpose
- Phase 2a: Identifying Research Goals
- Phase 2b: Researching Context
- Phase 3a: Identifying Document Goals
- Phase 3b: Implementing Document Goals
- Phase 4: Drafting
- Phase 5a: Editing
- Phase 5b: Testing
- Phase 5c: Revision
- Phase 6: Proofing
- Phase 7: Publication

### Phase 1: Coming to a Purpose

The first phase of a writing task is often coming to a purpose. Sometimes this phase, like all of the phases, can take a long time. Other times, you can get through the entire timeline in the space of a minute or two (such as when you're writing a work email).

What usually controls the direction of the first phase is the origin of your writing task—is this something you want to do or is this something you've been asked to do. If you're being asked to do something, you have much less control over the purpose that you're carrying out. If you're doing something on your own, you're going to be able to craft purpose with a bit more control.

#### Identifying Your Purpose

- What am I doing?
- Who am I doing it for?
- How will they use it?
- What will it be about?
- When will it be used?
- Why am I being asked to do this?

The answer to the above questions will give you a sense of your purpose. You don't always need to know all the answers to the above, and really you just want a sketch of the answers at this point. But, you need to know the general gist of each of these questions to have a clear idea of purpose. Once you've figured these questions out, you should have a clear idea of what you will be doing and who you will be doing it for.

For an example, you might be asked to write a white paper on a new service your company is creating. Below, you'll find the rundown for this project via the questions on purpose:

*What:* I am drafting a white paper, an informational and persuasive text designed to education folks enough to know why they should want a service.

*Who:* I am doing this work for my immediate supervisor, but really this is a service to the entire company and getting new clients helps us keep the doors open.

*How:* The reader should use this paper to understand our service and why it is valuable and worth having.

*What:* It will be about our new service that provides on-site minor medical care for construction firms.

*When:* It will be used in the early part of the sales process. It may be used as a cold-call tool.

*Why:* I am a technical writer and familiar with the program and our sales process, so I am being asked to write this document.

Notice in the example above, most of what I'm writing is coming from the writer's own understanding of things. Understanding your purpose, ideally, shouldn't involve a ton of research. You just need to know the parameters of your project and what is going to be required and what will be recognized as success. These are primarily internal metrics, not external ones. Once you know these things, you can move on to the real work of research in Phase 2.

## Phase 2a: Identifying Research Goals

In Phase 2, we move away from the internal understanding of the project we started with in Phase 1 and expand to understand the project from outside perspectives. We'll also carry out research in this phase, so we'll really be going past simply identifying. In doing all of this, we'll be trying to figure out what we need to know to be effective writers in the situation we're currently in. This phase is a long one, but it is one of the most important steps in good technical writing!

To identify research goals, we need to know what we don't know. I won't go into the full Donald Rumsfeld quote on known-knowns and known-unknowns, but we do need to get a sense of what we need to find out. This is a fairly natural course of events if you think about it—what would be the purpose of research if we already knew what we were going to find out?

To help out in identifying what we need to find out, I like to work through a series of questions. (You may be noticing a pattern at this point). Below, you'll find the first set of questions I often ask:

### Identifying Research Goals

- Who is going to be the primary user of this text?
- Who might they consult when reading this text?
- Who might be interested in this text for secondary reasons?
- What laws and regulations will govern this text?
- Who in my organization is going to control the release of this text?
- What will they expect?

In each of the above questions, we're trying to get at the question of who. We need to figure out the identity of the users of our documents, and we need to know who is going to be assisting them in that use. At first, that might seem like an odd question, but if you examine your own use of important documents as well as workplace practices, it makes more sense.

When you use an important document, you often ask folks that know more about specific parts of that text for assistance. For example, if you're looking over an application for a college, you might ask someone who has applied successfully to that college or another college for assistance in a particularly tricky part. If you're in a business situation and you are reviewing a bid for a new service, you might ask one of your employees or coworkers with expertise in a particular part of the package you don't understand or know much about. In each case, these consultants are not the primary user, but they're using the text nonetheless.

Once you've identified consultants and users, you're going to want to at least consider who might run into this text for secondary reasons. This might be someone who is a competitor—they want to see your text so they can make sure they're staying competitive with your offerings. It might be a news organization that wants to report on your business practices. It might even be an advocacy group that has decided you are their enemy! (For example, you might be building a new shopping development near a historic neighborhood full of folks who simply don't want your traffic in their streets).

The next who you want to identify is the governmental who—which federal, state, and international laws might govern this text? What government agencies might you need to interact with? What will the expect? This question doesn't always come into play, but when it comes into play, it can be of the utmost importance. There is nothing quiet like running afoul of a governmental agency's paperwork demands.

Finally, you're going to want to know who in your organization is going to control this text's release. This might be the person that tasked you with the purpose you're operating under. This might be the legal department. What matters is that you know who they are and what they want. If you've done your homework in assessing Purpose, this may well be the easiest bit of research.

## Phase 2b: Researching Context

Once you've identified all of the relevant who answers, you'll need one more pass to do some actual research. Yep, it's time for another list of questions. For each of your who's, you'll need to answer the following questions:

### Research Context

- What does this user need from the text?
- What will be this user's attitude towards my text?
- What will this user appreciate in my text?
- How will this user's political situation impact their interaction with my text?

In each question, we're going to be trying to find out what exactly we need to know when we're doing our writing of the text. With the question on need, we're trying to figure out what use is going to look like for an individual user. With the question on attitude, we're trying to ascertain how we need to present the information to get a good response. With the question of appreciation, we need to know what will win over a particular user. With the idea of politics, we need to know the internal stakes for each user when working with our text. (Note: when we discuss politics in this text, we're almost always talking about politics in the general sense—what groups exist and how will they respond to our choices? We usually aren't talking about political parties and elections and the like.)

These questions likely make more sense when they're given some context. Below you'll find an example of answering each one of these questions for a primary user in our example of the service white paper:

*Need:* The user will need to know what we offer, how the service is carried out, what the cost of the service will be, the benefits of the service for their business, and the competitive advantage the service will offer them.

*Attitude:* As this will be drafted as a cold-call document, it will likely be met with some skepticism. In order to get past this, we'll need to make the document quite informative for the users and make sure it doesn't come across as a hard sell from page one.

*Appreciation:* The users will appreciate timely and up-to-date research on industry best practices. Anything we can do to make the reader feel like they've got a better appreciation of what is current and cutting edge in the business will be advantageous. If we can do this without coming across as someone after a sale at all costs, we'll likely get a good response, even if we don't get a sale for this service at this time. Building a solid relationship matters.

*Politics:* We will be sending these documents to the owners of the companies we want to address. There will be generally fewer political hang ups over this because they will be the final decision maker. However, there may be some political issues that arise if the employer already has a service provider for healthcare. Additionally, there could be internal pressure from employees or external pressure from governmental agencies to provide better healthcare for employees on the job site, so this may be something we can take advantage of.

For each of your users, you'll want to answer questions just like the example above. As you can see, hopefully, these questions are designed to push you to find out information and to put that information on the page. You can also put these questions on a whiteboard for discussion purposes. Often having generative questions can make group writing more effective because it gives you a way to get the expertise out of each member's head and into the shared discussion space.

## Gathering Research on Users and Context

Before we move further into the phases, we should pause to note that the questions above on the context we're researching are fundamentally different than the internal-facing questions from Phase 1. In Phase 1, we could easily answer questions because they were from our own situation and our own circumstances. In Phase 2, especially in 2b, we're looking at other people's circumstances—that's a totally different animal. You can't just wing it when you're answering questions about other people because you aren't other people. You're you.

To gather information on other people, you need to actually do some research. Some of this research can be research from academic sources and trade publications. Some of it can be from the experiences you've had as well as the experience of others you might be writing with. But, all of that is no substitute for actually interacting with the folks you're going to be writing with!

In the back of this text, you'll find several smaller chapters on research methods. You'll likely need to consult at least one or two of these methods to gather information on the context of your audience/ users. To start off, interviews might be a useful place to begin if you have access to the folks you will be writing for. Read through the various approaches' introductions and you'll get a feel for which might fit your situation best.

After you've carried out your research, you'll be in a much better place to make decisions about your audience and writing for them. You'll be able to ask yourself questions and then have data to answer them instead of relying on suppositions, anecdotes, and hunches.

## Phase 3a: Identifying Document Goals

Once you've identified your research goals and done some research, you'll be ready to move on to the next phase of the writing process, the phase where we turn from users and audience to the structural makeup of our text.

When we talk about document goals, you may be tempted to conflate that with coming to a purpose in Phase 1. While they do sound similar, the focus in Phase 3 is on the actual document—the key features of the text and the expectations that readers will have for it. The difference here is that we're looking at the ways that the actual document, its features and its structure and appearance, helps meet our purpose and satisfy the expectations of our audience. Again, they sound similar but have an altogether different focus.

Document goals come in a couple of forms, each with their own focus and point of view. Some goals are focused on the document's genre—what kind of document is this supposed to be, and what does that kind of document look like? Others are focused on the way the document's structure will be oriented to meet the purpose of the text and the audience's needs and expectations. Taken together, all of these goals help us plan out the drafting of our text to make sure we're as effective as possible in our writing efforts.

### Identifying Document Goals

- What genre will the document be?
- What topics will the document need to cover/convey?
- What types of information will need to be highlighted?
- What accommodations will be needed?

Each of the questions for this phase focus on identifying key aspects of our text's structure and content that will need to be researched to gain a clear understanding of what will be required. Some of this research can be internal, and some may be external.

## Document Genre

For the question of document genre, you will need to look to your internal and external expectations. This may be a fairly simple step—your purpose may explicitly discuss what genre will be required. If not, you'll need to do some primary research. Look for similar documents in the professional world that carry out the same goal as yours. What genre are the documents? Are they all the same? Are they different? Identify one genre that you feel would best fit your current goals, or make a mashup that meets your own internal goals.

For the question of document genre, you will need to look to your internal and external expectations. This may be a fairly simple step—your purpose may explicitly discuss what genre will be required. If not, you’ll need to do some primary research. Look for similar documents in the professional world that carry out the same goal as yours. What genre are the documents? Are they all the same? Are they different? Identify one genre that you feel would best fit your current goals, or make a mashup that meets your own internal goals.

One example might be the police procedural television show. In these shows, the audience follows along with police officers as they go about their daily work. Not all of these are framed the same way of course, and older shows like *Dragnet* maintain a focus just on the cases, whereas newer shows may focus more on the people doing the policing and their lives, sometimes even with some comedy added in with shows like *Castle* or *Brooklyn 99*. In each case, there are certain hallmarks that are echoed by each show that places the show within the procedural genre. That doesn’t mean that there are hard and fast rules that must be followed—genres change all the time—but, there are expectations that must be met or at least addressed.

Document genres work the same way. When you think about annual reports, tax returns, grant proposals, or even memos, each of these texts play by a certain set of genre rules and expectations. Often you can see similarities between the function of genre examples taken from any number of places, even if the specifics of how the genre works will be tailored to a specific audience and organization.

Fundamentally, document genres (and others really) represent an approach to working with a given text. A genre is the way that a textual problem has been solved. If the solution was effective, it was likely repeated. As time went by, the solution was tweaked to meet challenges the original approach didn’t address. The genre continues onward as a way to meet a challenge until it faces one that it simply can’t address. At that point the genre is either retired or fundamentally overhauled to meet the new situation.

To research genre, you should first look to your purpose. Is there an already present genre in your organization you’ve been asked to create a text within? If you already have a standard format for something like an annual report, use that. You should never go searching for a new genre or a new approach simply because you’re making a new text. Unless the genre is no longer solving the problem, keep it as-is. Otherwise, you spend valuable time you could be writing your document trying to come up with a new approach when none is needed.

If you don’t have an in-house genre, you need to create one. Look at example documents that are doing the same thing your document is doing. What structural choices are present? What kind of language is used (informal vs formal)? Take notes about all of this and sketch out your own model based on the examples. It will be a bit shaky on the first go, but that’s what happens anytime you create a new approach to a technical writing task. This is why versioning and revisions exist.

### Topics and Audience

Once you’ve got an idea of genre, you need to think about the topics you need to cover. Look at the purpose of your text and look at your audience and their context. What will you need to cover in order to complete your purpose and satisfy your audience?

For example, if you’re being asked to write a series of instructions on how to upload video content to the web for grade schoolers, you will approach this much differently than if you were writing the same content for a retirement community looking to get their members more engaged with social media. In the first example, fundamental questions about video, the web, and social media wouldn’t need to be addressed. Kids get those things. However, the elderly members of the retirement community may not have a firm grasp of how the web works, how video hosting on the web works, and they may even distrust computers! With that said, both groups would likely benefit from a robust set of tips on privacy, so that isn’t to say each group is totally different.

Make a list of your topics and try to make a note next to each item explaining what you mean and why you think that topic needs to be included. You may think this level of documentation is silly (and it would be for something like a three-sentence email to arrange for your friend to meet you for lunch), but being able to look back and explain to your superiors why you’ve made the choices you did in a document based on research and evidence can be a powerful tool when your choices are called into question or someone wants to know why your work is so successful.

### Thinking About Types of Information

We we ask about types of information, we’re really thinking about formatting. What types of information in your text will need to have custom formatting? Will there be keywords? Will there be warnings? Will there be cautions? Will there be movies and books

listed? Will you be using non-standard characters a lot, such as names in Arabic or Japanese? Each of these questions is a formatting question.

You'll want to make a list of each of the types of information that will have a special format. If you want to be exhaustive, you could even include numbers and symbols associated with chemical formulas or mathematical equations. The goal here is to have a handle on what will be represented in the text.

Once you have a list of these types of information, sketch out what your formatting for each will be briefly. Will caution be yellow? Will warnings be red? Will formulas be inline or separate from text? Sketch out those answers now. If you're not sure, do some research. Look at how others have presented the same data in their texts. If you have an internal style guide, use it. If you have a normal way of doing this in your own organization, use that. Otherwise, do the research and make your notes!

### Thinking about Accommodations

When we think about accommodations, we're trying to identify alterations to the text that will be necessary to make sure our users will be able to use it without unnecessary burdens being placed on them. When we think about accommodations, you'll be thinking about things like the following list:

- Do we have users with special color needs for color-coding?
- Do we have users that will access the text via a screen-reader that will require image captions?
- Do we have users that will need the text translated into another language?
- Do we have users that will need the text written to a specific reading level?

These questions and others will help you identify any accommodations you might need to make.

Your goal here is to make sure you know any sort of need that will have to be addressed by your or your organization as you write. In some cases, you will have an office in the organization that handles this type of content. In the US, this type of content usually falls under Section 508 rules and regulations when dealing with government agencies. Other countries and organizations may differ in their approaches.

By approaching accommodations early in the writing process, you'll be in a better position to ensure your text will serve its audience well, regardless of the way they'll be reading it.

### Phase 3b: Implementing Document Goals

Once we've identified document goals, we need to do some research and planning to get those goals ready to draft. We need to explicitly identify what genre means for us in this context, we need to connect our list of topics with a series of sections in the text, and we need to create a miniature style guide for any special information and accommodations that will be needed.

#### Genre Requirements for Drafting

First, we need to explicitly write down how the genre of our text will work. This usually involves two steps: identifying the specific sections that will be needed, and identifying the voice used in the text. For the specific sections, we'll need to identify what sections are expected in our genre. Next, we'll need to make sure we have a consistent voice throughout—this may be casual, formal, or something in between.

For example, if we're going to be working on an annual report, there may be some expected sections that will be present. Now, we're not getting to the point of topics and sub-topics here, but we need to know about major segments of the text. For an annual report, there may need to be a special executive summary that will be present. Knowing that needs to be in the text helps us plan our writing task. There might also be an expectation of appendices with hard data included. Knowing that helps us make sure the document meets the expectations given by the genre.

When it comes to voice, we just need to make sure we know what voice we're using. This can be the start of our mini style guide. Simply describe the voice and how it should work. Will it be formal with no contractions? Will it be informal with a lot of "you" and other direct address use? Will it be silly? Jot down your goals and then use this later as a rubric for your own writing. This type of work is especially useful when you're working in a team environment where several writers need to use the same voice to write sections that will be combined into one larger document.

## Setting up Topics and Sections

Next, you'll want to connect your topics that need to be covered with specific sections for the document. You'll want to sketch out the major sections and then map your content to each area. You'll rely on your research on the audience as well as your purpose here to craft a table of contents for your text.

This will be a rough outline of the text and may look something like the list below:

### I. Introduction

- i. Salutation to readers (familiar customer for 10 years)
- ii. Background on project (reworking of a project by other contractor)
- iii. Description of rest of text

### II. Project Approach

- i. Previous work (Current CEO ordered this work)
- ii. Current method (Focus on environmental factors)

### III. Project Staff

- i. Leadership structure (Emphasize experience)
- ii. Team member bios (Structure around leads)

### IV. Project Timeline

- i. Overall timeline (Focus on Earth Day deadline)
- ii. Possible delays and challenges (Highlight variables)

### V. Goals and Outcomes

- i. Overall project goals (Connect with ongoing relationship and with ongoing relationship and environment)
- ii. Rubric for measuring success (Use contract for detailed specifics)

### VI. Closing (Personal thanks and contact information)

In the above example, I've sketched out a potential structure for a project report that might be given to a client at the outset of the project, presenting the reader with a simplified and accessible version of the existing technical plans that emphasizes the why of what will be going on. In each case in parenthesis are some notes that will be useful regarding the audience and the writing. For example, when talking about previous work, there is a note that the current CEO ordered the infrastructure being replaced. Knowing this, we would want to be rather gentle with our critiques of what is currently being done—there is no reason to throw our client under the bus, especially when that can make the boss look bad to an entire organization.

In your own work, you may want to follow a structure like the above, or you might try something altogether different. What matters is that you come up with a structure for the text that covers all the content you've identified as necessary while creating sections that make sense within the genre you're drafting, sections that will help this text meet your stated purpose. We're trying to put all the stuff we now know into a plan that we can use for the actual writing work ahead of us.

## Style and Accommodations

Last, you'll want to come up with a mini style guide addition that covers any content that needs special formatting or accommodation. A style guide for our purposes is really just a list of things that should be done in the document to maintain consistency. It doesn't have to be complicated, but it does need to be clear and accessible those doing writing and editing. We'll get into this in much more detail later when we talk about project management in a later chapter.

Think about the style guide as the place you go to answer any questions regarding how something should look. When someone is writing a warning, the style guide should give them instructions on how that should be formatted. When someone is including an image, the style guide should list any special instructions for accommodations. The text will work as a reference for your writing, and a living one at that.

Style guides can and do grow over time. Anytime you have to spend more than a moment deciding what something should look like, make a new entry in your style guide. By doing this consistently, you'll make sure you have a record of the choices you're making and an explanation of those choices. In a group situation, this allows you to hash out your approach once and then maintain it consistently across multiple authors and perhaps even multiple documents. In the world of coding, you often see a similar documentation alongside code, but also within code in the form of explanatory comments. In all of the situations above, you're trying to remain consistent and help future you remember what past you wanted done.

The style guide can be fairly simple, as you see in the below example:

#### *Style Guide for Green Infrastructure Project*

*Voice:* The overall voice of this document should be formal, though contractions will be allowed. Formal titles, names, and address should be used throughout

*Major Sections:* Each major section should be in Impact font, 14pt, bold. The color for each major section should be green (color code should be decided by end of project)

*Sub-Sections:* Sub-sections should have titles in 12pt Times New Roman and should use italics. The color should be standard black.

*Images:* All images should include descriptive captions that will be screen-reader accessible.

#### *Revision Log for Style Guide:*

Version 1.0 Original style guide added

Version 1.1 Image caption guidelines stipulated to accommodate screen readers as client has several members of team that will be using these devices.

Again, the style guide doesn't have to be too terribly complicated, but it should be a place you can go to make sure you're addressing document issues consistently throughout your writing. Making a decision once and then referring back to it makes life simpler.

## Phase 4: Drafting

Though you might have wondered if we'd ever get here, we're now at the phase of writing where the actual document comes into shape—drafting. The drafting phase is the most important phase in that this phase actually creates your text, but it can only be successful if it is built upon a firm foundation of research from the previous phases. (And yes, this is even true of short emails with an abbreviated version of the process).

When drafting, you'll be taking your style guide and section outline and fleshing out the content you'll be creating. In each section, you'll want to draft a text based on your guidelines and your audience research. When you wonder how to approach a particular subject, think back to your research on audience and purpose and genre. Any choices you make should be, whenever possible, grounded in research and tied to your users.

When drafting, I find it is often helpful to skip the introduction of your text and to move directly into the body. An introduction is designed to introduce a text, but that is fairly difficult if no text exists. By skipping your introduction and moving into your body you are able to get going on content you can actually create without needing to know the entire document's content. Once you've finished the text, go back and introduce it. It may seem counter-intuitive, but it helps quite a bit.

As you go, think a bit about how you're saving your text and how it is accessible. You'll likely want to have at least one backup of your text, and you may even want to save versions as you go. This will allow you to revert to an older copy or an earlier point in the process if you realize you've gone in the wrong direction or realize an earlier draft of a section was better than the current one. Saving your text can also be useful when accidents happen. If you lose the device with your text, accidentally delete your current draft, or have a file that gets corrupted, backups make things much less stressful.

## Collaborative Drafting

You'll also want to think about making your text accessible to any collaborators. I won't go through the trouble of advocating for any particular type of solution to share with your collaborators—these services change and morph all the time. But, I will say that it

is ideal to use some platform that hosts files with synchronized updates when you're doing a lot of work on the same document at once.

If you and your team need to be in the same text at the same time, use a platform that will host the file natively—a platform that lets you edit in browser in real time. If you just need to have the files available, you can use different options that will sync up as you need them to.

Above all, don't use email! Nothing in life is worse than trying to reconcile multiple files and multiple versions of a text into a final document from a chain of emails. Emailing files leads to poor communication in highly collaborative texts. If you're editing, it's not a big deal. If you're actively drafting, it can ruin your text, or at least your life for the duration of the project.

Finally, as you draft collaboratively, think about voice and tone. Make sure you've all got the same supporting documentation to draw on. Make sure that you all have an idea of what the text is supposed to sound like and how it is supposed to relate to the audience and subject. Life is not fun when you get a text with two to four authors and each author has written with a different tone and vocabulary. At the end of that process you're either rewriting the word choices or putting together a series of texts that simply don't belong together. Neither is fun. Create a style guide. Use the style guide. Love the style guide.

## Phase 5: Editing and Revision

Alright, so you've finished your text. Congratulations. Next, you need to make some decisions based on your goals, timeline, and resources. You may wonder why editing comes first as you gaze at this list, as editing is normally treated as a secondary/final concern—you don't edit something you are going to revise heavily. It all comes down to the decision you'll make based on the three topics I mentioned at the start of this paragraph: goals, timeline, and resources.

### Goals

In some cases, you will want to immediately jump into editing a text when it is finished. Why? Your goal may be to get the text out the door quickly and to respond to a pressing request. This would be a useful workflow if you're writing an email reply to an important client or member of your organization. You need to get information back quickly in this case, so editing immediately makes sense. You aren't going to spend too much time on this text because, frankly, it isn't a major document.

Think about the level of importance of your text—is your goal a simple response or a durable document that will withstand continued scrutiny and use. Some documents just aren't worth as much time as others. That may feel a bit sacrilegious in a writing course, but it is true. If I'm texting someone a quick reply, it is nowhere near as important as a formal assessment document for a graduate program I might be writing the same day. As such, I should set my goals accordingly.

### Timeline

Another item to consider is the timeline you need to meet. Sometimes, you simply don't have a lot of time. In those cases, you may need to jump directly into editing. In those types of situations, I recommend focusing much of your time on the first two pages. Most readers are going to set their mental image of your in the first few pages; if you have a ton of errors in that space, they are not going to like you very much. However, if your first two pages (or first page even) are immaculate, then you're going to get a less critical reader that will forgive more later in the text. In short, you don't want to trip the "gotcha" response in your reader. If you start out with tons of errors, then it almost becomes a game to find more. If you start out flawlessly, the text becomes a narrative rather than something to be read critically while looking for errors.

In situations where you have ample amounts of time, do not edit first. To do so would be a colossal waste of resources and time. Editing is hard work and it takes a lot of focus and time. You don't want to spend an hour editing three pages that get deleted from the final text or entirely rewritten after testing. If you have more time than a few moments, save editing for last!

### Resources

A final consideration is resources. You may note that in the middle of the next section is a testing phase. Testing is an ideal step in any technical document that will be used. There is almost always a gap between what happens in the writer's head and what happens when the text is used. Sometimes that is a gap that has been created because the author is so familiar with a process they skipped a step. Sometimes it is simply a mismatch in terminology between an interface and a document. In any case, testing is very useful. But, it is not always something you have resources for.

Testing really can run a spectrum, something we'll talk about later and in the final segment of this text with research method, but sometimes there just aren't any resources to carry out testing. That may be because of budgets or timelines, but it can also be due to institutional views of the writing process. Some organizations simply don't have testing on their radar as something that is done in technical writing.

In cases where testing is not feasible, go through the text as closely as you can. Think about how accurate the text will be for its intended use. Read the text aloud if at all possible—this catches more errors than you'd realize because of the way we read texts of our own creation. Once this is done, move along to revision or editing, depending on your timeline and goals.

## Phase 5a: Editing

Editing, as we discussed previously, is going to be your last phase in virtually any writing context. Even when you briefly look over a text before you send it, you are in essence editing. But, it comes first in this list because many times when you are writing you will simply stop here. There won't be time or need for testing or revision. And, as we discussed—that is okay.

When we talk about editing, we usually think about two types of editing—copyediting and comprehensive editing. In some situations, you'll just do copyediting. In other cases, you'll be doing comprehensive editing that goes much further. Think about your goals, timeline, and resources when you make this choice.

### Copyediting

Copyediting is simply looking for issues in the text related to grammar, structure, and content. Does the text do what it says it will? Do the sections come in the correct order? Are terms used consistently? Is structure consistent? Is the grammar okay? Is the spelling consistent and regionally-situated?

In copyediting, you are looking at the text as a finalized document that needs some checking on the textual level. In a fast-paced environment, this is a quick glance. In a slow-paced environment, this may extend to checking terms in a style guide for consistency with institutional norms and spellings. (For example, if you have British and American clients, you need to standardize color or colour). As in everything, think about your goals, timeline, and resources.

When carrying out copyediting, you want to ask the following questions of the document before assessing the document via these questions' answers:

#### Copyediting Question

- What does the document say it does?
- What sections does the document say it contains?
- What is the voice of the document?
- How is the first section formatted?

Once you have these answers, you can then assess the text. I recommend you move through the questions in the order listed above using the answers you've generated as a standard for testing.

For example, if the document says it will teach you how to true a bicycle wheel, does it actually do that? Can you understand the process by reading through the text? If not, you need to revise accordingly. In cases where you are the author, this is simple. In cases where you are simply an editor, pass it back to the author with instructions on what to add.

As another example, the text might reference an appendix that includes a conversion chart for converting dosing from milliliters to teaspoons. Does the text actually have that appendix? If it doesn't, that calls for revision as well. (Or maybe just locating the lost file).

With something like voice or formatting or term use, you want to go by the start of the text versus the rest. (This is based on the assumption the author at least got the first bit the way they intended—that isn't always true, but it can be a good strategy). If the document starts incredibly formal and then swaps randomly in one section to being informal, that requires revision. If the text has blue headings for the first half, it doesn't need to suddenly swap to green with no reason,. The same goes for calling a process by

one name and then swapping to another. In technical writing, there is no real need for creative re-naming. Consistency and intelligibility are more important than keeping things fresh and new.

### Comprehensive Editing

Comprehensive editing is much more involved than copyediting—make sure you have time and resources and it meets your goals. In addition, make sure you do the comprehensive work before you copyedit! Just like with editing as a whole, copyediting is listed first because many times that will be where you stop due to limits in time, resources, or a mismatch of goals with the process.

Instead of looking at the details, comprehensive editing looks at the big picture. Does the document stand together? Does the order of the text make sense? Is the correct audience being targeted here? Should the current sections stay in the text, or should something be added or removed? All of these questions are fair game!

With comprehensive editing, you want to query the document based on the purpose and audience.

This can be as wide ranging or as narrow as you have time/desire for. The following questions can be useful in this process:

#### Comprehensive Editing Questions

- Who is the primary audience?
- How will their context impact their reading of the text?
- Who might be a consulting audience?
- What aspects of the text might need to be tailored to them?
- What is the purpose of this text?
- How does this text fit with other texts in the organization/genre?

Once you have these answers, you can start to comprehensively edit the text. Using these answers, you have a rubric for grading the text's content, formatting, and style.

To narrow comprehensive editing to something that fits within this sub-section of the book—I teach an entire course on editing—you can follow the following steps as you go through a comprehensive editing:

1. Check to make sure the text has everything the audience is going to need. If the audience is made up of novices, make sure the text has ample explanation of technical terms. If the audience may need additional resources that will be hard to find, provide them for the audience
2. Make sure the text is appropriately ordered to carry out the task at hand. Sometimes when we write texts, we don't always write in the best order for use. Think about the way the text develops. Does it build from one section to another? Does one section later in the text need to be earlier for a section to make sense? If so, consider moving it!
3. Analyze the voice of the text—does it make sense for the subject and audience? Think about who your audience is and what they will think about your subject. Is the choice of voice appropriate? If you have a skeptical audience, you likely don't want to have a super-excited voice that doesn't critically engage with your subject matter. On the other hand, if your audience already agrees with you fully, it wouldn't make sense to be skeptical of everything.
4. If the text has multiple types of users, make sure they can stay in their lanes. Sometimes, a text will have a variety of users that will have different skill levels. In those cases, you need to be wary of how the text is formatted for their use. For example, if you have expert users that know terms and processes, you won't want to label each and every step and process—your expert users will get exasperated quickly. Instead, think about how you can signal that content is for new users. With instructions, you might have a bold, simple instruction for each step of a process that caters to advanced users or those referencing the text. Under that bold text, you can include normal formatting in paragraph form or just a few sentences that explains what the step means in detail for those who are learning for the first time. Pretty meta, huh?

Once you are done with copyediting, you'll want to revise. If you have time, editing again can be useful, though at some point you'll want to switch from comprehensive to copyediting. You can continually comprehensively edit a text forever. Find a stopping place that honors your goals, timeline, and resources.

## Phase 5b: Testing

Testing is the middle step of our process, though if you have a great deal of time, it may well be the first one—it depends on your purpose and audience for testing. Testing can have different permutations depending on your resources and timeline. You might simply do internal testing with folks in your organization testing out your work. Alternatively, you could actively recruit testers in the generic sense to go over your text. Or, you could get the actual users that will use your text to test it—and those could be internal or external, depending on what you're writing.

If you are simply passing something along for internal testing, it is more likely that you might send it directly to testers after drafting, or perhaps after a quick edit. With internal testers, you don't have to be as concerned with the polish and finish as you might with external testers—they won't be judging your organization based on this text. However, in some cases where the politics of internal testing are fraught (such as cases where the testers see all of this work as silly), you may want to make sure the text is exceptionally polished.

With external testers, you're going to be either finding folks that fit a generic profile of users or you'll be finding the actual users to test with. In each case, you'll want to make sure the text is polished and doesn't reflect badly on your organization. With a generic profile, you'll just want to find folks that will fit a certain set of parameters to test your text. These may be individuals with similar age ranges or skill levels as your users. Or, it could just be the general public. With actual users, something we'll cover later in this chapter in more detail, you'll be working with the folks who would be using your text to make sure it works as intended.

Testers can be paid or unpaid, but in each case you need to treat their time and experience as valuable. If you pass along a text riddled with errors that looks like a joke, you're going to be wasting your time and theirs. If you go through the trouble of testing a text with outside users, at least make sure you have a polished text!

### Goals of Testing

When you're doing testing, you're asking folks to use texts as they are intended; in the process of using them, you're hoping to find problems with the text. You might find that there are terms that are unclear to the average user. You might find an important step is mislabeled or omitted entirely. In each case, you're trying to figure out what happens when your text actually gets used the way it would after it leaves your desk. It may seem like overkill, especially since you're reading this text in a college classroom environment, but testing can save you and your organization time, money, and reputation losses associated with sending an awful text out into the world that simply is not fit for use, or in a worst-case scenario, dangerous.

Later in this chapter, and in the end of the text, we'll get into the specifics of testing. For now, here is a general workflow you can use for testing:

#### Testing Workflow

- Identify what you want to learn from testing
- Find users that will be testing your text
- Have the users make use of the text in ways that will help you learn what you want
- Record or observe this use, or have the users self-report

Take your findings into the revision process or editing process, depending on the changes needed

With the above workflow, you can get a rough idea of how you can update a text to better fit the intended workflow it will be part of. Later, we'll dive into this with considerably more detail with specific research methods.

## Phase 5c: Revision

So, it has come to this. For many writers, revision is a bad word. Revision is failure to launch, failure to generate a good text the first time. Nothing could be further than the truth. Revision is central to the production of great writing—almost no one gets it right the first time. In fact, many of the most trusted types of texts, such as peer-reviewed academic work or works published by major presses, are produced in environments that are designed to lead to revision and reflection by the author!

Now, as a note—revision and editing are different in this text, and in general practice. Revision often happens when an author reflects on a text. Editing usually happens when an outsider or a non-author reflects on the text. Sometimes revision will incorporate the suggestions of an editor and will be guided by reviewer feedback. Other times, it is self-contained.

When it comes to revision, you can think about it on two levels: global and local revision. Global revision comes first and involves looking at the big picture of your text; in many ways, it is the author’s side of comprehensive editing. With global revision, you move paragraphs, you check to see if topic sentences are supported by the rest of a paragraph, you delete content or add content as needed. With local revision, you focus on small-scale stuff. Does this sentence sound right? Is this the correct word? How can I fix this comma splice?

For carrying out revision, you want to first make sure you have ample time to actually revise, and you need to make sure you’re doing it right. In regards to time, if you are pressed for time, you likely will need to focus more on local revision—large-scale changes to a text can create large-scale problems. If you don’t think you have time for a total overhaul, don’t half-overhaul. Focus on fixing what is there rather than altering it dramatically. If you do have time, focus on global before local. As with comprehensive and copyediting, you don’t want to fix something small that will be deleted later because the larger component it is part of has been removed from your text.

Much of the work of revision maps on top of the work of editing—usually revision and editing are separate parts of a process. Editing identifies the issues, and revision fixes them. (Every editor varies in how much work they do and how much the author does. At the least in modern workflows you’ll have to approve changes in your text). In the case of a single author, you often do both at the same time. Your global revision and comprehensive editing are one and the same. In larger organizations, this is broken up into individual roles with different folks doing different parts of the work.

Carrying out revision effectively takes practice—you learn how to best respond to your own writing by responding to your own writing. There isn’t one workflow that works best, but below I’ll provide some checklists for global and local revision to give you a starting point. Not all of these suggestions will fit every situation, but consider them a good starting point that you can adapt to your own writing. (For example, you might notice after a while that you tend to create a lot of extra “is” formulations where instead of saying “this takes practice,” you say “this is something that takes practice.” In cases like that, you’ll want to focus on finding these “is” formulations because you know that is your kryptonite).

#### Global Revision Checklist

- Is there a document map?
- Do the major sections follow the plan of the document map?
- Are there sections that shouldn’t be in the document?
- Does each paragraph have a topic sentence?
- Does the rest of the paragraph match up with these topic sentences?

In the above checklist, you focus almost entirely on how the document and paragraphs are structured. The idea is that the document map is your starting point—it tells you what should be in the text and the order that those things should be in. You’ll then audit the rest of the text based on that map before descending to the paragraph level and treating each paragraph’s topic sentence as a document map for that paragraph, auditing each paragraph’s sentences to make sure they fit with that text’s purpose. You can add in some of the extra checklist items from comprehensive editing if you’d like to make this more thorough.

#### Local Revision Checklist

- If you have time, read the document aloud.
- If you are pressed for time, read the first page aloud
- Search for errors you know that you often make
- Double-check terms that are important for the text

- Work on re-writing sections (important ones especially) that you feel have poor flow or read badly

In the second checklist, you're focusing almost entirely on small-scale issues. Reading the document aloud is central to effective local editing (and copyediting many times), because it forces you to actually read each work. Often times when we read, we skim without realizing it. When we read our own work, we tend to both skim and edit the text as we read; we read what we meant rather than what it says. Reading aloud gets around both of these issues and helps with the problem most of us face— we can't stand reading our own work. You can also have your word processor read to you, but I find reading aloud keeps you more focused and able to catch errors

## Phase 6: Proofing

Proofing is a phase of the writing process that many guides and writers overlook, but it can be the most important one when it comes to costly mistakes and embarrassing errors. You'll sometimes see it called proofreading. Proofing involves the creation of proofs—samples of your final document with all of the production choices and text choices put into the form they will have in publication.

Proofing is valuable because it can catch errors that won't show up in the drafting process alone. For example, you might think that a certain color combination looks great with a certain type of paper when you're drafting, but when you actually get the printed proof, it looks awful and the colors clash. Or, you might have accidentally used an RGB color code when you should have used CMYK and your text or document has colors that are nothing like what you expected and planned for. Or, you might realize that a choice of font size or style simply doesn't allow for easy reading when placed into a real-world document. Proofing helps you catch these errors before you've paid for an entire run of a document.

In college writing, proofing is not something you run into that much. Most of your writing in classes is often in an office-style program that will go to your professor. Most technical writing, however, goes to outside audiences that will be using your texts. Whereas proofing doesn't usually make sense in college settings because you rarely get something professionally printed and put together, it is a must in professional settings.

Proofing can be very project-dependent, but a few suggestions can help when you're looking over a proof. We will cover proofing again when we discuss the production process later in the text.

### Proofing Checklist

- Do all of the images look correctly colored and free of pixelation?
- Are all fonts correct or have some fonts been substituted for incorrect ones?
- Are the colors accurate?
- Is the paper correct?
- Is all content on the page, or is some content cut off due to being too close to the binding or too close to the edge of the document (the bleed region)?
- Can the document be read easily
- Are there any errors in formatting or spelling or grammar?

By following through with proofing after final revision, you can catch some last-minute errors and mismatches between what you hoped to find when you created your document and what you find in front of you. Again, proofing is about saving you money and embarrassment—you don't want to print a run of hundreds or thousands of pages with really awkward and obvious errors throughout. Even the best editor will miss some errors—proofing gives you a chance to catch and replace those before you pay money to get them printed and sent out to your users.

If you want to take things to the next level, you can do some proofreading as well. Proofreading as part of the editing process involves taking the last version of the text that was editing and reading through it and the final proof concurrently, looking for situations where changes that should have been made didn't make it into the final document.

## Phase 7: Publication

Congratulations—you did it. Publication is the final phase of the writing process, a process you may have thought would never end in this text. With publication, you are confident in your text and your proof and you're ready to send it out to the world. Often publication is a matter of logistics and delivery—you want to make sure the write amount of documents get out to the right people at the right time. We'll cover publication more in Chapter 6.

For publication, you have a fairly simple checklist:

### Publication Checklist

- How many copies do I need?
- Who needs a copy of the text?
- When do they need it?

Once you've made sure you've got your bases covered, the writing process for your document is over! Congrats—it got published.

---

This page titled [2.3: Technical Writing Research and Writing Process](#) is shared under a [CC BY-SA 4.0](#) license and was authored, remixed, and/or curated by [Adam Rex Pope](#) via [source content](#) that was edited to the style and standards of the LibreTexts platform.

## 2.4: Usability, Use, and Participatory Design

---

### Usability, Use, and Participatory Design

Having looked at the writing process and the way it relates to use and users, we're now ready to tackle a much broader topic—usability, user-centered design, and participatory design. While the writing process we've looked at is a fairly simple conception of the interaction between the user and the author, this section will dive into a much more hands-on approach that we can and often should use to make sure our work is going to match up with the needs of actual users. We have so much we can learn from our users: they are the world's foremost experts on the tasks they carry out on a daily basis.

### Usability as an Approach to Writing and Design

Usability is entirely oriented around use—how easy to use is a device or a system or a building or a text? Does it allow different types of use? Does it guide users to use it correctly? Is it open to users with different accessibility issues? All of this and more come into usability, though the term gets thrown around today in ways that more often than not imply a sleek design rather than a usable one.

For us, usability and user-centered design come down to putting users and use before production-oriented concerns. This isn't always possible to the extent we'd like, but it is an ideal that we should continually strive towards. After all, our documents are supposed to be used and should be designed around that use rather than their production.

What does production-centered design look like, and how is user-centered design different? Production-centered design is a design process where we write or design a document in a way that makes things as simple as possible for us, the person doing the writing, or our organization, the group putting the writing out into the world. What is easy for you is not always easy for users. Sometimes there are legitimate production-centered issues that impact users, such as two-factor authentication that makes logging into a service much safer, but also more of a hassle. However, most production-centered issues come to placing the author before the user.

For example, you might use your own terms or disciplinary terms in a document that is meant for the general public. Production-centered design focuses on getting the text out the door with the most efficient and writer-centered choice available. Often, that choice is simply keeping complex terms. After all, if someone really wants to understand what is going on they'll do the research. Right? Unfortunately, internal or disciplinary terms can be an insurmountable barrier to some, or may turn some readers off a text entirely. Think about water quality reports and ingredient lists on packages— if you don't understand what the words mean, you've got to do a lot of digging to figure them out, and even if you figure them out, you may not know what the associated text means for you. Should I be worried about turbidity or anhydrous dextrose? Production-centered design leaves that question up to me and the Internet. That's an awful combination.

User-centered design takes a different tack entirely. It asks what the reader needs from a text to make use of it effectively, often couching that question in actual research with users in the manner that we've discussed previously. While this is more work, it often results in documents that are more effective and users that are much more fond of your organization and your work. While many organizations talk about usability as part of their workflow, not very many actually go through the trouble of making their work user-centered as opposed to production-centered with some lip service to users at the tail end of the development process. You can think about user-centered design as a competitive advantage!

What does usability as an approach look like? We can visualize it with a simple comparison of the two different approaches as competing workflows:

#### Production-Centered Design

1. Assess purpose
2. Draft Document
3. Edit Document
4. Test Document with users (optional)
5. Revise document lightly
6. Publish

## User-Centered Design

1. Assess Purpose Internally
2. Assess Purpose with users
3. Finalize purpose weighing internal and external factors
4. Draft document
5. Edit document
6. Test document with users
7. Revise document as heavily as needed
8. Publish

In the two cases, the difference is how quickly the user is consulted and how aggressive that consultation is. The two permutations above are aggressively different, though user-centered design can operate on a spectrum between highly involved and lightly involved. The main difference is that users are taken into account from the start. At the extremes of production-centered design, users are an afterthought at best. They are simply the people that make the document or system work, and the document or system's effective circulation/operation is the most important consideration.

Now, sometimes we do have more production-oriented designs for special reasons such as security. If you are writing documents that contain highly sensitive documentation, you may have a more production-centered workflow that doesn't let you open up your text to users as much. Why? Because things that would make the document easier for users would also comprise the security of the workflow. Sometimes we pay a price in ease of use for added security in technical writing settings. With that said, a good technical writer goes to great lengths to minimize the impact on readers in such situations.

The drafting process we sketched out earlier in this chapter you may note is closer to the production-centered design end of the spectrum than the example above because purpose is primarily seen as being an internal matter. Practically speaking, this is a concession to political realities—you often are not given enough time and space to assess purpose with your users and your organization. In an ideal world though, that is part and parcel of the design process. Note that you could easily add external users to our process from earlier and make your process instantly more user-centered.

## Participatory Design

At the extreme end of the user-centered design world is what is known as participatory design— design where the user is a participant from the get-go, much like the example we just finished discussing. This kind of work is hard, but the benefits can be immense. The major difference between user-centered and participatory design is agency. Participatory design gives the user agency and control over the design process rather than simply consulting them for more data to help make decisions about the writing process.

When it comes to letting users into the process of drafting a text at the start (and giving them agency), things can get tricky matter. There are ethical concerns—users might criticize their boss and their boss might find out! There are also logistical concerns—how do you end up getting good information from folks and getting them together with designers? And, there are political and financial concerns—how do you convince your organization to let users help you think through things and spend time that could be used drafting to communicate (and possibly compensate) your readers?

With that said, participatory design can be a huge boon for your organization because your readers and users know more about what they need and want than anyone out there! Often times when users work, they work around bad workflows and bad documentation. How many times have you seen in a professional environment a situation where a document or piece of software is lightly used or misused? Think about a clinical setting where someone is putting information into a client management software system—many times huge sections of the system are skipped because they simply don't fit the need of the office, but the software wasn't customized to those needs so they are there anyway. How many times have you been handed a form and someone tells you, “don't worry about that—we never use it!”? In each of these cases you have documents being misused because they don't fit actual workflows or they impede them.

By taking what users know about how things actually work and what they actually need, you can make a better document, build a better experience for users, and make everyone happier in the process ideally. You can remove content that isn't going to be needed, you can add content that is needed but not present, and you can build a relationship with the folks you interact.

With all of this said, participatory design isn't a fit for every situation. In some cases, users want things that are not possible for legal reasons. In the case of real estate, the user might want to indicate the type of buyer they want for their home. That's illegal. In other cases, the benefits just aren't worth the cost. Participatory design is not for every situation, but for situations where your users are going to be incorporating a document heavily into the way they work and operate, it can be useful.

### Doing Participatory Design

Having talked a great bit about participatory design, what does that workflow look like? An extreme commitment to participatory design can be seen below where I've sketched out what an example might look like where you commit from the front to back of a design process to working with users rather than for users. Again, this is not practical or even advantageous in every situation, but in the right circumstances it can be invaluable! (And, this is just one suggested workflow—it by no means represents the entirety of participatory design).

#### Participatory Design Workflow

1. Build relationship with users—find out what they like and dislike about documents
2. Come up with parameters for the design process—what will be the scope and timeline?
3. Arrange to work with users to brainstorm ideas on the document's purpose
4. Come to agreement internally and externally on purpose
5. Draft a skeletal outline of the document/system
6. Consult with users for feedback and comments
7. Revise the draft/skeleton
8. Consult with users for feedback and comments
9. Complete the document as envisioned
10. Test the document with users, soliciting feedback and suggestions
11. Revise the document as heavily as possible, potentially reverting to step 4
12. Test the document again
13. Revise the document as needed
14. Publish the document
15. Consult users regularly on the document's impact and unforeseen issues
16. Revise periodically with user's input and consultation

As I have mentioned, the above is a heavy investment into working with users. It isn't always the best choice, but it can literally give you information that can be found nowhere else and can help you find solutions to problems that you aren't even aware of that impact the way your organization and those that use its documents operate.

### When to use participatory design?

In an ideal world, I suppose you would use participatory design for every single major writing project. After all, folks should have a say when things are going to impact how they work and live. But, we don't live in that ideal world and we often have to work in environments that aren't open to participatory design. So, when should you take the time to aim or participation? The checklist below can help you think through this question:

## 📌 Participatory Design Assessment

- Do my users operate with my document in ways that I don't understand?
- Do I often see users using documents in ways different than intended?
- Are there problems between the way forms are filled out and how my organization uses them?
- Do I have a relationship with the users that I can leverage?
- Can I have users participate in an ethical and legal way?

Answering the questions above can give you an idea if you have enough benefits to start to make an argument for user-focused participatory design. If your organization doesn't already use participatory design, you may have to start with baby steps, working your way towards this process with some user-centered choices. In all such situations, be on the lookout for ways that you show the benefits of getting outside feedback—you need to be able to explain how working with users benefits the bottom line.

What might things look like if your organization and your users are going to benefit from participatory design? One example might be the process of buying real estate. Buying a home or other type of property is often a dizzying task for many first-time buyers. You have to consult a bank, you have to find a realtor to work with, you have to tour properties, understand loan options, make bids and assessments of value, navigate inspections—all kinds of peril await! But, what if the process was full of documents that were designed in participatory ways?

In such a scenario, a real estate group would consult with the types of first-time and recurring clients they operate with. They would ask the clients what types of things they do well, and what types of things they don't do so well. They might focus on things like client education. When a real estate relationship starts, how much information is shared with the client? Perhaps a client is going to be buying a rural property that is eligible for federal grants for rural development. What does the client want to know? How would they use that information to assess things? Those are questions that only the real estate group could answer by workshopping with clients about what is valuable and not-sovaluable.

With recurring clients, maybe more of the information revolves around getting loans and paying taxes when you are buying multiple properties, operating as an LLC or other legal construct, or operating across state lines. In those situations, the same type of workshopping with clients could be advantageous. You can identify what they need, what they ignore in current information, and the times and places they simply need questions answered that you either aren't answering or aren't being asked in the first place.

The outcome of these workshops would likely be a draft of some informational documents for the clients, documents which could be tested with clients as they navigate the process, and documents that could be assessed at the end of real estate deals for suggestions to tweak them on an ongoing basis.

The end result of all of this would be a series of real estate documents and a workflow for clients that would likely go above and beyond what is found with other real estate groups. Yes, there would be a cost, but the benefits would be immense with clients having a firmer understanding of their options and a greater connection with the real estate group and appreciation for their efforts to make the process as demystified and clear as possible.

---

This page titled [2.4: Usability, Use, and Participatory Design](#) is shared under a [CC BY-SA 4.0](#) license and was authored, remixed, and/or curated by [Adam Rex Pope](#) via [source content](#) that was edited to the style and standards of the LibreTexts platform.

## 2.5: Institutional Writing

---

### Institutional Writing

Having looked at drafting and design and usability, we will close this chapter with a few notes about writing in institutional settings. When you write in an institution, you operate differently than when you write in your college classes or when you write on your own. The institution will have its own conception of what it does, how it is seen, how it operates, and what it expects from documents. This understanding will then be layered onto the hierarchy of the organization with your supervisors and coworkers and subordinates all bringing their own understanding of the institution, their own understanding of how things work/don't work, and all the fun unwritten and written rules that pervade such situations.

When you join an organization, one of the most important things you can do as a writer is to figure out how things work and how they don't work. Many times this involves a savvy interrogation of the written and unwritten rules, a process that can be daunting. To make sense of all of this, you can append the following suggestions to your existing writing workflow:

#### Institutional Writing Question

- What am I being asked to do? Who is asking?
- What does the document I'm creating normally look like?
- If I'm creating a new document, who will it need to make happy?
- How does the institutional normally communicate? What voice/terms are used?
- Is there a style guide? Does it apply to my document?

By asking the above questions, you can become more aware of the situation you are writing in with a new institution. In many cases, the secret to effective institutional writing is to simply take things slow. Watch what other people are doing. Think about what they're not doing that you might naturally do in your own writing. Take all of this into account as you slowly learn what is going to work for you as a new hire/member.

---

This page titled [2.5: Institutional Writing](#) is shared under a [CC BY-SA 4.0](#) license and was authored, remixed, and/or curated by [Adam Rex Pope](#) via [source content](#) that was edited to the style and standards of the LibreTexts platform.

## CHAPTER OVERVIEW

### 3: Visual Communication and Technical Writing

[3.0: Introduction](#)

[3.1: How does visual communication work?](#)

[3.2: Using visual conventions](#)

[3.3: Signs, Safety, and Visual Rhetoric](#)

[3.4: Data Visualization and Infographics](#)

---

This page titled [3: Visual Communication and Technical Writing](#) is shared under a [CC BY-SA 4.0](#) license and was authored, remixed, and/or curated by [Adam Rex Pope](#) via [source content](#) that was edited to the style and standards of the LibreTexts platform.

## 3.0: Introduction

---

In our third chapter, we're going to be looking at the visual side of technical writing. It may seem a bit unusual that in a text on writing that we are going to be spending an entire chapter on visual design, but more and more the visual design of technical documents has become increasingly important for authors and users. With that said, this is not document design—we will be talking about document design in the next chapter, and document design is as important as visual design. In some ways they are the same sort of process, but for our purposes we're going to talk about visual design first before diving into document design. To differentiate between the two, consider visual design anything that is primarily visual in nature added to a text—a graphic, an image, etc. Document design, on the other hand, is the visual nature of the text itself—the formatting, the colors, the paper, etc.

One advantage that we have over past practitioners of technical writing is that we can actually spend time on visual communication and carry it out without years of practice working on our skills at actually drawing the visuals we want to use. Desktop publishing technology has entirely changed the way visual design happens in technical communication over the last three decades by giving almost anyone the ability to design competent visuals. In the last several years, with the boom in infographics and other design-heavy presentations of data, this process has only gotten easier and more friendly to newcomers, all the while become more advanced and powerful for those willing to put in the time to truly manipulate data and design.

In addition, many technical deliverables are found in electronic form first, print form second. The advantage of this change in format conveys to visual design can't be understated. Printing in color, especially vibrant and heavily colored texts, isn't cheap (though it has gotten markedly cheaper and more accessible). Designing for the screen first grants us much more freedom to use visuals that have a robust palette of colors to indicate any amount of information—though if our text will also be printed in black and white it can add in new challenges.

### Why does visual design matter?

One question that may be on your mind as you read this chapter intro is simply, why does visual design matter in technical writing? The answer is all around us really—more and more of our communication is visual. Think about how much time we spend on computers of any format—mostly phones these days. These devices are often almost entirely visual—there is very little tactile feedback outside of vibration.

Concurrent with this rise in the visual is the rise in the prestige of certain visual designs. It isn't enough to have a phone—you need a phone looks awesome. Sometimes, even the manufacturers of these phones get caught up in this, embracing trendy choices without necessarily thinking about the usability of something like a fingerprint sensor on the back of phone or a notch carved out of the top of the screen. This can go even deeper than visuals—think about how small your phone's thickness is compared to a phone from five years ago. I wonder how much more battery life we'd all have if our phones were the same thickness but had the more advanced batteries we use today.

The problem with visual design, as we've hinted at just now, is that what looks good isn't always what works well for users. Too many times a design is created because matches an existing trend or has visual appeal—not because it makes whatever task the visuals are draping easier to perform.

Now, just because visual design can become too central doesn't mean visual design is bad. Visual design is vitally important because there is so much we can say with visuals that we can't say in a compressed space with words. Think about the logo of your university's athletic teams—when you see that logo, you see more than just the letters and images and colors, and what you see is controlled by your circumstance and your situation. In addition to brevity, visual design can also bring clarity. Sometimes you can more clearly see something than you can read about it, especially when you're dealing with a very delicate task like soldering a resistor into just the right place on a circuit board.

Visuals can also have an ethical case—some folks can't read or can't read the language that your text has been written in. With the use of visuals, you can make it more likely that someone will be able to understand your text and act accordingly. If you doubt the usefulness of visuals that work across cultures and languages, you've never had to go the restroom badly while visiting a country where you don't speak the language.

---

This page titled [3.0: Introduction](#) is shared under a [CC BY-SA 4.0](#) license and was authored, remixed, and/or curated by [Adam Rex Pope](#) via [source content](#) that was edited to the style and standards of the LibreTexts platform.



## 3.1: How does visual communication work?

---

### How Does Visual Communication Work

When we use visual communication, something happens that allows us to see the visual as more than a simple collection of different components—we don't see a visual, we see the rhetoric embodied by the visual. As hinted at earlier with our sports team example, visuals don't function as individual parts or even as a simple sum of their individual parts. Visuals operate using complex rhetorical systems that we'll be referring to from this point onward as visual conventions.

#### A rhetorical aside

Now, before we go further we should probably take a moment and unpack the whole idea of rhetoric. Much like our usage of technical writing, rhetoric is a term that means a lot to a lot of people. By many definitions this entire textbook is a book about rhetoric, though I've not chosen to make rhetoric the term that we use over and over again to talk about what we're doing. Rhetoric is, in our terms, the available means of persuasion in a given situation. If there isn't any room for persuasion in a situation, there isn't any room for rhetoric either.

To unpack this definition, rhetoric is looking for points where you can work to bring others around to your way of looking at things, or at least the point of view or information you're advocating for. Parents use rhetoric when they attempt to convince kids to eat a new food: "It tastes just like those tacos we had last week!" Razor manufacturers use rhetoric to sell their newest blade: "Get an even better shave than ever before!" Phone designers use rhetoric when they pitch something as the newest, the best, or as "magical."

In each of these cases, rhetoric is the identification of the audience, of what that audience values, of how the message will impact the audience, and then ideally the use of that information to create something that will appeal to the user/reader/hearer. Sounds a lot like our second chapter, doesn't it? Thinking about the examples above, the parent is using their knowledge of the child's appreciation of tacos to make a favorable comparison, to re-write the way the child sees a dish. The shaving example playing off the doubts you may have about your current shave—could it be better? The phone design is playing on your desire to have the best, the brightest, the shiniest, and to have the prestige (unspoken in this case) of having a device with all of these attributes. Each of these approaches is a rhetorical approach, one based on research and considerable of where a text is going, where it is coming from, and what it is about.

Other definitions of rhetoric you may be more familiar with usually revolve around something being "just rhetoric." These definitions are usually referring rhetoric's role in making a text or idea more palatable, making rhetoric like a costume, a style, or even a seasoning for your text/idea. None of this is wrong, per se, but the focus on rhetoric as window dressing cuts off the most valuable part of what rhetoric brings to the table as a lens to see the world. Rhetoric may be many things, but it excels at helping us think through ideas to make them worthwhile to others.

As I noted earlier, much of our text is based on rhetoric, though we've not been using the term directly. As someone who was schooled in rhetoric from start to finish in my doctoral training, the approach is the most fundamental one I can imagine. With that said, rhetoric is a very broad field of study with any number of applications. As such, I use technical writing and technical-writing-based terms to discuss much of the content of this text. Audience analysis is very much rhetorical analysis, but I prefer audience analysis because it hews closer to the technical and the formulation makes us more aware of the transactional nature of our writing. We could use rhetoric, but that is a broader term and for our case I prefer the more focused one.

Having said all of that, visual rhetoric really is the best term for what we're discussing right now because it gets at exactly what we're talking about. We are looking at the available means of persuasion in the visual arena, looking at what visuals mean, what they do, and where they come from, and how we can use them to persuade and educate.

#### [Back to visual communication—how does it work?](#)

Much of the approach we'll be using in this chapter involves visual conventions, a rhetorical concept developed by Charles Kostelnick and Michael Hassett in their book *Shaping Information: The Rhetoric of Visual Conventions* (2003). For Kostelnick and Hassett, visual conventions are an inherently rhetorical communication style that relies on a bevy of hidden conventions and

histories to make sense, conventions that will change and evolve over time, rising and falling in response to the course of history. Their book is awesome and I recommend it to anyone and everyone who does visual design.

With any given visual design, what matters are the visual conventions that the design creates, redefines, integrates, or ignores. These visual conventions are choices in the design process that have come to mean something to certain folks (sometimes even meaning different things to different people). These visual conventions have rhetorical effects—they move people to understand things a certain way, to treat information a certain way, and to see visuals as conveying a certain type of information or a certain type of authority or association.

Sometimes a visual convention's meaning is mandated—think about the road sign that you follow on any given drive. There aren't really options when it comes to depicting the speed limit of a given stretch of road—the design is a convention that is used over and over again across the country. In each case when you see the speed limit sign, the combination of the white color, the shape of the sign, and the font and wording on the sign all signal to you that this is an official government sign informing you of the expected limit to your vehicle's speed on this stretch of road. Sometimes the placement can vary to make the sign less effective for drivers (though perhaps more effective for officers giving tickets), but the sign always means the same thing because of the power of the visual convention and because of the various laws and ordinances preventing competition with other designs and information. In the case of these signs, the rhetorical weight of the national or state government is behind each visual because of the associations with that government and the interactions those signs can prompt with law enforcement because of their correlation with state and federal laws.

In other cases, a visual design can be subject to tweaking and manipulation. Think about the veritable industry that has popped up over the last several years drawing on t-shirt mashups of various fandoms. The designs in those shirts often play on potentially obscure mashups of different elements of pop culture fandoms, creating a shirt that is quite meaningful to those that get the reference.

Wearing a shirt with visual references is a rhetorical move—you're showing those around you, or making the claim, that you are a part of a particular group with a particular mindset. When you put on an "I'm With Her" t-shirt or a "Make American Great Again" hat—you bring with you everything that anyone has ever associated with those visuals and invite classification of your political preferences. In fact, the power of political clothing in particular is something so great that it has spawned numerous laws and lawsuits related to voting and voter intimidation.

As you may be aware, or not, the printed page is also a visual convention, a bit of visual rhetoric. When you see a printed page with black text and white paper and clear margins on each of the four sides, you realize you are reading a printed page. That, in and of itself, has implications! How many documents have you not read simply because they looked like a printed page rather than something more interesting or quickly readable? Visual rhetoric gets complicated quickly.

---

This page titled [3.1: How does visual communication work?](#) is shared under a [CC BY-SA 4.0](#) license and was authored, remixed, and/or curated by [Adam Rex Pope](#) via [source content](#) that was edited to the style and standards of the LibreTexts platform.

## 3.2: Using visual conventions

### Using Visual Conventions

As technical writers, we want to ask ourselves—what do we need to convey visually in this situation? The question of how to convey something visually can get complex quickly due to the multitude of factors that impact how a visual is interpreted. To navigate the process effectively, you need to ask the right questions and identify the issues that may pop up with your visual choices. There are risks and rewards to using visuals heavily in a text, and the risks can multiply as you lean harder into your visuals to carry the weight of your meaning. Too many references, too many meanings, and your visuals can become more complicated than a word-based text!

When you go to design visuals, try starting with the workflow/questions below to guide your visual design and thought process:

#### Drafting Visual Rhetoric

1. What is the goal/purpose of the visual?
2. What needs to be conveyed?
3. Who will be the audience and what visuals will they recognize?
4. Are there any visuals that could be altered or integrated to fit the purpose?
5. What will the visual look like?—Draft it.
6. What associations, good and bad, come with the visuals?
7. What legal guidelines, if any, impact the visuals?
8. Will this visual be understood, or will it need to be explained?
9. Finish it or return to a previous phase.

#### 1) *What is the goal/purpose?*

First off, you need to decide your purpose and goal for the visual. If the visual is a stand-alone document, then this process is much more involved. If the visual is a part of a larger document, or a single document that is part of a larger campaign, then you often have less work before you when it comes to deciding what your goal and purpose are.

The goal and purpose are going to be guiding principles for you, just like with the drafting process. You need to make sure that you keep your goal and principle in mind always—they are the rubric that you will use to grade your work and that you will use to judge the choices that are available. Never allow your design to take control of your drafting process! Your purpose is what matters—not the awesomeness of the design. There are a lot of awesome looking designs out there that are absolutely awful documents or experiences because the folks creating them became so enamored of their visual design that they forgot that people had to actually use the text. To quote Dr. Ian Malcolm, “[they] were so preoccupied with whether or not they could that they didn’t stop to think if they should.”

#### 2) *What needs to be conveyed?*

Going along with the question of purpose, we need to figure out what exactly the visual is going to be doing—what is it going to convey? To answer this question, you need to ask whether the visual will be carrying all of the weight or simply part of the weight of your project. If it is the sole document, then it will convey all of your information. If it is part of a document...well...you get the picture. Make a list of everything the visual needs to convey, and then run that list by your purpose and weed out things that don’t fit the criteria of your purpose.

Once you have an idea of what you’ll be conveying, try to get specific. What particular values are going to be conveyed? What specific data? Go beyond simple typology and get into how much data will be there and what format it will have. These considerations matter a great deal. During this process don’t be afraid to doubt the creation of your text—sometimes a visual needs help and that is okay.

#### 3) *Who will be the audience and what will they recognize?*

Once you have an idea of what information you should be conveying and your purpose, you need to run this all past your audience and what they’re going to need and understand. This might seem a bit backwards, but you want to at least have a firm idea of your

own goals before you hit the audience angle. You don't want to have this project/visual spiral out of control.

At this point, you may need to add some information if your audience needs some help—that is alright. But, always keep your purpose in mind. Your text doesn't need to do everything your audience could ever desire and want. It needs to complete the goals you've set for it. Sometimes you need to expand what you thought the text would be to do that, but you make that expansion with your goals and purpose in mind!

If you realize that your audience may need more than your purpose allows, you have some hard conversations ahead potentially. When you want to make a project bigger, there are often institutional concerns about mission creep—letting a project grow until it basically can do anything and everything. More often than not, good projects do one thing well rather attempting to do all the things. As such, organizations can be—rightfully so many times—opposed to expanding what a document is supposed to do. If you feel strongly that a text needs to be expanded, make sure to couch your conversation in language that serves your organization—show them how this is going to help them too.

When it comes to what your audience will recognize, you're going to be thinking about what you can rely on without explanation and what you can rely on with explanation. Most folks understand what a stop sign is, but not everyone can quickly read the chemical hazard sign that you find on the doors of laboratories with dangerous chemicals inside. That's okay. Part of your visual design at times should be an explanation of the design itself—that is what a key on a map is for after all.

*4) Are there any visuals that could be altered or integrated for the purpose?*

Once you know who your audience will be and what they will recognize, you can move along to the next phase and decide what visual conventions could be altered or used for your purpose.

In some cases, you can quickly alter a visual to make something visible. You might, for example, take a generic soccer jersey shape and then use that shape as a frame in Illustrator with a nation's flag underneath. The end result is a quickly-made graphical representation of a national soccer team. In this case, you've identified two visuals that make sense to your audience/user—the national flag and the soccer jersey. Combining the two is fairly seamless and with the right context (such as a poster title referencing the beautiful game) the visuals should fit right in and explain things visually at a glance.

The goal here is to identify what visuals would be useful, or to create some visuals to be useful. You can mashup various conventions to make one whole convention, or you can rely on a single convention or two to make things work. Don't think about this as a close-ended process; this stage is all about coming up with ideas.

Create a list as you work of what conventions might work or might be modified to fit your needs. If you want, jot down some notes as to why you've chosen this convention and how it might work/ integrate with your purpose, audience, or content.

*5) What will the visual look like?—Draft it!*

For the next phase, you'll want to take all of your information and come up with at least one or two drafts of what your visual could look like. One thing that may be helpful as you go through this process is to get all of your data into one place where you can reference it clearly. A table can often help for these purposes:

PURPOSE AND GOALS	CONTENTS	AUDIENCE AND AUDIENCE KNOWLEDGE	POSSIBLE CONVENTIONS	COMBINED CONVENTIONS/FINAL VISUAL IDEAS

With a table like the one above, you can see your information and make connections across the matrix you've created. This can be extremely helpful in group writing situations and can help you see/ make connections that you might not make or see when you're simply referencing a list or talking out loud.

After you've gotten some ideas together, sketch them out. Don't spend a ton of time on polishing your concept though—you want to make sure this is something you can/should stick with!

#### 6) *What associations, good and bad, come with the visuals?*

Next, you want to take stock of your visuals and what they connote. This may be something you've been doing all along, but sometimes you can include some imagery without critically engaging with what that will mean and say to others.

In this phase, take a hard look at your visual drafts. What are they saying? What type of message is being conveyed? Does this align with your purpose and your content and your public image? If not, you may need to make some changes. Your audience is crucial in this phase—you might even want to reach out to some testers and get some feedback from the audience you are targeting. There could be positive, negative, or political associations with some of the visual conventions you've chosen without you having realized the connections that exist! Just because you don't see them doesn't mean you'll not get implicated in any mishaps.

For example, you may have chosen a shade of red that is associated with a major rival of the flagship state university's football team. You likely wouldn't want to have that color associated with your project, especially during a tense football season. But, if you're not huge football fans, you might not realize that a connection exists. Getting some outside feedback can be really helpful when you're figuring out what exactly your visual conventions may be saying. Don't be Picard on Risa with a horga'hn.

#### 7) *Will this visual be understood, or will it need to be explained?*

Next, you'll want to make sure your visual can be understood, or if it can't be understood that you provide interpretation. If your entire visual is difficult to understand, you'll likely need to revert to a previous phase of development. There isn't much use in creating an entirely novel set of conventions that require painstaking explanations. (Sure, you can make some what-about cases, but for the most part entirely novel designs that make sense to no one are a bad idea).

As you consider your visuals, run past what you're conveying and what your purpose is and combine that with your audience. Where are the gaps that might appear? Once you've identified those gaps, create some explanations to help guide the user. If the gaps can't be bridged, redesign!

For example, you might be using the soccer jersey with national flag example from earlier in an infographic. In addition to the jersey, you might also be including soccer balls that represent 500 people in order to create an infographic about the average attendance of home games for the national team. In the case of the ball and the 500 people, there is not a direct visual convention that exists. No one that I'm aware of naturally associates 500 people with an icon of a soccer ball. Since that is the case, you'll want to label this aspect of your visual accordingly, teaching your reader that the value of a single soccer ball in your visual is 500 people in attendance.

#### 8) *What legal guidelines, if any, impact the visuals?*

This step comes late in the process, though depending on the field you're working in, it might need to come earlier. In this phase, we're going to basically be assessing the legal guidelines that impact our text in one way or another.

You may primarily want to think about copyright here—visual design is an area that has lots of tangles that you can get into. You can't simply use the Nike swoosh and think everything is going to be okay. Make sure that you have the rights to the visuals that you will be using!

Go through your visuals—are there any copyrighted or trademarked aspects that you're using? Do you own those or have permission for their use? If you don't, see if you want to take the trouble to get the visuals or if you simply need to design around the issue. Be warned—if you are using parody or satire, you can still end up in a legal battle.

#### 9) *Finish it up or return to a previous phase*

Once you've finished the previous steps, you should have a final candidate and be confident in the candidate's effectiveness and legality. In that case, put some final polish onto the design and get it ready to go. If, however, you're not happy with what you've found yourself with, take some time to go back in the design process.

---

This page titled [3.2: Using visual conventions](#) is shared under a [CC BY-SA 4.0](#) license and was authored, remixed, and/or curated by [Adam Rex Pope](#) via [source content](#) that was edited to the style and standards of the LibreTexts platform.

## 3.3: Signs, Safety, and Visual Rhetoric

### Signs, Safety, and Visual Rhetoric

When you're working with visuals and visual communication, one important aspect of this type of work to keep in mind is the presence of safety and warning signage and their associated conventions and representations. As with any type of visual rhetoric, there are conventions that will come into play and conventions that can be flouted or adapted. Think about this section as an extended addendum to the previous, one that goes over a few issues that are of note when we're working with visual conventions and rhetoric that involve safety and signage.

#### Warnings and Color Systems

One ever-present part of almost any instruction manual or poster is the warning and caution system. These warning systems are so regular for some of us that we almost ignore/internalize them, but they are worth focusing on specifically as technical writers. When you have any sort of technical process, you have some aspects of that process that are more dangerous or more important than others. You may have some steps, for example, that are particularly troublesome or have just historically caused issues (even if you wouldn't think they would—people are weird). In those cases, you may need a warning note or signage.

Coloration is one important part of warnings and cautions. When we think about the Western use of such colors, we often resort to the colors red and yellow for our work—these colors map onto our streetlights and are used in any number of areas. The visual rhetoric behind these choices is fairly universal—when you see red, you're expected to stop or expect some serious consequences that should be avoided or that you should be made aware of. When you see yellow, you're going to expect to slow down or realize that there is a particularly tricky step or issue about to happen. In each case, color gets recognized before the text.

Even though we use color, we should be aware that all colors don't mean the same thing in all situations and cultures. Colors that have one association in the United States may have entirely different meanings in other cultures! Part of understanding how to use colors in signage and visual rhetoric is to understand the meaning behind your choices or the meanings you're trying to connect to your choices (which we'll focus on more in document design). For example, Halloween is my favorite holiday of all time, but it is a holiday that isn't universal. Invoking Halloween with orange and black won't work everywhere because the tradition is not one that is immediately apparent to some groups.

#### Warnings and Signage Conventions

When we create any sort of visual rhetoric that is designed to warn or caution folks, first and foremost realize that these signs often have mandated rules and regulations behind them. You don't simply create your own chemical safety poster/signage—you use the mandated and approved signage. These mandates are important because the diverse groups may need to use them quickly, such as first-responders going through a burning building. The flexibility of some visual rhetorical choices is limited simply because more flexibility would introduce the chance that misunderstandings could happen.

As a brief aside, this is also true of auditory warnings. A few years ago a film got into trouble for using the Emergency Broadcast System tone for a trailer. You simply can't do that—it is illegal. The whole goal of that tone is to prepare citizens for emergency information. If it was allowed in any other case, it would lose its value. Because of that, it is protected vigorously.

#### Developing Visual Rhetoric for Safety with Signs

For our purposes, we need to be acutely aware of what existing laws apply to any signage that we might use. While it may be amusing to read those faux signs that warn something akin to, "If you touch this, it will kill you and it will hurt the whole time," there are many times government or institution-mandated choices that have been made for us already.

For signs that involve harm to the process being carried out or to individuals, we can follow a fairly direct workflow, in addition to what is noted above:

##### Signs and Safety Workflow

- 1) What are the dangers of this task?
  - a. To people

- b. To property
- c. To other stuff™

- 2) What needs to be communicated to folks involved?
- 3) What official signage already exists?
- 4) What signage exists that covers similar territory that could be adapted?
- 5) What legal or regulatory constraints control the signage or its presence?

#### 1) *What are the dangers of this task?*

First and foremost, establish what dangers exist. You want to first of all know if someone might become injured or perhaps even lose their life. You also want to know how something could be damaged, potentially catastrophically. Finally, think about the types of dangers that exist that aren't necessarily either—such as risks to appearance or reputation or relationships. (Medical records are private for these exact reasons.)

#### 2) *What needs to be communicated to the folks involved?*

There is a difference between knowing what is dangerous and knowing what someone needs to know. Figure out what someone must know about the situation. It might be that there is a live wire involved. It could be that installing a certain part is a one-way process that can't be reversed. It could be that no lifeguard is present. It depends really. But, figure out what is absolutely needed.

#### 3) *What official signage exists?*

If something official exists, you'll need to use it. Find out what examples are out there and what templates you can use. In some cases, you need a specific sign, such as with material labeling.

#### 4) *What signage exists that covers similar territory that could be adapted?*

Because of the way that visual conventions work, you may have something that exists out there that you can adapt. If there is a common way of signaling something that isn't legally mandated, you can draw on your audience's knowledge of that format to get your point across. The same is true if there is an institutional equivalent that is often used in these situations.

#### 5) *What legal or regulatory constraints control the signage or its presence?*


In some cases, you may have some legal rules around when signs must be present, though the signs may not be mandated to have a particular design. You need to be aware of those needs and design accordingly. For example, theme parks have ride-heights that are enforced via signage. The conventions vary between parks, but they are regulated to prevent accident and injury and are often easily understood by audiences because of their shared visual conventions.

### The Visual Rhetoric of Context with Signage

When it comes to creating signs in particular, think about the users that will encounter those signs. As with the above section, think of this as a focused addendum to the visual rhetoric drafting process from earlier. Signs should rely on visuals that make sense to readers within the context they are deployed. Signs, more than any other type of visual rhetoric, relay information with visual shorthand. Too much information and a sign is useless, or it becomes an infographic or directory or map. Too little information in a sign and ambiguity and confusion reign.

#### Signs and the power of context

Think about the signage in a library, such as the library I'm drafting this text in. Library signage can do things that other signs can't because of the way that we read them. In a library, we're expecting to find things in the way that you find them in a library. For some collections, that means the Dewey Decimal System or whatever equivalent might exist. In other situations, it means alphabetical listings. In either case, signs in the library can reference alphabetical lists or a numerical reference system without explanation because the situation of the library explains what those elements mean:



**A SIGN FROM THE LIBRARY**

Take the example sign above—You have 7 major areas that are conveying information to the audience/user. You have a major block at the type labeled “Large Print.” This block, from the context, we would assume refers to large print books. There really aren’t a lot of other options in a library for this to have another meaning! Below that are two large blue blocks, each with arrows within them and smaller blocks as well. The arrows, from the context, we interpret as one side or another of the bookshelf. The arrows function that way from the context—there isn’t room for much else to make sense. Finally, there is the smaller box that starts with one short snippet and ends with another, such as the amusing choice of “Sad-Tru.” Because the context of the library, we can understand these terms to likely reference alphabetical ordering. If we want something that falls between “sad” and “tru” in the alphabet, we’ll look on the left side of the shelf. If we want something beyond, we’ll need to look at the other side or further along.

For your own work, think about context. What can someone be expected to know? What will they not know? What visuals will make sense within this context? Which won’t?

---

This page titled [3.3: Signs, Safety, and Visual Rhetoric](#) is shared under a [CC BY-SA 4.0](#) license and was authored, remixed, and/or curated by [Adam Rex Pope](#) via [source content](#) that was edited to the style and standards of the LibreTexts platform.

## 3.4: Data Visualization and Infographics

### Data Visualization and Infographics

When we think about visual rhetoric, one of the most iconic tasks we associate visuals with is the graphical display of information. Visual representations of data are one of the quickest ways to take something numerical and data-driven and make it digestible to a lay audience. For example, you may not know much about quarterly profits or the levels of methane in the atmosphere, but you can understand a trend line on a chart showing these figures rising and falling. Visualizations of data are powerful, and potentially perilous on ethical grounds.

#### What is data visualization?

Data visualization is at its heart a fairly simple task—you take data and you represent it in a visual format, often in the form of a chart. Now, if you are like most people, the idea of working with charts does not exactly get your blood pumping. I think that is a natural reaction, perhaps even a healthy one considering the state of most charts out there. But, it doesn't have to be so boring and dull. Data visualization can be one of the most engaging and useful parts of your work in technical writing and an essential tool in communicating complex information to others.

We tend to think of data visualization hand-in-hand with charts because charts have traditionally been the name of the game for most folks, historically speaking. Until the relatively recent creation of powerful and accessible data visualization software that laypeople can use successfully with little training, simple charts were the most accessible option for sharing data visualizations because they often had to be drawn by hand or with tedious software. With the rise of more and more software tools to craft visuals and design texts, data visualization has changed dramatically in a short amount of time. For example, infographics are a type of data visualization that have existed in one form or another for a good while, but they have seen an astounding burst of popularity in the last several years, likely due to the confluence of easier-to-use tools for their creation and low-cost/high-traffic venues for sharing them: social media and websites.

At its core, data visualization is a process of translation more than anything else. Much like the standard definition of technical writing that we started with early in the course, data visualization takes a piece of data and then passes it on to a new audience, making choices along the way of how to present that data and which parts of that data to make more visible and which parts to make less visible or to omit altogether. For example, you might have a dataset that includes information on fifteen different criteria about different institutions of higher education in your state, but you may create a chart that only displays three of them together to make an argument about how the three are interrelated or dependent on each other or to simply show a huge disparity between institutions. The entire dataset doesn't always come through into the visualization, and even if it does, it will be altered in some way by the shift from text/number to visual.

Now, you may have paused briefly at what I just said—shouldn't data visualization just be about numbers? Why would we want to talk about text? Well, thinking that data visualization is just about numbers is a mistake, one that limits our understanding of the power and flexibility of visualizations. For example, I could have a dataset that lists the colors used by a college athletics team since its inception. This dataset likely includes color swatches, perhaps color codes, and will also contain dates for the usage of these colors and perhaps even imagery demonstrating the jerseys that the colors would be used on during any given time period. Notice that most of this dataset is not actually numbers. A good bit of it is going to be visual already! From this information I could create a timeline that shows the evolution of jersey design and coloration, or I could create a pie-chart that shows how much of the team's existence is devoted to each particular color choice, or I could do something else entirely. Data visualization doesn't have to be about taking numbers and turning them into images; visualizing any sort of data counts!

#### Data Visualization, Education, Persuasion, and Discovery

When we think about data visualization, we must keep in mind that we're working with a particular goal in mind (at least, I hope we are) to either persuade or educate our readers about something in our original dataset. (Now, that isn't to say this is a definitive list of stuff we can do, but let's keep it simple for our purposes). In each of these cases, we may actually find ourselves doing even more than simply educating or persuading—we may end up learning things we didn't set out to learn.

When we work to educate or persuade with data, we're making editorial choices, choices that we've discussed above. We situate ourselves, our audience, our goals, and the dataset. We try to figure out what particular part of the dataset needs to be visualized

and how that visualization will work. This may sound familiar, and it really does align almost one-to-one with our visual rhetoric workflow above. The key here is that we need to think about our dataset and what we need to pull out of it— what will be of use for our users and our context? Once we figure that out, we need to see how that can be carried out in a way that is clear and that doesn't mislead.

Going about the work of figuring out how to share information visually can lead to unexpected discoveries, and that is part of the beauty of data visualization. The approach can be used to share information, but it also has a strong role in invention. You may be wanting to simply relay the growth of different categories of students at your university, but in that process you realize that while all groups are getting larger, the rate at which they are growing is different, resulting in some groups actually becoming a smaller percent of the overall student body despite continually getting larger. You wouldn't have started out looking for this, but in the process of crunching all of those numbers into visuals you stumbled upon this information, giving you a new perspective.

When we share visualizations, we're trying to get people to engage with data they might otherwise overlook or ignore. For example, many people take numbers and simply don't hear them as data, but instead hear them as noise or non-meaningful parts of your message. This isn't to say that folks who think numerically don't exist—they do—but, they aren't going to be in the majority as far as I'm aware. The same is true for other datasets—they are often super meaningful to a specific group of folks. What a data visualization does is present the information you are sharing in a new way, giving your readership a new lens to view your data through. In some cases, this can actually cause them to engage with the data when they otherwise wouldn't. In other cases, it may help them see around pre-existing conceptions they have about the data or subject by allowing them to see figures and information they are already familiar with in a new way or with new connections emphasized and old ones deemphasized.

### Types of data visualization

Just like with any other type of visual rhetoric, data visualizations work off of existing visual rhetorical conventions. Often times these are codified into types of charts such as pie charts, scatter plots, bar charts, etc. These types of charts exist because they represent an approach to visualizing data that has a value and a purpose. For example, pie charts show us how much of a whole something occupies. Other more novel designs exist, especially in the realm of infographics, but even those designs often rely on visual conventions from outside sources to make sense.

With charts, we have a powerful tool because most popular types of charts are easily read by the general public. More specialized charts have more specialized audiences, but simple bar charts and line graphs and their companions are found all over and can be easily created with spreadsheet software or design software. The advantage of the popularity of these types is that we don't have to do much work to get across the gist of what we're trying to say—the charts have a built in message. Pie charts, as mentioned above, show us a slice of a pie versus the whole. When you take a dataset and you want to emphasize just how much of the dataset is a certain category of content or just how big a certain group is, a pie chart makes sense. If you want to instead show how five different groups are outclassed by one larger group, you might want to use a bar chart because having the different group next to each other allows for a much easier comparison between them and emphasizes size similarities and differences in ways that a pie chart can't do with much rigor. And the beauty of all of this is that folks already understand how these charts work.

Sometimes, it can be useful to try to get your data into multiple types of charts and graphs, just to see what these types can teach you and show you, but you'll often come to a particular type of graph or chart because it represents something you want to say about your data, something you already know.

With infographics, the conventions and audience understanding can vary wildly depending on how you create your text. An infographic might be made up of a bunch of normal charts with some text to narrate, but often you find more novel approaches in infographics, approaches that borrow visual conventions from elsewhere to make their point.

For example, if we used our previously mentioned dataset on the color changes in an athletic program's history, we could compare the different colors by the number of wins a team had while wearing them. You see this sometimes with home and away and alternative jerseys in sports discussions. In this case, we would likely want to create a miniature version of the jersey that we could then use to represent a particular amount of wins, perhaps 50 per jersey. Then, we could have a grouping that showed all wins over a certain period of time with each jersey in each particular color representing the amount of wins that occurred in that color. The result would be a block of tiny jerseys that would meld together into chunks, letting us see how stark or not-so-stark the differences in wins were between the colors. In this case we've turned data into a visual, one that borrows the visual convention of the colors and the general jersey design to convey information via a key that each jersey is 50 wins.

Now, the above is just one example of how an infographic might be made—you'll often find that infographics are not as simple as one subject and one visual. There can be any number of charts and unique constructions in a given infographic: the goal of the project will help constrain and guide the choices of what needs to be shown and what doesn't.

### Building a workflow for data visualization and the ethics of visuals

With data visualization, we can mostly work with the previously discussed workflow on visual rhetoric and visual conventions. When you're identifying what to share and what your goals are, think about which parts of your dataset are going to be shared and why you're doing that sharing. When you think about what an audience can understand, think about the types of charts that could be used or the visual conventions that could be altered to create infographic components.

When visualizing data, one special extra issue stands out—the relative ease of purposefully or accidentally distorting the dataset behind a visual through design choices. When someone looks at our visual, they often do so with very little critical thinking, or at least that is what any number of sources and anecdotes claim. We tend to trust visuals, especially pretty looking visuals that are professional and shiny. This perhaps is part of a larger cultural trend in the US that connects polish and graphical prowess with excellence. (Just think about how much value is placed on the visual appeal of certain brands of phones, for example, rather than their functionality. Think about older looking websites— do you want to give them your credit card?) In addition, realize that visuals operate on the rhetorical idea of synecdoche—the part stands for the whole. When you represent a dataset to someone, they often take that to be the dataset. We really should be more critical I suppose.

When creating data visualizations, we need to ask ourselves: am I making choices that alter the way this data is perceived? You may be using a truncated X or Y axis on a chart to make a point, but that may not be obvious to your readers. In this case, your chart may be showing what looks to be a huge change in figures where one simply doesn't exist. Once you have created a visual, audit it. Get it tested with various users. Make sure that what it is showing and emphasizing can be backed up by the data behind the visual. If the visual can't be backed up by the dataset, you've got a problem.

---

This page titled [3.4: Data Visualization and Infographics](#) is shared under a [CC BY-SA 4.0](#) license and was authored, remixed, and/or curated by [Adam Rex Pope](#) via [source content](#) that was edited to the style and standards of the LibreTexts platform.

## CHAPTER OVERVIEW

### 4: Document Design in Technical Writing

[4.0: Introduction](#)

[4.1: Document Design Essentials is Essential](#)

[4.2: Layout and Document Design](#)

[4.3: Typography](#)

[4.4: Attributes of Fonts](#)

[4.5: Font Availability and Ethics](#)

[4.6: Remembering those signposts](#)

---

This page titled [4: Document Design in Technical Writing](#) is shared under a [CC BY-SA 4.0](#) license and was authored, remixed, and/or curated by [Adam Rex Pope](#) via [source content](#) that was edited to the style and standards of the LibreTexts platform.

## 4.0: Introduction

---

In this chapter, we're going to be looking at content in the vast arena of document design. Document design can be an entire course in and of itself (I happen to teach one at the graduate level), but there are certain essential skills in document design that technical and professional writers simply must master to communicate effectively and with purpose. We will cover the essentials of document design, followed by layout in design work, followed by a discussion of typography, and finally a reflection on document design and the signposting we've discussed earlier in the text.

When we talk about document design, realize that we are talking about the way that someone reads our text. The design of a document encourages a reader to view a text a certain way, to navigate a text in a certain way. Sometimes that is done using color. Other times it may be done using layout choices. At the end of the day, we're designing a document to be read a certain way and used a certain way, using design to help align the needs of the user with the text within the document. The best document design syncs up with how the text is designed work and encourages users to navigate the document that way. A well designed document is a joy to use.

---

This page titled [4.0: Introduction](#) is shared under a [CC BY-SA 4.0](#) license and was authored, remixed, and/or curated by [Adam Rex Pope](#) via [source content](#) that was edited to the style and standards of the LibreTexts platform.

## 4.1: Document Design Essentials is Essential

### Document Design Essentials is Essential

Document design as a component of technical writing continues to push further and further into the forefront of what it means to communicate effectively. Put simply, the bar for what is considered good design has been raised rapidly over the years and the minimum expectations of what a technical writer can do, and the value of being able to create good document designs, have risen. Think about websites, just for an example. How many times have you been hesitant to put your credit card information into a dated looking website? We judge websites, and documents, and the companies and individuals they are associated with, by their design chops.

Much of this rise in importance has gone hand-in-hand with technological advances—something we’ve discussed previously. Much like with visual design, document design software has developed and proliferated at an astounding rate. From the 1980s through today, the evolution of software and publication options has multiplied considerably, and in the last several years the explosion of design apps on phones and tablets has pushed this trend even further along. With the advent of software like Microsoft Publisher in the 90s, suddenly even small business owners could create their own custom signage, coupons, and brochures—something that we often take for granted today. Yes, the templates and the clip art are comical today, but at the time the software was revolutionary. Combined with the expansion of inkjet printers and eventually color laser printers and the expanding footprint of commercial printing services online and elsewhere, advances in technology and access have made creating and producing attractive documents easier than ever before.

Now, you aren’t going to be expected to work at the same level as someone who works primarily as a designer or artist—those folks have entire degrees focusing on the art of typography and drafting and other important skills if you’re going to be creating truly unique content as part of a design agency or the like. Instead, we’re going to be focusing on using the massive array of tools at our disposal these days to make attractive texts that are well-designed and well written for the context they’re going into. In particular, we want to focus on the design choices available to us and how to use those choices with meaning and purpose, not to simply click on buttons until things look nice.

To help prepare you for your work as a writer that has to keep design in mind concurrently with the usability and appropriateness of their writing, we’re going to cover some essential ideas as well as some tips and tricks that make working with highly styled texts much simpler and effective. We’ll cover in this introduction to design the research of design, the choice of paper/PDF, discuss styling tools for easy changes to texts, and cover images and accessibility/usability.

### Design is Work, Research Work

Many times when we think of designers, we tend to think of folks who sit around all day dreaming up wonderful designs that are a delight to our senses. We may stereotype these folks as being sensitive, whimsical, and driven by fits and starts of inspiration. Generally speaking, these folks don’t exist—and if they do, they don’t have steady jobs. Good design, like good technical writing, is a job that is research-driven and process-oriented. Good designers are good researchers that work by process rather than waiting for the mood or inspiration to strike.

The goal of all of this work is to support your design choices, nay even to make those choices, based on the information you have about your goals and your users/audience. If someone wants to know why you used a certain color, you should have an answer that makes sense based on your research and the context. Generally speaking you shouldn’t be simply doing design on a whim—there should be a goal with research connecting that goal to your choice. The idea here is that if someone questions your work your time usage, you can explain what happened and why you made the choices you made.

The research for design is pretty much the same research we’re doing when we look at the research in the writing process or the design of visuals or data visualizations. In fact, though we’re separating each of these into discrete processes to aid in learning the importance of different facets of each of these processes, in practical usage you’ll make use of all of these processes together, tailored in a way that fits your personal needs and context. So, when we look at doing research for document design, we’ll follow off the information we have on audience and visuals.

The first and most important concern when doing design work is of course your audience—who is going to be using this and who are you actually creating it for? Your internal goals and purpose need to be honored while also adapting your text as much as makes

sense to work with the primary folks using what you'll be creating. Each of these groups has information you will need: you will need to know what style is appropriate for your organization and the document you're creating, and you'll need to know what types of styles will be appreciated by your intended readership.

When working internally, you'll primarily need to know if there is a style guide that governs what you're writing. Some organizations have expansive style guides with templates for almost any type of writing you would want to do, right down to putting the company or institutional logo on your polo or company car. Others have much more lax document requirements but extremely specific color and logo expectations. Figure out what is expected or required.

You'll also want to think about the folks who will be using your design—not everyone values the same types of design and deliverables. For example, an ultra-trendy and modern design might not make a lot of sense if you're trying to target senior citizens for a research study or educational opportunity. In the case of the older demographic, you may want to use styles that are attractive to them. Don't know what those are? Do some original research! (I may have mentioned this a few times, but the last section of the book is chock-full of methods you can use to research audiences and usability). Remember that design isn't universal—it is always situated in culture and individual perceptions. I, for example, roll my eyes when I see rebooted 80s and 90s fashion choices that I thought were awful when I was living in those decades worn by students on campus. I didn't like acid wash jeans then, I don't like them now. Folks view design through their own experiences and their own values.

### Paper, PDF, and Beyond

When you're doing document design, an essential choice is the venue for your document. Are you going to be creating something that will be printed? Are you going to be printing something that is in color or black and white? Will this be on the web? Will it be on phones? Will it need to be multilingual? The choices are endless, but you need to know what type of document you're creating!

Practically speaking, you should know fairly early on what will be possible or not possible. If you're doing something for a class, obviously you have more freedom than if you're going to be published a run of 5000 documents that will be printed and delivered to their users. Find out what the goal of your work is and what will be expected.

When it comes to design, the medium matters—some mediums cost more, some allow for more options and design moves, and some present more accessibility barriers than others. For example, electronic documents can be more readable for folks using a screen reader, but only if the document is designed for that usage. In another situation, you might be creating a resume that you know will be photocopied. you'll want the actual text to look nice, but you won't want to use colors that will lose their legibility when they're transferred to a black and white copy.

One final consideration with the medium—color. Be aware, and we'll discuss this more in later sections, that there are different color palettes used for screen and print. Generally speaking, you can get much brighter and more vibrant colors on a screen than you can on the printed page. Now, that's not to say you can't get super-vibrant printed colors—you can—but, these colors often come from special palettes that can be expensive and hard to set up for a production run. The primary two palettes you'll want to know about are CMYK and RGB. CMYK is the set of colors used in most printing and consists of a mixture of cyan, magenta, yellow, and black. You may well have seen these colors in the ink cartridges of a printer. RGB is the set of colors used on screens, and is made up of red, blue, and green. Though it may seem counterintuitive, the smaller selection of colors creates the brighter shades.

If you ignore the question of color, you may end up with unintentionally hilarious or just plain awful results. If a printer is given a document set up for a screen, a document that uses RGB color, then it will perform an on-the-fly correction. This correction isn't going to be perfect and you may end up with a markedly different shade than you originally intended. At the same time, if you don't check that your RGB colors are going to translate to the printed page, you may pass along a digital proof of something that simply can't exist on the printed page without a lot of extra work and equipment. Often software makes use of out-of-gamut warnings or the like to give you this information, but you need to be aware those features exist and matter. (If you're wondering what this looks like in real life, think about any time you've had a really vibrant picture you've taken on your phone and had printed. It tends to look duller and less colorful when you get it printed, especially in the areas of intense color. This is what happens when you send something out of gamut—the printer will downgrade the colors to fit the available palette, often with dismal results).

## Styling Text and Quality of Life

While we are going to be discussing typography and layout in much more detail later in this chapter, I want to spend a brief amount of time early on letting you know about the most powerful and life-changing tool that you may well have been ignoring for most of your academic career—paragraph and character styles.

When you work with a large document, you often want to have a good selection of stylistic choices available to create signposts for your readers in the text. We've discussed this at length earlier in the text, and we're going to be coming back to it later in this section when we look at combining document design with signposting. The end result of this process is that you end up with a lot of text with specifically styled choices, choices that you may well want to edit later in your project! If you've ever spent fifteen minutes changing the font size or weight on a resume that you're tweaking before sending it you, you know just how miserable changing the font choices and design moves in a large document can be. There is, however, a better way.

Paragraph and character styles are tools built into most word processing suites that allow you to markup your text to allow the program to remember what type of styling you want to use for a particular segment of text. This information can relate to spacing, font, color, etc. You may well have noticed this before when using something like Microsoft Word when you see the various styles listed as Heading 1 or Sub-Heading in the top section of the user interface.

By painting a selection of text with one of these styles, you're allowing the document to know that this text has a certain purpose within the text. You may be saying this is a section heading, or it might be a keyword, or it might be a warning. In any case, the text has a label that you will be associating with a design. The magic of these styles, much like the magic of CSS when doing work with HTML, is that the program will always remember the purpose and label of the text, but it will be able to change the style associated with the text anytime you'd like. What you're doing is creating a label that then gets used to selectively apply style choices like holding the text. If you decide later to change the font from bold to underlined, you can simply alter the settings for that style and then every single instance of the text that is labeled with that style will be altered. It really is life changing.

When working with a larger document, using styles is almost a necessity and needs to be part of your workflow. Think about what types of text you will need to label for signposting and then create styles for those types in your word processing program or using existing styles as a starting point. By coming up with the styles that you'll need for signposting and design at the start of drafting, you'll be enabling yourself to easily change how the styles work as the document gets longer and more complicated. Suddenly, changing the font on a part of your resume goes from a painstaking process of clicking and dragging over and over again to simply selecting a new font or font permutation via the style settings.

I'm not going to go through the process of telling you how to go about setting up styles in this text—that would be likely a choice that would instantly date this text and the software I'm using. I would instead encourage you to look up the style options for your software of choice. If you're using something like Adobe InDesign or Scribus, the options will be overflowing. If you're using a cloud-based option, you may find significantly less tools available. Do some searching in the online documentation for your software for paragraph and character styles and go from there. When doing so, be aware that usually character styles are simply the characters in the text—not the spacing. Paragraph styles incorporate the style of full paragraphs, including line spacing and page spacing. Character styles tend to overwrite paragraph styles, allowing you to set up a particular font and spacing for your paragraphs and then selectively override the font when you have a single bit of text, such as a keyword, that you need to consistently look different.

## Images, Video, Accessibility, and Use

One last important area that we need to cover is the inclusion of images into your documents. Images are more and more common, especially in digital deliverables that don't have to rely on being printed. With the spread of high quality camera and camcorders via smartphones, almost anyone can take a quick photo or video that is impressive in quality versus anything available to the average person in previous decades. (Writing this text is making me feel old). Because of the availability and ease of creating images and video, we see them a lot. But, their uses are not always effective or even legible.

One important aspect of using images is the quality of the image—images are created at a certain level of pixel density and using a particular ratio for the dimensions. Despite what you see on TV, you can't simply yell at a screen with an image to “enhance,” and expect magic to happen. The pixels you need to create a more detailed image simply don't exist—they were not recorded when the

image was taken or they're not present in the current form of the image. You can't get them back with programming magic, though sometimes you can attempt to extrapolate what they might look like.

For our purposes, you want to make sure that your image is not pixelated and that it will print at a decent quality if you're going to be doing a printed project. Different applications have different needs—you can get away with different densities when printing depending on the size and use of the image. Test out different densities and see how they look. For printing, starting at 300dpi can be useful. And, of course, if you're going for a pixelated look to begin with, that's okay. After all, it wouldn't be a proper picture of Nessie or Bigfoot or a UFO if the image was in focus.

When it comes to images on screens, keep in mind that our desktop or laptop screens and our phones can have drastically different levels of image density. An image that looks awesome zoomed in on a desktop with a dated display will look awful when you zoom in on a mobile device with a high density display. Keep in mind that the size of the image, no matter the medium, needs to be scaled with the quality of image available and the space requirements you have.

When it comes to video, think about your composition and framing. Basically, remember that most people prefer video in landscape format for professional usage. Unless you're composing on Earth 2, please try to hold your phone sideways when you film footage. Just saying.

Images and video also introduce accessibility issues for some readers. To assist these readers, you'll need to give titles and alternative text for each of your images in digital deliverables. This alternative text will allow a screen reader to read to your user whatever you consider to be a good description of the image that you've provided. Usually you want to design your alt text to allow the reader to get from the image whatever you'll be using it for later in the text. If you don't do this extra work, folks with screen readers will have no clue what your images are.

Going along with the question of alternative text is the question of how to title and refer to an image, or a visual, in your document design. Generally speaking, you'll want to give a title to your images in a text that will be referencing them. You may call them Figure 1, or Figure 2, or Image 1, but you'll need to have some form of reference. This allows the reader to understand when you're discussing a particular image, and allows for easy navigation back to an image later on if you reference it again. In some contexts going without labels is preferred, but if you're going to reference an image a lot over the span of several pages, titles can help.

Finally, you want to make sure your image is actually visible and doesn't blend into your text. Often times when you include a photo with a skyline, for example, the edges of the image may tend to bleed towards white due to how the image has been exposed and balanced by your phone or camera. When you place an image like this on a printed page, you end up with a visual that blends into the document itself, creating issues with visibility and crispness. To avoid these issues, you can often using a simple border that is maybe 1 or 2pt in stroke. Something that contrasts with the background of both the image and the page can work—usually black will work. You won't want an overly thick border, but you'll be amazed at how much a simple stroke can change how easy an image is to see and how professional a layout looks.

---

This page titled [4.1: Document Design Essentials is Essential](#) is shared under a [CC BY-SA 4.0](#) license and was authored, remixed, and/or curated by [Adam Rex Pope](#) via [source content](#) that was edited to the style and standards of the LibreTexts platform.

## 4.2: Layout and Document Design

---

### Layout and Document Design

On the most global level, document design is all about layout. The design of a document is first and fundamentally controlled by the layout of the text and images on the page. Yes, the size and color of the text matters in how someone reads, as we'll get to in a moment, but layout controls what they encounter and when as they navigate in the traditional top-left corner and over and down manner. (And, if you're writing for languages that are right-to-left, from the top-right corner and over and down). Learning how to use layout to guide/assist readers is a fundamental skill for technical writers.

With that said, most word processing software doesn't really dive into in-depth document design as part of its core functionality. Instead, we tend to operate in a set of conventional document design presets that govern how we read and write everyday documents. When you open a word processor, you likely have a white page with black text, probably Calibri or Times New Roman or Cambria as your font, and your margins are usually set to 1 inch or so on all sides. When you type, the text fills the whole page until it hits the margin, unless you may use of tools like tabs or lists or indents. This is the world we're used to operating in, and while document design is possible in these types of environments, the freedom to determine layout isn't really baked into the fundamental operation of these traditional word processors. You aren't supposed to have to think about fundamental layout—you're writing.

When we take control of layout, much more is opened up to us. Many times a program truly dedicated to document design will simply open up to a blank page—there will be no places to write, there will no places to insert images. All of the choices are open to you, the designer. This can be a bit overwhelming at first, but you'll come to enjoy the freedom. You can place text boxes to house text, you insert frames for images, or just insert the image into the document and move it around. You can create custom paragraph and text styles as well as object-level styles that govern how and when text and images interact. The amount of choices you have are virtually endless.

Document design programs are designed as sandboxes for the creation of any sort of document you can think of rather than any particular type of document. The amount of choices they provide and the lack of handholding go hand-in-hand with professional work where you want to create your design rather than spend your time undoing someone else's preconceptions of what a design should start with.

This can be a bit overwhelming if you're new to things, and you may try to start reinventing the wheel, creating your own take on a fundamental document type from scratch. Try to resist that urge. If you're creating a document that you've never made before, find some examples of the document in the wild from competitors or internally. Look at what they've done that you like and that you don't like. Figure out which elements work for you, and bring them together in a unique design that borrows from a few different traditions. This is how design works—incrementally and building off older ideas. Sometimes you'll see older content brought back to the forefront as the next new thing. Sometimes you'll see existing content tweaked a bit for a new take on design. Designers tend to work to develop off of what is already here—it is much more rare to create something that is fundamentally unconnected to any previous design. Design is a conversation more than anything, and when you contribute to the conversation you're building on what has already come before.

If you can think of the flavoring you wish to give your design, you often start off in a much better place than simply saying, I'm going to create this type of document. I'll give you an example from my own development as a designer to illustrate this point. When I was a Ph.D. student, I met my future wife and we decided to get married. At the same time we were planning the wedding, I was taking a design studio course over the summer. Neither of us were happy with the traditional wedding program, so I decided—naively—to suggest that I could design it and get it printed at the local printer. At first, this did not work out well at all. I would go to my future wife with a design, and she wouldn't like it. I would go to her with another, and she wouldn't like it. A good part of this was related to my actions—I was trying to create something I had no experience with and with no conventions to reference. It was awful. This happened for a while before I realized that I didn't need to reinvent the wheel—I simply needed a new paradigm to view what I was doing.

I thought about who we were as a couple and what we had in common in our pasts. Both of us had many friends in theater when we were in college, and we both helped a lot with theater productions. I realized that what we could do was create a wedding program that was designed with the same visual aesthetic as a low-budget college theater's program for a play. Once I had this idea, which

my future wife loved, I had a much easier time developing things. I was able to use classic clip art to give it a retro and low budget feel, and I set up the “play” of the wedding as a love story. The exit song and theme of the program was “Ever Ever After,” so that tied in nicely. The different parts of the wedding were set up as acts and scenes in the play. Our history as a couple was the summary of the story thus far. And the back page, which I was particularly proud of, was the cast and crew—the wedding party basically—with headshots and short bios about each member and how they connected to the bride or groom. Having the theme, an approach that I could take to reimagine and meld two different types of documents, made all the difference.

So, with your layout work, don’t try to start with nothing and create something. Do some research on what is out there. Think about your goals, your audience, the use of your text. Find a thematic that works well and features that you like from elsewhere and blend them together into your own design that speaks in a particular design language that makes sense. As I’ve mentioned, you see this all the time. Ever noticed how phone design seems to work based off one hit design that gets copied and adapted just because? It works the same with material design and even architecture! Folks doing design operate in existing traditions and expectations. You can get rewarded for something novel, but that is extremely hard to pull off, and often outside the scope of what you need to do in any given project.

To flesh out the rest of our discussion on layout, we’re going to cover some fundamental ways of viewing layout and doing layout. We’ll look at the basic concept of stacking to create layouts and designs, we’ll discuss placement and purpose, we’ll discuss legibility and color, and we’ll discuss print concerns with layout choices (bleeds and such).

### Stacking—The Fundamental Design Tool

When it comes to doing document design, or any sort of visual design really, the concept of stacking is absolutely central to pulling off virtually any sort of complicated multi-element design. (And, if we’re honest, it applies to drawing and painting too, but let’s not go too far astray). Stacking is a way of viewing design, one that makes the process of breaking down and then creating or recreating a design much easier than trying to tackle a full image by itself. I’ll explain.

Let’s start with a terribly-drawn example of a carved pumpkin. I believe I’ve mentioned that Halloween is my favorite holiday, and thanks to the iPad Pro that I’m working on, I can draw you the world’s worst drawing of a pumpkin. (I promise I can do better design work on a pc with a mouse). This example will provide for us both comic relief as well as a brief insight into how stacking can be used to create document design effects when doing layout.

In this image, you see a pumpkin or something that looks like a pumpkin that has been carved for Halloween—but we need to move beyond seeing the image as a single entity to understand how stacking works. Normally, we would view this image as a single visual. The stem, the eyes and mouth, the banding on the body, the outline of the body, and the color of the main body are all seen as one. We need to instead see each of these items as a single entity that has been created through stacking several different elements.


Stacking works in layout and document design fairly simply, much like an old fashioned projector, you layer one visual element on top of another, creating a stacked effect that creates your final product. Crucially, you also operate in a stacking mindset, creating each individual level of elements on their own layer of the image. By breaking down the image into differing layers and stacking those on top of each other, you create a final image.



**A BADLY DRAWN JACK-O'-LANTERN**


In the example above, we actually have four different layers that are being used. First, we have a background image that is being used. In this case, we have a transparent background, so we can ignore that for now. Next, we have the actual shape of the pumpkin and its outline and stem as you can see on the next page.

This is all that we have on this layer, and if we wanted to be really process-driven, we could have put the stem on a different layer entirely. What this allows is for us to create the basic look and overall shape of our design element without having to worry about other elements.




**THE BASIC PUMPKIN SHAPE LAYER**

Next, you have a layer that consists just of the banding that you see on the pumpkin. In this case, I started with a solid black line stroke and painted that onto the pumpkin body from left to right. Once that was done, I lowered the opacity of the layer so it would be less harsh and look more organic—which I suppose is overkill when you're drawing the world's worst pumpkin carving. Once I was done, I was able to clean up by erasing any strokes that went past the edge of the pumpkin body. Because I was on a totally different layer, I didn't have to worry about erasing any of the pumpkin's body. This is another key advantage to stacking and layer-based design. Here is what this layer looks like alone:



**THE PUMPKIN LINE LAYER**

Notice that just the lines are visible here. That is all that is operating on this layer. However, due to the way that layers work, I was able to see what was below when I was doing my line insertion. The final product, combining the two layers, can be seen here.



**THE PUMPKIN AND LINES COMBINED**


Through the use of layering, you can see how the image slowly evolves into something that looks more and more like a terrible pumpkin. The complex design elements (ha!) are layered on top of each other, allowing you to tweak each layer independently without impacting the others.



**THE FACE**

The final step was to take the eyes and mouth and add them onto the pumpkin. This was, as you might guess, yet another layer that was drawn on top.

As you can see, there is simply a mouth and two eyes here. This was drawn with the advantage of seeing what was going on below, allowing me to line everything up. However, since the elements were all on their own layer, I was able to tweak them, erase the edges as needed, and redo them even without having to worry about the rest of the document getting altered. The end result, which you can see, was far from striking, but it does take advantage of this concept of stacking when doing document design layout.



**THE FULL EFFECT**

Each stacked element, from bottom to top, blends together in the final image to create a carved pumpkin. Each element is standalone, which means I can tweak the colors and the shapes quickly without having to do much work at all. If I want to have a bright purple pumpkin with a silly face, I can do that by simply repainting the coloration on the pumpkin, making the lines darker, and redrawing the face layer. In less than two minutes, I was able to get just such a result that you can see on the next page.



**A QUICK DESIGN REMIX**

Again, because of the leeway that stacking gives us when doing a design, we can quickly change the elements, move different elements and recolor them quickly, etc. Stacking really is the secret to a good layout! It also helps when you need to replicate something with slightly different looks over and over again. Think about my pumpkins above—I was able to create a basic pumpkin then riff off that design with the same dimensions over and over again, giving me a basic template for future pumpkins that could all fit into the same slot/spot.

Now most of our examples thus far have been with our outrageously bad pumpkin illustration. I started with that type of example because stacking is often the secret to creating complex logo elements and other pieces of technical writing that you may need to create from time to time. But, it also works for standard designs like signs and newsletters. You just need to apply the same paradigm and thought process to your work. Think in layers and stacks and you'll be able to break down virtually any design that you see and replicate it fairly easily. This also gives you any number of ways to find inspiration for a design because you start to see the various elements in the stack rather than the entirety of the image or document. You can borrow a few elements of the stack as inspiration and leave the rest.

Take for another example the newsletter template you'll find below. In this example, you have several different items stacked in simple layers. The background layer has all of the major color blocks for the header and the footer, then you have text on top of those layers one layer of text for the main text in the body of the newsletter. To create colored segments that are edge-to-edge, you simply need to draw a box or equivalent shape and then color it. That becomes a stand-alone layer and colors that particular part of the layout:



Here you get the effects of a simply-designed newsletter with a space for a photo in the center and a colored header and footer. A few of the elements could be aligned better, but the overall layout works as a newsletter. By making use of layers and stacking, you can create virtually any design layout you'd like by breaking down your intended final product into a series of independent layers. And, again, this makes recoloring and movement of elements easy because you're not constantly running into all of the elements at any single time.

### Placement and Purpose in Layout Design

Having looked at stacking, we now need to look at the central move we make when doing document design work—placing elements and using that placement to convey purpose. Whereas stacking is an approach to creating document designs, placement represents a type of choice we make with each individual element in our design. Where we place elements and the relationship of that placement to the whole document and other elements in the document controls the way our text is perceived and navigated.

When we view a traditional document, placement often determines the level of importance that we give to a line of text. Looking at the x-axis of the document, the further left or right an item is placed usually determines the level of importance in the textual hierarchy. If this sounds familiar, it is because we touched on this same issue when we were discussing taxonomies in chapter 1. Generally the closer to the left side of the document, the more importance something is given. The same also holds true to the y-axis: the closer to the top, the more important something is.

As we noted earlier in the taxonomy discussion, placement has a crossover effect—items that are placed in the same way and along the same line on an axis are considered to be of equal importance. If you have three images that are placed side-by-side in the middle of a page, you consider them of equal importance.

Going along with the idea of placement equaling the same value for different items, placement together also creates groups of items, groups that are usually read as being considered one unit to be read together. You see this in many texts where you will have a grouping of images or paragraphs. Each of the paragraphs or images that are placed together are considered to be equal and connected in some way because they share the same placement on a line in the x or y axis. See the example below for what this looks like:



In the above example, you have three different images of pumpkins on the same level of the y-axis. Because they are of equal size and on the same line, they are viewed as being of equal value to most readers. If you look at the x-axis alignment of the pumpkin images with the text that is below them, both the text and the image are on the same line of the x-axis. This creates an association that these two items are of equal importance and draws a connection.

In addition to simple alignment along an axis, the relative closeness of two items in a document matters as well. In the pumpkin example, the relative closeness of the text and the images suggests to the reader that they are part of the same item—they belong together because they are quite close. Each of the pairs is considered to be of equal value because they are on the same line of the y-axis, but they are not considered the same item because they are not quite as close together.

The end result is that we can use placement along an axis to indicate that items are of equal importance, and the relative closeness between two items along an axis to group them together visually, creating a unit within the text on account of the proximity each item has to its companion.

When it comes to placement, do note that subtlety is usually not something to be sought after. What I mean by that is simply that when you want to space items out or want to group them together, don't be ambiguous or subtle. If items are together, place them close to each other. If they are of equal importance, place them along the same line. If they are not together, make sure the distance is great enough that it doesn't appear to be a mistake—very slight variations in distance can be read as mistakes by an author rather than a differentiation between two different images. The same holds true for any types of placement that indicate value or groupings—if you make the differences between groupings or alignments slight, it can and will be read as a mistake. See the image below for an example of this:



**AN EXAMPLE OF BAD GROUPING**

In this example, you can see that the placement of the left and right pairings of pumpkins is almost exactly along the same line on the y-axis. There really isn't much difference between the two, and there is an awkward gap between them on the x-axis that just sits empty and open. To most readers, this is read as a design mistake because there is a very subtle shift in the placement of the images and a general lack of balance to the placement as well—the large white space doesn't sit well with us.

### Supplementing Placement with Size and Design Elements

To fix this, we would likely want to use a different alignment, but we can also supplement our placement using size and other tools. Generally speaking, the size of an item that is placed in a document correlates to importance, just like the size of a font usually connects to the importance of text in a document. In addition, much like with text, we can use lines and other visuals to underscore our choices in the layout placement.

Putting a line between grouped items is the equivalent of a line break or other spacing equivalent in text. The size and placement already indicates a relationship in the layout, but the extra elements underscore this as in the example below:



Here we have a massive size difference between the two pumpkin/text groups. On the left we have traditional colors for the pumpkin in a fairly large size. On the right, separated by a black vertical line but still occupying the same line on the y-axis, we have two additional pumpkins. This line exaggerates the importance or at least draws attention to the importance of the size difference and layout differences between these two groups. It also makes the two groups separate cleanly. The symmetry between the smaller elements size and placement also indicates they are of equal importance, but of less importance than the larger and left-most image and text combination.

### Legibility and Color in Layout


In addition to the placement of the elements of a design and the relative size of elements in a design, we need to consider the relationship the overall legibility of elements and the relationship in particular of legibility to color choices. While you can put a lot of great information into a document, that doesn't matter much if no one can actually read the information that you've placed in the text. Texts can become illegible for a couple of reasons including physical placement, size, and color contrast. We'll spend a little extra time discussing color because uses of color can cause text to be less obvious without necessarily making it fully illegible.

We cover legibility for practical and ethical reasons. If you've ever run into a document that had important information in a place that was hard to find or in a place that didn't allow you to read very easily, you understand the ethical issues with legibility. Sadly, there are some writers out there who have purposefully used the layout and design of their texts to make some information less legible or to hide it altogether. One fundamental question we have to ask ourselves regarding legibility is simply: am I making this text fit at the cost of readability?

One way we need to deal with legibility is just the physical aspects of legibility—where text is on a document and how conducive that placement is to use and reference. In some cases, you may have a text where certain parts of the document simply aren't that useful for prime information. For example, if part of your document could be exposed to excessive wear, you wouldn't want anything important to go in that space. (This might be an issue with a text that has a long life and gets referenced and used continually). You can also have parts of a text hidden by the physical structure of a document—content too close to the spine of a book can be unreadable.

We also want to think about the size of the text that we're placing and how that size impacts readability. When it comes to working with size, we want to be able to balance the overall amount of space that a bit of text is using with the importance of that text, the amount of information that needs to be there, and the legibility of the choices that we're making.

Not all fonts are created equally, as we'll discuss in our next major section on typography. One way we can measure/assess fonts is their relative x-height: the height of a given font's lowercase "x." X-height allows us to assess the general contrast between the height of lower-case and upper-case letters in a particular font. The closer the lower and upper case letters are in height, the more legibility a particular font tends to be at smaller sizes. This isn't universally true—some fonts are just hard to read at small sizes—but, it can be a great rule of thumb. So, if you need a font that will perform at small sizes, find one with a relatively small level of contrast between lower and upper case letters. For an example, see below:



**AN EXAMPLE OF THE IMPACT OF X-HEIGHT**

Here you have two different fonts, each set at 10pt. Notice that the top example is much easier to read at any level of distance. A major reason for this readability? The x-height.

When we're dealing with text in general, legibility concerns should lead us to try to never go below 10 point sizing. 12 point is a relatively common size for general paragraph text, and while smaller font sizes can be readable in certain contexts, going below 10 can cause issues for some readers. If you simply need more space to convey the information on a given document, you may need to either edit your information for clarity and brevity, or you may need to create a larger document or a supplemental text that can be referenced. (Though, the issue with supplemental texts is that very few of us are going to go out of our way to find and read them).

As a secondary issue related to legibility and size, we want to make sure our use of size is proportional to the importance of a bit of information to our users. We shouldn't go out of our way to make less important information super visible while hiding less important information—to do so is unethical and often causes no amount of frustration with readers. Have you ever gone to the store and seen a special and decided to go ahead and take advantage of it, only to get to the checkout and realize you didn't see the fine print that makes you ineligible to actually get the special price? If so, you've encountered this very issue! Depending on your mood, you may have rewarded the misuse of font sizing by just going ahead and getting the purchase, regardless of the sale price, but if you're annoyed enough you might just abandon your whole purchase. Without naming names, I can tell you that a certain local retailer with a national footprint has basically turned me off of all of their "buy X and get a gift card for X amount" deals for this exact reason. If I see those signs, I tend to ignore them—I've been misled too often and I'm too annoyed to mess with them.

To get around issues related to size and importance, simply make sure that any critical information is obvious enough on a quick read. If you've gone out of your way to make a special visible to a reader, make sure any common disqualifications are equally visible, or at least make sure the fact that qualifications exist is very visible. When possible, try to give all information regarding a subject equal billing, that way you don't risk annoying or misleading your readers by gating certain information via sizing. For example, a BOGO (buy one, get one) sale sign that doesn't let you see that the BOGO nets you a 10% discount is deeply frustrating to someone who assumed a second item was free or heavily discounted. In this case, we would want the tail end of the BOGO to show up at the same size as the rest of the text, or at least at a size that allows instant comprehension of the deal. In situations like this, the extra text placement simply makes sense—you can't assess the value of a BOGO offer without the final bit of information.

Having looked at physical placement, font size, and the size/importance connection, we finally need to cover the importance of color in layout legibility and readability. Color can impact the way that we process texts in any number of ways, each worth taking a moment to focus on. First, color can impact overall legibility of text and other elements. It can also impact the way that readers assess a text and associate a text with other information. Finally, color pose an accessibility concern that we need to be aware of.

When thinking about the legibility of a text's layout in regards to color, we want to think about how much contrast is available between a given text and that text's background. The traditional writing arrangement that we see when we fire up a word processor makes optimum usage of contrast by presenting us with a total contrast between a solid white background and solid black text. In a few cases we see this reversed for nighttime reading on a screen with a solid black background and solid white text. Regardless of which is used, the goal for both layouts is an optimum level of contrast. When moving beyond these two choices, we need to make sure our color choices maintain an acceptable color contrast in our layout.

When dealing with contrasting colors, the simple rule of thumb is to choose colors that different in their general darkness or shade—you want a lighter option to contrast with a darker option. Generally speaking, light text and light background shades don't go well together as in the example below:



With this example, you can see the horror that has been wrought by using a light yellow with a light blue background. These two shades are both too close in coloration to be of use to us.

One trick to finding useful colors is to simply use complementary colors—colors that are opposite each other on the color wheel. Any number of tools exist to select color off of a wheel-type selector, and all you need to do is choose from colors on opposite sides to create a level of contrast that is legible and often aesthetically pleasing as well. See the example below where we've kept the same general shade of blue but alternated the text with something complementary:



Notice that the orange shade is much more legible on the blue background, creating a much more attractive layout choice in general for text that should be easy-to-read.

Now, when it comes to color, this isn't to say that you should always avoid using similar colors! When you're creating a design, you may well want to use colors that are shades of each other or that blend well together. This can create aesthetically pleasing designs with the various elements of your text. You should only avoid having colors that blend together easily when you're trying to say something important to your readers, when you're passing along textual information.

In addition to general legibility, color often impacts the way that we read a text—it colors our interpretation. For example, if you're trying to associate a document with a particular brand, you will want to use that brand's colors. Think about the way we can identify someone's affiliation at a given sports event based almost entirely on the colors they are wearing—the same holds true for texts. Certain brands have iconic colors and iconic imagery—by using those, we're drawing on the associations and immediately impacting how someone assesses the text.

There can be issues when we misuse color to draw associations—you want to make sure your usage is genuine and not misleading, else you risk the ire of your users. No one likes to be deceived by a document and using color to imply something that isn't accurate does just that.

In addition to brands, colors also have seasonal and cultural associations. We've already highlighted how black and orange can signal Halloween, and the same can be true for green and red for Christmas in the US. You likely can think of any number of color associations you have with seasonal and local events, and the number of associations that go with these colors reaches even further

when we open up to an international audience. For example, Chinese weddings tend to make use of abundant amounts of red—white wouldn't be appropriate at all because of associations with funerals. At the same time, a red wedding in current US culture might draw entirely different associations with a popular television and book series. Color and culture have a close connection that must be researched and respected!

Next, as with size, you want to use the contrast and impact of a color choice to correlate with the information's importance that you're sharing. If you're simply creating a background element that makes the text nicer looking, there is no duty to make things stand out—blending in is a good thing. But, if you're relaying important information, you need to make sure that it stands out! Don't use your contrasting colors for unimportant information while hiding the important stuff with colors that blend into the background. Make sure your text stands out!

Finally, keep in mind that colors can pose accessibility issues to those with different visible color spectrums. Keep in mind that combinations such as red and green can be difficult to many readers who cannot differentiate between these two colors! While going into a full discussion of colorblindness accessibility is outside the scope of this current text, you should make sure to test your documents and identify issues with color choices that may impact your readers. For example, green and black can be a difficult distinction for some with colorblindness to make: my father's favorite pair of pants is a set of olive slacks that are his favorite pair of black pants that he owns. A growing number of design tools have a built-in testing tool for color accessibility—if those are available for you, use them.

Just like other audience issues, color needs to be researched! You need to be aware of any brand connections with your color choices, any cultural significance related to your colors when you're creating a text, and any barriers that your colors may present to those with color blindness and different views of the colors around them. This type of work is simply due diligence for us as technical writers. Colors send a message, and we want to make sure we're using them to send a message we fully understand and intend to send.

### Layout and Printing Considerations

One final layout consideration we need to tackle is the issue of printing, primarily an issue of bleeds and margins. If you've not done any professional printing, or at least any edge-to-edge color printing, you likely have no idea what I'm talking about. That's okay. We'll dive into the physicality of printing in this section and give you a brief boot camp on getting this stuff done.

Whenever you see a printed document that has color elements that go all the way to the edge of the page, you're seeing a choice that was designed around the physical nature of printing using bleeds. Edge-to-edge printing is not something that naturally happens in a production environment. You may have noticed with your own printers that you can't print all the way to the edge of a piece of paper—there is always a margin the printer simply can't touch. The same is mostly true for professional printing. To get around this, documents are printed on larger pieces of paper than the final product and then cut down to the actual size needed. Usually you pay per cut for this service, so if you had four sides of a text cut, you'd pay for the four different cuts in your run. (Note, this is for the full run, not per document).

The issue with cutting a text down to size is that cutting is not as precise as we'd prefer. There is almost always going to be some variability in the cut made by the printer. To get around this variability, we make use of a document element known as a bleed. A bleed is a small extra margin around a text where all elements that go to the edge of the final text will bleed off the normal page to a secondary edge of the text, usually one that is perhaps a quarter of an inch or less more than the standard edge. This extra area is the bleed, and is used to make sure if the blade cuts too far outside the document there will still be designed elements to keep the text looking as intended. The same is true for the opposite side—you generally don't want important information within the same margin of the bleed on the inside of a text's border either—the cut can be too far in either direction.

When you set up your document for these types of printing, you'll want to go into your document settings and create a bleed. The size of the bleed will depend on where you're getting the document printed—different places will have different tolerances they prefer. Once you've set the bleed, you'll want to make the printer aware of the bleed that will need to be cut off the text to reach the ideal size.

In addition to the bleed, you'll want to be aware of the binding's impact on your text. Any text that is bound by some sort of spine will have less room on the inside of each page for legible content. Too close to the spine of the text and your words will be lost in the page—especially on documents with a hefty spine.

This page titled [4.2: Layout and Document Design](#) is shared under a [CC BY-SA 4.0](#) license and was authored, remixed, and/or curated by [Adam Rex Pope](#) via [source content](#) that was edited to the style and standards of the LibreTexts platform.

## 4.3: Typography

---

### Typography

Having looked at layout, we need to next cover the subject of typography in document design. Typography is a massive subject, one that we could spend an entire semester on and still find ourselves lacking by some metrics. For our purposes, we will look at how typography impacts our work as technical writers and investigate the choices that we have at the level of typography to tweak the appearance of our texts and their impact. We'll discuss fonts and font families; the attributes of these fonts and how they impact our texts; choices of kerning, tracking, and leading; and font availability.

In general, I think we find ourselves in a world that is more aware of fonts and font choices than previous generations. We have entire documentaries available on the font Helvetica. We have folks that will instantly turn their noses at the usage of Papyrus or Comic Sans. Fonts and their names and impact are a bit more on our minds in popular culture, but these issues I've hit on only scratch the surface of what a font is and how we can view it.

For one, if we're going to be traditionalists, we should distinguish between a font and a typeface. Generally speaking, when we discuss fonts, we're really discussing typefaces. Typefaces are the full collections of the fonts of a particular family that share a common design. You may not realize it, but each particular variation of a font is often designed by a designer creating a typeface. There are separate variations for regular, italic, bold, and small caps, just to name a few. These variations are designed by the font's creator to maintain the font's aesthetic and legibility throughout. With that said, not all fonts have these options, or more correctly, not all typefaces have fonts with all of these variations. In those cases you may simply not have the option to bold or italicize or small caps your font—you're running into limits in what designer intended. Now, some programs will override this distinction and give you italics and bolding and small caps where none exists, but those options are usually less aesthetically pleasing and more likely to clash with the rest of the typeface.

Going beyond the distinction between typefaces and fonts, we could go into different traditions of fonts and font designs. Suffice it to say that we can see fonts in a couple of ways. Some fonts are historically designed and oriented—they are recreations of classic fonts that were used in a particular era by a particular printer or artist. In the case of book printing, the font may be based on a typeface that was used by a particular printer. In the case of comics or other visual texts, the font may be based on a particular lettering style. On the opposite end of the spectrum are novel fonts, fonts that are created by their designer within particular traditions but without a direct one-to-one historical target. We could go even further down this rabbit hole, but for our purposes this amount of awareness should work for us.

---


This page titled [4.3: Typography](#) is shared under a [CC BY-SA 4.0](#) license and was authored, remixed, and/or curated by [Adam Rex Pope](#) via [source content](#) that was edited to the style and standards of the LibreTexts platform.

## 4.4: Attributes of Fonts

### Attributes of Fonts

When we look at fonts, we often use the most basic of distinctions to decide the difference between two different competing typefaces. One may simply look better than the other to our eyes, but fonts have any number of fairly universally recognized attributes that we can discuss, as well as distinct personalities. Moving beyond simply liking a font to choosing a font based on its attributes and personality gives us even more ability as technical writers to shape the way our texts impact readers and the way that we research our projects.

First and foremost we can divide fonts by whether or not they have serifs, tiny little embellishments on the letters, often referred to as feet. Serif and sans-serif fonts as they are usually referred to, have different aesthetics that can be traced in any number of directions. Below you'll find an example of the two types of fonts, with serifs highlighted in red:




In the first sentence above, we see a sans-serif font. The letters terminate with solid blocky forms with no extra embellishment. In the second example, we see a serif font, one that has the small feet on the edges of the letters.

There are any number of claims made by various sources that about whether serif or sans-serif fonts are superior for different usages. The traditional line is that serif-fonts are best used for body text because the feet allow the text to flow together well. Sans-serif are used in this line of thinking as the headings and headers because they are stark and each letter stands out crisply. Some will also claim that electronic screens are best suited to sans-serif fonts, but there is conflicting research on this subject.


For our purposes, we want to be aware of these differences and use them rhetorically—to persuade and inform our readers. Because sans-serif and serif fonts have a clear visual difference, we want to use that difference to our advantage. We can use serif fonts for one type of information and sans-serif for another, correlating font type with the information type available. We can also think about the cultural character of each choice—serif fonts tend to feel more formal and bookish whereas sans-serif fonts tend to be more minimalist and high-tech in their feel in our current culture (that can change). We can take advantage of these differences and use the font family that best fits the aesthetic and audience we have chosen.

Going beyond serifs, we can also look at the x-height of a font and the behavior of ascenders and descenders in the typeface. As we mentioned previously, x-height refers to the relative height of the lower-case letter x compared to the upper-case letters of the font. The x-height of a font can be used to judge how well the font will perform at small sizes; in addition, a shorter x-height may look less imposing at a larger size if you're wanting a larger font without overwhelming the reader. Ascenders and descenders are, as perhaps the names suggest, the elements of a font that ascend and descend from the normal line of text. Letters like “q” and “p” and “t” can be tricky with fonts that have substantial amounts of descending and ascending characters. See the image below for examples of each of these elements:




You can see in our two examples that the x-height of the first sentence is considerably higher than the x-height of the second. This creates a font that takes a good bit of room on the line and page. At smaller sizes this can be very useful, though it can feel cramped at larger sizes. With each font you see the ascending “t” and the descending “q.” When the line spacing is tighter, as you see in the example, these ascenders and descenders with more exaggerated lengths can cause issues of legibility that we need to be aware of. The more ornate and exaggerated these elements, the less a font can be condensed with tighter line spacing on the y-axis. (Hint: this is called the leading and we’ll get to it soon).

In addition to the letters, we need to focus on how numbers are presented in fonts. There are generally two types of font that are of importance to us as technical writers, those with lining and those with non-lining numerals. As perhaps the name implies, non-lining numerals are those that don’t stay in an even line with each other. Lining numerals, on the other hand, line up nicely. The difference in readability is incredible and you’ll almost always want to go with lining numerals for technical writing that conveys a lot of numerical data. Compare the two examples below:



In this example, the first sentence makes use of lining numerals and the second uses non-lining numerals. You can immediately see the difference, with the second example using numbers that vary in their height and line placement. The first example is much more regular, creating a figure that can be referenced a bit easier. Lining numerals are to be generally preferred for passing along large quantities of data since they make reference easier. Non-lining numerals can be more effective for an aesthetic effect or to convey smaller amounts of numbers.


In addition to these attributes, some typefaces have what is referred to as a small caps font within the family. These small caps are a condensed version of the font in all caps that creates a more compressed yet readable variant of the font. You often see small caps in texts that will reference things like the scientific name of a particular species such as *vulpes vulpes* for a fox. With that said, not every font has an explicitly designed small caps—those that don’t are restricted in their access to this format or have a fake version created by the word processor you’re using. These fake version of small caps are often less legible and less distinct. See the example below for what small caps looks like when designed explicitly:



As illustrated above, small caps make sure of a smaller and slightly stylized version of the regular upper case font characters. These characters are sized close to the x-height of the font while maintaining the same general feel of the larger characters. You can see in this example that also lends itself to a slightly wider character as well.

Small caps can be useful for aesthetic reasons as well as practical and conventional uses. In the case of species names, you will often find the usage of small caps appropriate and superior to italics. Compared to italics, small caps stand out more and have more distinct characters. They are also more subtle than all caps, which in the present day are often associated with screaming or HIGH LEVELS OF EMOTION IN WRITING.

Having looked at the various attributes of fonts, we finally need to look at the collected impact of those attributes—the personality of a given font. In addition to having particular characteristics, fonts have an overall feel that makes them work in some situations and not work in other situations. Script-style fonts tend to feel more formal and antiquated or intimate whereas more bold and blocky letterforms seem convey an entirely different aesthetic. Decorative fonts, at the furthest extreme, sacrifice paragraph-level readability for a particular look and feel. Compare the fonts below and the messages they convey:



In the example above, the message is one of general sympathy that you might find in a card that would be sent after the loss of a fox. Each of the fonts above conveys the message in a different way with varying levels of appropriateness. The first example is blocky and modern feeling, attributes we don't normally associate with sympathy. The middle example is a script-style font and conveys the aesthetic we'd associate with grief communications. The final example is a decorative font that simply feels out of place and difficult to read—this font may have its uses, but full sentences of text is likely not the ideal choice!

Before we move on, I want tack on one additional note about fonts and symbols, and specifically symbol-oriented font families. You may have wondered in the past, like many of us no doubt, about the purpose behind the Wingdings family of fonts. Why do they exist? Who can possibly read them? The answer is simple: they aren't designed to be read. Wingdings and other symbol-based fonts, such as stylized fonts of the Greek alphabet that you might use in creating content for a fraternity or sorority, exist to provide high-quality and scalable graphical indicators that don't have to be embedded as an image. Instead, they scale in the same way that a font would and provide access to certain images without the need for embedding other content. They may not always have immediate uses to us, but be aware they exist and that you can browse them using the symbol insertion feature of most design and word processing tools.

### [Kerning and Tracking and Leading, Oh My!](#)

Having looked at the various attributes of fonts, we now want to turn our gaze to the ways that we can manipulate fonts for different effects. As with the attributes and personalities of a font, all of this work is done in service of the use we have in mind for a font and the way we plan to implement the font in our documents. Just like the attributes of a font, these manipulations of fonts can impact the way the fonts are received and the readability of the text that results from their usage.

Each of these attributes of fonts has to do with the relationship between individual characters and lines vertically and horizontally. By adjusting these characters, we can often fit a particular font into a particular use for a particular goal. Kerning and tracking and leading aren't necessarily something you'll be tweaking all the time—just like you won't need to constantly obsess about the x-

height of a font. But, being aware of these options for font adjustment can be the difference between a deliverable that is good or okay and one that is excellent for a particular usage.

We'll start with kerning, the spacing between individual characters in a particular font. Kerning is something that is often hidden from us when we're working with fonts in a standard word processor. Unlike other options that we'll eventually look at, kerning works on a letter-by-letter basis, adjusting the spacing of different letters until we're entirely happy with the way they're spaced. One reason that kerning is often overlooked is because the choices regarding kerning are normally baked into any given typeface that you make use of. The designer of the font, in laying out the different glyphs, will have chosen what the natural kerning will be of the font.

The most likely scenario where you'd want to regularly adjust kerning would be when you're going to be using a font in a way that it wasn't designed to be used—often at a very large size. This isn't always the case—some fonts are designed for signage rather than paragraph blocks of print—but, more often than not you'll find yourself wanting to tweak kerning after you've made something excessively large. With programs that are more design-friendly, you'll be able to choose between optical and metric kerning. Metric kerning is the basic kerning baked into your font, whereas optical kerning applies math to the spacing to give you a better spacing at larger sizes. The idea behind the optical option is that the default kerning just won't work as well at larger font sizes where everything gets exaggerated—especially letter spacing.

See  
what I  
mean?

As in the example text on the previous page, you start to see more issues with kerning using letters that need a good deal of elbow room, letters like “R” and “W.” These letters can be a real bear to work with because they have a larger spacing to begin with in the font's internal calculations, and the larger sizing means that those calculations get exaggerated effects at larger sizes. Some fonts will do better than others, but you'll likely need to switch to optical kerning or manually kern the letters to get the impact you want—usually a tighter text profile.

Take a look at the examples below: two different font options will be presented for the same font and the same text, one with tighter kerning at a larger size and another with a looser kerning at a larger size. See which you prefer for a headline:



In the above example, you have two different amounts of kerning between the two text groups, though my kerning isn't perfect in the second. The top example is the default kerning of the font I'm using at 150pt or so. Below it I have some placeholder text that you can use to see how well these would go with a body of text as a headline. Notice that the second example is much tighter and looks a bit more impactful—the lack of extra spacing gives the text more weight. The wider kerning doesn't work as well—it looks a bit too airy for a headline. Now, my kerning could be better: I'm not 100% happy with the gap between “F” and “o” in “Fox,” but the difference I think is fairly clear.

Besides using kerning to adjust for larger sizing, you may also want to use kerning for creative effect, altering the spacing on words to make them convey something different than they would with traditional spacing. An example will likely make this use a bit clearer, though my example won't be the best:



Here, you have the “her” of “together” kerned manually to create an emphasis on the “her” part of things. You might be able to use this perhaps in an instance where you're naming a brand or a product and you want to have an iconic wordmark that you can use for identification. It might look something like this:




Now, you may have already seen some issues with the way that I've done this. For me, I see that when you separate “her” from the rest of the word, “together” can be read as “To get her,” due to the way that the spacing makes us more aware that there are

individual smaller words in “together.” So, in this case it might not be the best idea to separate “her” with kerning because the final result might run afoul of my goal. That’s the risk we run into when we start kerning things to emphasize certain parts of words.

Having looked at kerning, we next want to take a step up to tracking, an approach to modifying text that takes the concept of kerning and applies it across a full word or more. Tracking is the adjustment of the space between all letters at once—instead of taking a one at a time approach, you do everything all at once. Tracking can be useful for tightening up a loose headline or header that has gotten too wide or for spacing out something that needs to fill a bit more space. Be warned, however, that tracking is a fairly blunt approach to spacing letters. You will sometimes find that tracking changes will make most letters look good while leaving a few letters looking awkward. These issues you’re running into with tight or wide tracking that becomes awkwardly wide or narrow for certain letters, they’re why kerning exists and why fonts are kerned in the first place! As a head’s up—many word processors will hide tracking under the term letter spacing.

As we’ve already noted, tracking can be useful to tighten up headlines as needed. I’ll even let you in on a little secret: I used tracking in my example above with the mayor-based headline. Practically speaking, it can be very hard to see differences between tracked headlines and manually kerned ones. In my case, as I noted above, the “F” gave me away slightly.

You can also use tracking in the other direction to give yourself more space when you need it to make sense. You may have seen this type of approach in certain word-based designs or posters that use extra space between letters to give an individual word the ability to fill an entire space. Below you’ll see an example of what that looks like with and without the extra spacing:



**AN EXAMPLE OF DIFFERENT LEVELS OF TRACKING**

In the above examples, you see two different approaches to the same wordmark design, one using tighter tracking, and the other using looser tracking. You’ll see in the top example there is an airy feel to things and the two different text selections hold the same general width. In the case of the second line, this takes a script that flows together and makes it much more spaced and less obviously a tight script font. Personally, I’m a fan of the first item—I think it works better as a brand as the letters stand out and are more aggressive in their presentation (though breaking up a script font that connects can be dangerous). The tighter presentation of the second example simply looks like text to me, text that has been made larger. What do you think?

Much like kerning, tracking can be used for these creative endeavors, or simply to fix the natural spacing of your fonts as you work with larger sizes. As technical writers you won’t be placed, normally, in the demanding position of a graphic design professional, folks who take knowledge like this of font design as a mere starting place for all that they do. However, having an awareness of the ways that you can tweak even down to the character and line spacing opens up so much more for you when you’re doing design work. There really is just about as much you can do with fonts and spacing as you can do with paragraphs and headings!

The final spacing term that we’ll discuss is leading, pronounced like the metal not the action. Leading refers to the space between lines, also known as line spacing. The classic term leading comes from the actual lead that would have been used in a printing press

between the different lines. For a fun font fact, upper and lower case letters are simply those found in the upper and lower case of a font collection. The name is based on the physical placement of those images. Here's an example of a simple press and font bin:



Leading, like tracking and kerning, can be used to shape the way our texts are perceived as well as the ways that they inhabit a space. As you create more space between lines, you give more space for ascenders and descenders to freely reach. Some fonts may well require you to manually adjust leading if they have an aggressive script that juts below and above the baseline, the invisible line that all type on a given line is oriented to. More space between lines can reach a point, however, where the lines cease to appear like they are part of the same text—they begin to break up into paragraphs or other structures. When you're using leading to give yourself more room, take care that you don't pass this invisible point of no return. See the example below for what different amounts of leading do to the same text:

<p>The unanimous Declaration of the thirteen united States of America, When in the Course of human events, it becomes necessary for one people to dissolve the political bands which have connected them with another, and to assume among the powers of the earth, the separate and equal station to which the Laws of Nature and of Nature's God entitle them, a</p>	<p>The unanimous Declaration of the thirteen united States of America, When in the Course of human events, it becomes necessary for one people to dissolve the political bands which have connected them with another, and to assume among the powers of the earth, the separate and equal station to which the Laws of Nature and of Nature's God entitle them, a decent respect to the opinions of mankind requires that they should declare the causes which impel them to the separation.</p> <p>We hold these truths to be self-evident, that all men are created equal, that they are endowed by their Creator with certain unalienable Rights, that among these are Life, Liberty and the pursuit of Happiness.--That to secure these rights, Governments are instituted among Men, deriving their just powers from the consent of the governed, --That whenever any Form of Government becomes destructive of these ends, it is the</p>	<p>The unanimous Declaration of the thirteen united States of America, When in the Course of human events, it becomes necessary for one people to dissolve the political bands which have connected them with another, and to assume among the powers of the earth, the separate and equal station to which the Laws of Nature and of Nature's God entitle them, a decent respect to the opinions of mankind requires that they should declare the causes which impel them to the separation.</p> <p>We hold these truths to be self-evident, that all men are created equal, that they are endowed by their Creator with certain unalienable Rights, that among these are Life, Liberty and the pursuit of Happiness.--That to secure these rights, Governments are instituted</p>
--	---	---

### AN EXAMPLE OF DIFFERENT LEVELS OF LEADING

Here we have three different takes on leading—the first example has aggressive leading, to the point that we barely get any text on the screen, the second example has an incredibly tight leading, almost getting to the point we don't want to read, and the third example has normal leading. Each has its own impact on the text.

In the example above, notice that one primary facet of leading is that it makes paragraphs more distinct as visual units when the leading gets smaller—you see the larger spaces between lines a bit better when the leading is tight, but those blur and almost fall away when you start dealing with larger amounts of leading. A slight reduction of the leading can tighten up a visual design, but larger amounts can have the opposite effect.

Practically speaking, you can use more leading in places where you may want to have a text annotated and worked on. Think about double-spaced papers that you might have been required to submit in the past: the number one reason these papers are useful from a practical standpoint is that if you're doing handwritten markup on a paper, grading with pen and paper if you will, then you have room for comments and changes. The same holds true for any type of editing work. However, outside of those constraints, tighter leading is more pleasant to read (at least to me!) and wastes less space and paper.

One point of caution regarding all of the types of typographical manipulation we've discussed: do not use these tools to simply make something fit where it won't normally fit. When you go to great lengths to wedge a text into a small space using tracking or leading, you're getting your text into a place it wasn't designed to fit, literally. In this equation you save space at the cost of readability, and the folks who bear the brunt of that readability will be your users. Don't do that to them, please.

This page titled [4.4: Attributes of Fonts](#) is shared under a [CC BY-SA 4.0](#) license and was authored, remixed, and/or curated by [Adam Rex Pope](#) via [source content](#) that was edited to the style and standards of the LibreTexts platform.

## 4.5: Font Availability and Ethics

---

### Font Availability and Ethics

Having covered a great many aspects of font design, I want to finish with a very short discussion of font availability and ethics. As you start learning more about fonts and what fonts can do when used in different ways, you may become quite aware of the limits of your font choice in your default working environment. Generally speaking, this is governed by your operating system choice—Windows and Linux tend to have less font choices than OSX, likely due to the classical heritage of Macintosh computers as designer-friendly spaces. To get new fonts, you usually have to find and download them or buy.

Font creation, like any other act of creation, is a lot of work. Font designers craft each and every individual character by hand and then go and create kerning for those designs and special characters and variations as well. There is a lot of work in this process, and just like any other creative professional they deserve compensation for their work. I say all of this to prepare you for a reality that you will encounter in any professional writing scenario: assets are not free, and many times they are not cheap for professional use.

For example, a professionally designed font might cost \$25 for a single license, but if you wanted to use it across multiple computers and with multiple devices, you would need to investigate a multiuse license. As we'll discuss a bit later when we talk about project management and intellectual property issues in technical writing, professional materials require expenditures if you're not going to create the assets you use yourself, and often the creation of those assets requires such a specialized skill set and equipment that you either have to hire someone internally or simply pay the fees associated with using the content you want. With that said, once you start thinking about all that can be done with \$250 image for a logo and a \$25 font, all of the money and interaction that comes from using these assets, the deal is quite reasonable.

With that said, there is a thriving world of open source fonts available for use, much like this textbook is open-access and free for anyone to read and use. As with almost anything open source, things can be a bit wonky and slanted towards a particular usage. Open source content is usually created by folks with a particular ideological interest for open materials, folks that believe that open is best (I suppose I'm closer to this camp than any as you might be able to tell since I'm writing an open-access textbook), and folks that are using open source for a particular usage as part of an organized effort or passion project. There are other permutations of course, but these are two big camps. The end result is that the same idiosyncrasies that come with these mindsets carry over into the assets. Just be aware that open source doesn't mean that you get the same breadth and depth of quality for free. It means that in certain cases you can get amazing content for free from passionate folks, and in other cases you get a good-enough effort that exists because it needs to.

With that said, you need to be careful of what you're getting into when you go looking for free or cheap fonts. There are individuals who will rather unscrupulously strip a high-end font and recreate it and release it open-source or as a low-end product to make a quick buck. These recreations aren't going to be as high quality usually as the originals and they won't reimburse the folks doing the amazing design and research work needed to create the font you've been eyeing. Be aware of these issues.

Generally speaking, you'll want to be able to trace any fonts or other assets that have a potential copyright back to their original holder, as we'll be discussing later on. The way that business and professional writing works, if someone uses a copyrighted item to make money there can be severe penalties for lost profits and lots of lawsuits coming your way. When you're working as part of a larger organization, they'll get targeted because they likely have much more money than you and they're the ones making the profit off the content that you appropriated without a license or permission.

However, there are many fonts out there that designers will freely offer to you with freeware licenses—if you're not going to be making money off the font, they'll let you use it without issue. These licenses can be helpful for many personal projects that you may have, allowing you to create content without licenses designed around commercial use. I've used these types of licenses many times and as of late I've tended to use fonts created by a designer that I know through our mutual appreciation of comics. There is a wide world of folks creating fonts and I think you'll find they are passionate and fascinating folks to work with.

---

This page titled [4.5: Font Availability and Ethics](#) is shared under a [CC BY-SA 4.0](#) license and was authored, remixed, and/or curated by [Adam Rex Pope](#) via [source content](#) that was edited to the style and standards of the LibreTexts platform.

## 4.6: Remembering those signposts

### Remembering Those Signposts

Alright, we did it. We got through document design! You've undoubtedly learned something from all of this, hopefully several somethings. With that said, you may be wondering in the back of your mind how this all will apply to you in a technical writing situation. After all, you signed up for a class in technical writing instead of a class in graphic design. At the very least, consider this content value added—if you never had this knowledge, you do now! At the other extreme, realize that this content is the very heart and soul of what it means to be a technical writer. The formatting and the presentation of the content you write has the same impact and resonance with readers as your choices in the actual words themselves. It all matters and impacts things!

Now that you have a firm grasp of how layout, color, fonts, and all the rest work, use them to make your documents wonderfully signposted and easy to access. You now have a cornucopia of choices to make use of to guide your reader through a text in a certain way or to create a text that lends itself to a particular type of usage. You have a toolbox full of new and at times creative ways of signposting your texts, and that's exciting! (At least it is for me!)

Here are just a few suggestions:

#### Signposting Tips

- Think about using color consistently through a document, syncing up with sections, the major colors of your organization, or the thematic that you're covering (green for green energy, etc).
- Analyze designs with stacking to create your own intricate logos and other effects through layering content to create a cohesive whole.
- Consider using layout to your advantage, creating sidebars with extra information for your readers that need it, while keeping your major text free of extra information that experts simply won't need to see.
- Choose fonts that sync up to your purpose with using them, allowing different fonts to serve iconic roles, instantly signaling to readers what they're going to encounter in a given section. (Though, don't use too many— that gets confusing, just like too many colors).

There are any number of things that can be done with the content we've covered—use this content critically and creatively to expand what you can do as a technical writer. I think you'll find that just this little bit of a background in document design can open doors to any number of possibilities you thought were outside of your reach previously.

This page titled [4.6: Remembering those signposts](#) is shared under a [CC BY-SA 4.0](#) license and was authored, remixed, and/or curated by [Adam Rex Pope](#) via [source content](#) that was edited to the style and standards of the LibreTexts platform.

## CHAPTER OVERVIEW

### 5: Writing in Genres

[5.0: Introduction](#)

[5.1: Genre Research](#)

[5.2: Popular Genres in Technical Writing](#)

---

This page titled [5: Writing in Genres](#) is shared under a [CC BY-SA 4.0](#) license and was authored, remixed, and/or curated by [Adam Rex Pope](#) via [source content](#) that was edited to the style and standards of the LibreTexts platform.

## 5.0: Introduction

---

Having looked at the general idea of technical writing, the relationship of technical writing to the user, the visual communication angle of technical writing, and the process of document design in tech writing, we next need to cover a major pillar of technical writing in the minds of many: genres. (This is the part where we talk about report writing).

When we work in genres, we're working in what are essentially categories of texts that have formed over time to mean something. We often run into genre when it comes to books and television, with some books or shows (or films) labeled with categories like "Suspense" or "Mystery" or "Comedy." We can also get much more specific, especially in television where there are very well-worn genres that have appeared over time, so you might run into a "police procedural," a very specific type of show. In the case of police procedural, you have a show that is entirely about the process of the police investigating a particular crime. The genre gives you a clue as to the general type of show or film you're going to watch. (Bear with me in this discussion—you may wonder why I'm talking about TV, but I promise it will all wrap back around in a useful way in a bit).

Genre, however, is not specific to the point that it controls everything about a production: genre is fluid and changes over time. For example, the police procedural of the earlier years of television with shows like *Dragnet* did not have a major relationship component to the show—it was just about the crime for the most part. However, if you made a police procedural today without heavy interaction between different leads and ongoing stories about the police and their lives, you'd likely have a flop on your hands. The genre has evolved and expectations have changed.

Many genres come with an expectation even that you'll have a sub-genre that will come into play to flavor the dominant genre. Think about police procedurals again—you have shows that are much more direct and serious like the various iterations of behemoths like *Law & Order* and then you have shows much more playful at times such as *Castle* or even shows that skirt further towards the edge of the genre (if they belong there at all) like *Psych* (A true gem of television, up there with *Star Trek: Deep Space Nine*, *Midsomer Murders*, and *Fringe*). In these cases, there is a general approach to the genre, but all of that is filtered through the general gist of the sub-genre, such as comedy. With very common genres like the police procedural we often judge these shows on how they take the genre constraints and then push them or subvert them with a secondary genre or a new approach. Very few shows gain success for being an ideal procedural—it's all about what they do beyond that framework that gets folks excited. Sorry *Dragnet*.


Now, let's bring this back home—all of what I've said applies to technical writing genres. When we think about a genre like a report, that term is just like a genre in television like a police procedural. The term itself gives you a general idea of what the document you're going to create might look like, but for the most part it is utterly meaningless if you're expecting the genre to give you a detailed insight into what your report should look like. Just like the television examples, the technical writing genres are not laws carved into the bedrock of reality—they are categories, fluid ones at that, that give you a general gist of the type of document you'll be making without really getting into the specifics of things.

Asking someone to teach you how to write a report or any other genre in the specific sense of what steps to take and what sections to include is akin to asking someone to teach you how to make a police procedural—they can give you a general sense of the expectations and permutations of the genre in a broad and classic sense, but they cannot tell you exactly how to write it. And, to go even further and hammer this point home, if I was to tell you how to write a report it would be at best a polite fiction. My idea of a report and your future employers' idea of a report would differ, and even the types of reports you'd write within the same organization would change over time. There is no secret bastion of knowledge where you can uncover the true secrets of writing the ultimate report, no secret recipe to follow for success across time and space. And to be clear, anyone who tells you different isn't being very honest. So, what are we left with? We are left with research. Imagine that. Didn't see that coming, did you? :)

Genre work, just like any other part of technical writing, relies on research to get things right. Report writing, white paper writing, grant/proposal writing, technical description writing, and any other type of genre you'd want to associate with professional or technical writing will always rely on the context that you're writing in and the expectations that surround you. That isn't to say that having a general sense of a genre is useless—it isn't at all! You need to know the general sense of the genre just to orient yourself and help identify it. But, expecting a general sense of the genre to guide you from start to finish is expecting too much from too little.

When you operate within an organizational context and you're writing a genre like a white paper or a report, you're often writing within a series of constraints that will guide your work. On one level, you have the general gist of the genre that will be guiding what is going on. Unless your organization likes to call things odd names (my niece, for example, used to call buzzards "pelican badgers" for reasons unknown to anyone), the general genre constraints will apply. At the same time, the formal history of the genre within your organization will come into play—how have people done this in the past, and how do they do it now? In addition, the physical format of your genre will impact what you do (is it a template, or is it something that you have more control over?). Finally, the audience and use of the document will come to play as well. This confluence of forces will shape the final format of your text, and unless your workplace has very strict rules on such things (and some do, I'll freely admit) there will be some movement between documents as to what the genre looks like and does.

When you think about researching your work in a genre, realize that each of these elements will play into the others to create a final version of your genre. In some cases one element may be more dominant—for example you may have a use or audience that is hyper-specific, such as a federal grant that asks for a series of employment documents and professional assessments of your project by subject-matter experts (such as an archival expert if you're getting funds to preserve an artifact or archive). You might also have an audience that is extremely formal or informal that will impact how you write, which may clash with your institution's existing culture—it gets tricky fast. Below you'll see the confluence of all of this mapped in a visual form for those that prefer to see rather than to read:



In each case, you'll want to query the general genre, the institutional practice, and the audience and use of your text to get an idea of what needs to be done.

For the rest of this chapter, we'll break down the discussion of genre into two major bits of content: we'll cover the general questions of research you need to carry out work on any particular genre situation, and we'll go through a top-level overview of a few genres and what you can generally expect in those genres. The real heart of the chapter will be the discussion of the research questions—they will be your guide in virtually any genre-dependent situation. The coverage of the various genres at the top level will supplement this by giving you an idea of what genres you might be called on to write and some general (subject to context) tips you might want to know when you're writing in those genres.

---

5.0: Introduction is shared under a [CC BY-SA 4.0](https://creativecommons.org/licenses/by-sa/4.0/) license and was authored, remixed, and/or curated by LibreTexts.

## 5.1: Genre Research

### Genre Research

When it comes to researching genre, as with almost all of our research that we've covered, it comes down to understanding the situation you're operating in and the expectations the situation places on you and the amount of freedom the situation allows you that you can make use of. The level of research needed really depends to a large extent on the amount of freedom that you have with the genre as it is designed physically. If there is a template, you're going to be highly constrained, but if there isn't a template you're going to get to have a bit more power. General genre, institutional practices, and audience and use still come into play in restricted situations, but in different ways than in a truly open context.

### Physical Context

Some genres have very little freedom baked into them—think about most of the forms you fill out when you visit a doctor's office—this is done by design to get a certain type of information and to control what gets recorded and what doesn't. Forms tend to be the types of genres that strive to be durable—the particular information recorded is there because someone somewhere has decided that it matters a great deal to them, though the value isn't always apparent on the front end.

Forms and other limited genres are useful because they create a set of data points that can be correlated across time and participants, creating a general sense of how things are working in the broader context as well as a sense of history in individual cases. Having a record of all of your vitals for example gives your doctor a sense of how your overall health changes from month to month and year to year. In fact, these types of ongoing records are vital in catching things like high blood pressure and other diseases that come on slowly at times.

The same benefits associated with forms also come with other genres that are highly regulated like grant and proposal applications. Many times these applications are highly specific to the particular project and agency that is offering money for projects or soliciting work. The categories exist because they matter in the rubric that the organization will use to judge the participants; they also exist because they help create a uniform standard for comparing the different applicants. Imagine how difficult it would be to compare different grant projects if the only universal requirement was that you send in a document describing your project—it would make valid project-to-project comparison much more difficult!

In contexts where you have very little control over the physical constraints that your text will work within, you may think that your job is fairly simple—you just fill in the data and move along with your life. That can be true in some situations, but especially in competitive environments where your text will be battling others that have the same constraints, the opposite is true. If you have five sections that are each limited to 500 words then the weight of each of those sections and the weight of each of those 500 words is exaggerated far beyond the normal weight that any given selection of 500 words would ever have. They matter because there is very little room for error or for elaboration. You simply must do the very best job you can with your allotment, and ideally you'll do a better and more persuasive job than anyone else writing under those same constraints.

In competitive cases, you need to focus intensely on the information provided about what is going on and how your text will be weighed. You need to be strategic in the deployment of every single word that you're using. Many times researching your audience and their description of these constraints can be useful, but you also stand to gain a great deal of advantage by having a clear understanding of the general expectations of the type of genre you're writing and an understanding of how your organization operates and uses these texts.

Because of the weighting power that forms have on what is valued and what isn't, the contents of any given form can have an incredible amount of sway over the politics of any particular writing situation. The form tells everyone involved what officially matters. Anything that the form omits or doesn't cover simply doesn't matter in the world of the form and making a case that it does matter means battling uphill against the form and those behind it. This is one of the reasons, by the way, that long term residents of bureaucratic systems are valuable assets and why institutional knowledge and history matters a great deal: if you know how the system works and what it values and why, you can craft a text that will get things done. If you don't have this knowledge, you may lack the ability to get a task done because you don't know the particular language and presentation that a situation requires to create value within a given form and institution.

One other aspect of physical constraints in the context of forms worth covering is the interaction that forms have with the level of freedom that those working with the forms have. Like any automated system, forms remove a great deal of power from those doing the work. At times this is very much the goal behind the entire system. In these contexts the value of individuals to the system depends on the expertise needed to fill out of form or run a system. The more work the system does and the less work the individual operating the form or system does, the more replaceable any particular individual can be. As you can imagine, many organizations and companies that chase after profit and other metrics that focus on data rather than people love the idea of replaceable workers. The less value a worker has in a given situation, the less power they have to negotiate for more pay, better benefits, and better working conditions. The idea here is that the less power workers have, the less they can demand and the more profit and other metrics that can be squeezed out of a given context.

In case it isn't evident from the rest of this text, I find this practice to be more than a little bit troubling. The true value in a given organization rests in the people that know how things work and what is needed for success. A system or form is only ever a poor substitute for those folks, but their value is often hidden to those that don't see the daily grind of the workplace. One pillar of technical writing is advocating for such individuals, allowing their worth to be more visible and giving them more agency. At the end of the day, people deserve to be treated as people rather than data points, and from a purely functional standpoint you'll likely have a better end experience if folks doing the work in a situation have freedom to develop and leverage expertise and are valued for that expertise. Sure you can get things done with less expertise and more automation, but the end result of that trade is you're blindly swapping money and metrics for the well being of people and hard-earned local expertise; that seldom ends well in the long run.

Having focused on the power of forms and limited context, we also need to focus on the physical aspects of production in genre. In some situations, you'll be working in a digital environment where everything will be accessible and readable via devices. In these contexts, color and length matter a great deal less than in a paper-based world. Knowing where the genre will be living helps you because it gives you a set of limitations in all your other research and choices. You'll want to keep in mind that the format you're allowed to take will limit things. For example, if you're creating a white paper that will be printed, you'll want to keep in mind what the length and color usage will do to costs. If you're creating a brochure to be passed out, there are severe limits on text in a traditional tri-fold brochure that will control what is possible. Physical context is the lens that filters almost everything else.

For assessing physical context, a few quick questions can be helpful to give you some guidance in your research:

#### Physical Context Research

1. Is there a specific form that I must use for this document/genre?
2. Is this an electronic document or a paper-based document?
3. What are the budgetary constraints of this project if I'm printing things?
4. Is there a physical format that must be followed, such as a tri-fold brochure?

There are obviously other things that you can and should ask, but these questions form a useful starting point for any investigation into genre.

### General Genre

In addition to looking at the physical constraints of a project, you need to investigate the general gist of the genre that you're going to be writing. We'll call this the triple-g of the situation. While the genre doesn't tell us everything we'd ever want to know and more about a given writing situation, and it certainly won't give us a set of concrete rules to follow, it can give us a firm understanding of the expectations that are generally out there for a certain type of text and what we need to do get our text recognized as a member of a particular genre (unless of course that isn't our goal at all).

For example, reports tend to report things and focus on providing information that is then used to inform decision making. The goal behind any given report is not simply to report findings—you're not just gathering data for the sake of gathering data. Instead, the report is being used as part of a decision-making process. Now, I suppose in some particularly vindictive contexts you might be generating a report for no other reason than the person responsible for your work doesn't like you and wants to make your life miserable, but generally speaking reports should have a role to play in deliberations. You may have already made the leap here, but in case you haven't, this then leads us to understand that with reports in particular what can matter a great deal is the types of

information that will be valued in the deliberation the report is going to contribute to. Your 150 page report on the feasibility of a water garden being installed across the middle of your corporate campus will be of no value if you don't build the report around the metrics and data that your organization's decision makers will respect (or take the time to create metrics and explain their value if they are foreign to the organization).

Understanding things like the nature of reports and why they exist is part of understanding the general gist of a genre: it doesn't tell you how to do something, but it often can tell you why that something is done historically. Understanding the general gist of things after getting a handle on the context can be valuable because it helps you understand the institutional practice you find yourself within. Once you get how reports work, then you realize that the particular focus in your individual context on the executive summary a little bit more—the decision makers involved apparently highly value the short gist of a project or simply can't be bothered to read longer projects that don't interest them after a quick skim.

One other aspect of a genre can be valuable in the general sense—the popular associations with the genre. For example, reports are usually not the sort of document that immediately quickens the pulse of your average individual. Yes, some people get quite excited about reports, but people get excited for all kinds of weird stuff. Generally speaking, reports have a rather dry and dull reputation. If you know that, you can go out of your way to counteract that in the structure and format of your text, as best allowed by other constraints. It is always good to know when you're going into a situation with a fundamental disadvantage.

To focus your work on the general gist of genres, the following questions may be of some use:

#### General Genre Research

1. What is the general definition of this genre?
2. What is this genre generally used to do?
3. What associations does this genre usually have?
4. Is this genre highly regulated or does it regularly support extreme interpretations?

Once you have this information available, you have another level of clarification and context to add to your investigation of the practices in your institution and the audience for your text.

### Institutional Practice

Once you've ironed out the physical constraints and the general gist of your genre, you need to take a long hard look at what your organization does with the genre you're writing within and how that genre operates in the context of your workplace. Just like different types of television series can be flavored by the broadcast network that supports them, or at least carry associations with audiences (think about the types of shows you associate with say HBO and Hallmark), genre and institution are linked. When you live and work within a workplace, you have to operate with the constraints that come along with it. You can certainly make an impact on how things are done, but that isn't usually something you have the power to do immediately without any dialogue or discussions.

For example, your organization may have an annual publication that it puts out for clients that covers major projects that have been completed this year and the benefits of those projects. It may be a weird hybrid genre, one that exists within your context as almost a take on the white paper. In the landscaping business, this might be a useful way to both celebrate the artisanship of your organization, create a sense of camaraderie between your clients, and could serve as the impetus for future work by clients that are on your list but haven't done much work lately. Think of it as the corporate equivalent of keeping up with the Joneses.

In the context of our example, there may be constraints that come with this genre. It may always have the same color paper with the same general length and same general types of material within. If the primary purpose of the genre is to get people to come in for more work, knowing that also helps because it gives you a sense of how your institution values the work and what will be seen internally as good work (which may not be the same as what is seen externally as good work on the text).

Even in cases where the physical constraints are already decided for your organization, such as with a call for proposals that has a very specific set of requirements, there may be a historically successful or required template within your organization, a certain way of doing things. In that case, knowing how things are normally done helps you understand when and where you need to

advocate for different choices and whether making certain choices is a wise use of your political capital. There is no use burning through the good will you've developed in an organization just to get a minor change to a document that really won't matter.

For our purposes, the following can be some useful questions where querying your institutional practices:

#### Institutional Practice Research

1. What does this document normally look like and contain?
2. What is the purpose of this document for our organization?
3. Which parts of this document are highly valued internally?
4. What is the normal workflow for producing this document?
5. If there are external constraints, how are they normally addressed?

These questions can give you a great starting place in your work, allowing you to figure out the particular expression of this genre in your workplace and the way the document is put together, why it is put together that way, and the workflow behind it that you may very well need to respect (such as letting the CFO see your draft before you get it edited because they have strong feelings about the text). Again, this is one more level of clarity you can gain in viewing the process you're going to carry out, one that helps you put the final level of research into even more specific of a context.

### Audience and Use

The last level of context that we'll cover is the intended audience and use. All the other levels of context inform our process, but the final layer of complexity comes from our use and the users of the document. This level differs from all other levels in that the user and use are often going to be without an advocate in the design process, unless the process has been explicitly designed around them from the start. Because of this one-directional workflow in many situations, your job as a technical writer is to gather as much as possible from this level that exists outside of your production process.

There are many documents out there that are visually gorgeous, make sense within a particular genre and physical context, and match up with what a given organization does, yet they fail to engage and serve their audience and assist in the tasks they're associated with. This isn't to say the other influences don't matter—each and every influence on a genre matters a great deal. But, of all the constraints on a genre, the audience and use are the most likely to be successfully ignored, that is they are the most likely to cause no consequences if ignored during the production pipeline. They don't so much create issues during production as much as they create issues after you're already out the door with a deliverable and it's too late to make changes.

Keeping in mind that audience and use can cause an otherwise successful document to fail, you can present alterations from this level of context from the viewpoint of a return on investment in the overall document creation process. You don't want all of this great work going to waste because the final audience didn't sit on the same level as the folks doing the writing and approval. As with any audience-centered process, you may run into pushback and need to scale back your goals until you can prove your point about audience/user information being valuable in the workflow of your group. But, I think you'll find the contributions this level of context brings can't be understated.

To research the audience and use, we'll primarily be walking along the same path that we traced in our earlier chapter on audience, but I'll narrow those down a bit for our discussion of genre in particular:

#### Audience and Use Research

1. Who will be using this document?
2. Who will be assisting the users of this document?
3. How will they be using the text?
4. How will their use differ, if at all, from the normal use of the genre?
5. How will the user's context impact their use of the text?

Once you have this information in hand, you'll be able to bring all of the various genre influences together into a single discussion. Keep in mind that the audience factors and use factors will be those that you may need to advocate for the most strenuously to those that are production-oriented rather than audience-oriented.

### Bringing it Together

Once you've built out a picture of all of the influences on your genre, you can start to plan your actions accordingly. You may find it helpful to create a table with information on each level of influence, giving you a broad view of what is going on and what the various stakeholders and forces on your work may be pushing for.

One thing I want to stress is that this isn't a process that should always come into play when you're writing. Once you really get a genre, you will find yourself pushing through the writing process much quicker and with more surety. You'll simply get things down and not have to worry about the specifics as much. You may eventually even get to dictate the specifics as someone with greater political power in your organization. Now, that isn't to say you shouldn't be critical of your work and reflect on it on, but by the very nature of how we learn to use genres and make them part of our workflows, this will be something that fades over time as you build your own expertise.

However, you will want to follow this process, or your own loose adaptation of this process, when you're working in a new genre and a new context. Correctly performing a genre for all of those involved is a crucial step to gaining acceptance for a text. You can't expect your report to be taken seriously if no one believes it is a report.

---

This page titled [5.1: Genre Research](#) is shared under a [CC BY-SA 4.0](#) license and was authored, remixed, and/or curated by [Adam Rex Pope](#) via [source content](#) that was edited to the style and standards of the LibreTexts platform.

## 5.2: Popular Genres in Technical Writing

### Popular Genres in Technical Writing

Having looked at a method to investigate genres, I want to shift our focus in the back half of this chapter to introduce you to a few specific genres in the world of technical writing. This will be a brief overview, giving you a window into what the general gist and goal of these genres tends to be in my experience as a writer, instructor, and researcher. Please note that between cultures and companies these documents may be drastically different—these are really just some popular conceptions of the genres themselves. To really dig into what they look and feel like, you'll need to do some original research. Surprised? Probably not at this point in our text.

I'd like to briefly cover some key players in technical writing circles: proposals and grants, white papers, reports, technical descriptions, instructions, and manuals. This is by no means an exhaustive list of genres—you'll find an almost endless supply of them out there. This is also by no means a definitive definition of each, but I think each overview will give you a window into the ways that these genres work and the types of problems they were invented to solve.

### Grants and Proposal

Grants and proposals are one of the most action-oriented genres that you can work with in technical writing, though they often also tend to be some of the most rigorously defined by forces outside of your control. A grant or proposal often comes from a specific solicitation by a funding source that is either looking for a particular project to be completed for them or looking to support projects that complete certain goals.

In a corporate context, proposals will be solicited for various jobs an organization might need. For example, I might put out a request for proposals and bids to create a new computer lab infrastructure in my building on a college campus. In this case, I'm soliciting folks who will complete a particular task and tell me how they'd go about doing that and what their budget would be, guided in all of this by my own suggestions and guidelines.

The world of grants can be quite different because grants are often not designed for a particular activity: they are instead designed to promote a type of activity. For example, there might be a civic beautification grant available in a large metro area that solicits projects from local artists to create public artwork that enhances the town and tells part of the local story to those that interact with the art. For the funding agency, giving these grants out is a way they can encourage and bankroll a particular type of activity without actually completing that activity themselves. It offers a way to make use of funding to influence activities without jumping into the business of doing a particular activity or pushing for a particular cause.

In some cases, grant funding agencies have a very particular set of values that they advocate for, or a very particular way of having projects completed, such as mandatory partners on a project. Be aware of these goals and values—they may not always mesh with your organization's values and skills. Almost any grant funding organization has an agenda for their funds, and it is entirely fitting that they would—it is their money after all. Just be aware of this and the issues it can raise. (For example, getting funds from some organizations may be more politically hazardous in certain areas than others, such as getting funding from an organization that supports charter schools and school choice in an area that is strongly against such measures).

Generally speaking, a grant or proposal has a few major sections, though the sections will always be contingent on the funder of the task at hand. The call for grants or proposals will tell you what should be submitted, what is needed, and sometimes will give you an insight into what matters and why. You simply must follow these recommendations. They are not optional! When a grant or proposal is judged, it will be judged by these rules and recommendations. Anything that doesn't fit will be discarded—an easy way to winnow the pile of applications.

Your goal with a grant or proposal is to show how you'd fulfill the goals of the call for proposals in a way that meets the needs of your funder. You need to show you understand the current situation, that you have a clear plan for action, that your group is competent and trustworthy for this type of work, and that you have a legitimate budget and timeline. Beyond these you may have some specific sections and deliverables requested, but usually any grant or proposal will give you a chance to talk about these types of subjects.

A good grant or proposal has a narrative structure. This doesn't mean that it's suddenly story time and it was a dark stormy night. What I mean is that you'll want to have an overarching narrative and theme to your work. You will frame the problem in a way that

makes sense for your solution. You'll frame your past work in a way that shows your ability to complete this current task. In short, you'll be persuasive. There are any multitude of valid and honest ways to tell the story of a grant or proposal; you'll just need to pick the right one for your situation. Again, this isn't a call to stretch the truth—lies and misdirection in a proposal is a great way to get into legal trouble or blacklisted. Instead, this is a reminder that your presentation of “the facts” is not enough.

You need to think about the context and who you're writing to and why. If you're offering new technology, you can frame the current technology as out of date. If you're offering green technology, you can frame the current technology as excessively energy intensive. Each of these frames is a valid one, but the pairs I've created make more sense than framing the current technology as outdated and offering green technology or framing the current technology as inefficient and offering new technology. Remember that this is a competitive genre and you need to make the best and most accurate case possible for your team.

When you're looking at how to frame things, look for what your organization values, what you've excelled at, and what the funding group values and what they excel at and ask for. You'll often find a way to draw connections between your group and the funding group. In some cases you won't be able to make many if any connections—this can be a sign this grant or proposal is a bad fit.

As a final note, and one that goes with all genres that we'll discuss—do not use boilerplate texts. Don't create a generic grant application and send it to everyone with a few names changed. This is a great way to fail at grant and proposal submission. No one likes boilerplate texts and boilerplate texts are incredibly obvious in their overly generic approach to everything. Take a little time and customize your texts to the situation and you'll go much further!

### White Papers

White papers are an odd genre, one that is not universally present in professional communication, but one worthy of noting. At its core, a white paper is a sales document, one that is designed to motivate someone to make a purchase. What is intriguing about a white paper in our context is that they are usually designed to educate someone enough to make them desire your current product or service. You can and should make a pitch for your organization, but usually after educating someone as to why it would be of value at all. (Note: white papers are not the same outside of the US. You may run into other documents called white papers that are totally different. Cultural context matters!)

To help explain how white papers work, I'll give you an example from my own background. Growing up, my father was the third generation owner of the family tire repair business. When I was younger, the primary work the shop did was the repair of damaged tires and the purchase of new tires. You could also get maintenance work like balances and rotations. At the time though, oil changes weren't even on the menu. During the 90s, my father started getting white papers from companies selling machines for front and rear wheel alignment. These white papers came with informative models that you could use to demonstrate what an unaligned tire would do to a vehicle and generally educated you on the value of wheel alignment on the life of your tires. It also made the business case for wheel alignment and advocated for a particular machine from a particular manufacturer. After reading the documents and talking with sales folks, my father purchased the machines and from that point on his business had wheel alignments as a service.

In the context of the 90s, wheel alignment wasn't something that a traditional mom and pop tire shop would have covered. It required specialized equipment that was not cheap, and it required special training for operators of that equipment. Getting a mom and pop shop to buy the expensive equipment directly wasn't a winning strategy—the price alone could spook people. Instead of making an immediate sales pitch, white papers and strategies tailored around education allow the manufacturers of this equipment to explain the importance of and sales potential of the machinery in order to help the audience to get to a point where they understood the technology enough to make an informed choice.

White papers are often used in areas where technology is advancing in a way that needs explanation. If you're offering a new piece of software or a new type of service, you may very well need a white paper to make the case for your approach. White papers don't make as much sense in established areas with established technology that you're going to be selling to folks. If you have a new spin on that technology, maybe a white paper makes sense. Otherwise, it's not going to be that useful.

### Reports

We've already hit on reports, and so I won't spend that much time on them here. Suffice it to say that reports are documents that give someone information on a process or series of events or a plan, anything really, and then allows the person who has that

information to make decisions or advocate for decisions or courses of action. If you want to blame someone for reports, blame a business major—a large part of the logic behind business majors is that they are experts at decision-making in business environments, aided by reports as part of their understanding of what is going on and what they should be doing. The rise of reports came along with the rise of the professional business major, allowing information to move beyond people and into paper and other sources.


With any report, ask yourself who is going to be using this document and what they're going to be using the data for. This can vary depending on who is reporting and why. You may be tasked with a feasibility report on a project—in this case, you'll be creating a report that helps decide what actions are available and whether they make sense. You can also see reports generated by openly or not-soopenly political organizations that have very particular values and goals behind their reporting. Not all reports are created equal.

When reporting anything that carries a value judgment, the most important thing you can do is create a set of criteria. If you set up the criteria and define them, you can have a productive discussion because you're making a case for what measures matter and then using those measures to make a judgment call. If your audience agrees with your measures, all the better. If they don't, you'll need to make the case for your measures. Without criteria, your report mostly stands as opinion. I have an opinion, and you have one too. Opinions are great, but when we judge them based off specific criteria we can debate on, we can have a constructive dialog. If we're just railing at each other's opinions with no overarching context to create judgment and value, we're not going to get far. (Just watch some political talk shows and you'll see this in action very quickly).

### Technical Descriptions

A classic of technical writing that is often associated with engineering, technical descriptions are fairly self explanatory—they are a technical explanation of how a particular system or device works. The use case for descriptions can vary, depending on who is going to make and share the description. For example, there is a thriving online world of folks that reverse engineer and build their own guitar pedals (effects devices that modify signals for distortion, compression, modulation, etc.). A large part of this community is sharing how a particular pedal works and what the components are within a given pedal, so they share a lot of domain-specific technical descriptions.

Technical descriptions are one of those genres where you may well get a chance to really get into using your field-specific terms and language because they are designed, often, for folks that are already experts or who at least know enough to read through the text. This isn't always true, but it can be many times. Here is a simple technical description of how the LED connects to a guitar pedal, badly drawn by your author:



Now, this particular technical description is entirely visual—that isn't to say that all technical descriptions are, but you do find visuals as a component in the genre. This is a particularly awful description because of my color choice on the black wire between the LED and the switch—you notice it overlaps the minus symbol, making it unclear as to whether it is positive or negative. In addition, I've neglected to include a resistor in this schematic, making it very likely my LED will burn out quickly and be ridiculously bright. But, this crude drawing could very well accompany some text like the following:

“In this pedal the LED is connected directly to a wall-mount power supply input. Not pictured here, a resistor is located between the power supply and the LED, regulating the output of the LED and preventing premature burnout. The ground of the LED

connects to the foot switch—several other grounds from the PCB and the input connect here as well.”

In this simple explanation, you get an idea of what is happening in the design. This isn't very technical, but it does tell you what is happening in this particular system of a pedal. That can be enough in the hobbyist's world where you simply need enough understanding to make things happen electronically without mishap. In the world of electric engineering, this would likely be entirely insufficient. Audience and context matter.

Anytime you're going to describe a system or a process, technical description as a genre can come into play. It isn't the most glamorous genre, but it has a useful purpose and helps folks understand how things work.

## Instructions

It's come to this. Instructions. You knew they were coming, right? If any genre is associated with the teaching of technical writing, the genre of instructions would be the one.

When we think about instructions, we want to think about them as tools for use—not those things you throw away because you don't need them or can't read them. Instructions get a bad wrap because too often they are designed as an item in a checklist that needs to be completed rather than as an essential part of any project that is oriented around sequential tasks. Good instructions can be a true joy to use, but we so often end up with the phoned-in-at-best variety that perhaps has lead many of you to despise the genre.

Time for a brief confession—I truly love instructions with all of my being. To the very depths of my soul, I love instructions. Why, you may ask? They help you do things. They tell you how things are supposed to be done. They put order into a situation. I like following instructions and I like making them because of this. I find special pleasure in good instructions that are thoughtful and useful, like so many are not. I like instructions because they take a process that might be challenging or tedious and make it easily understood and perhaps even educational. (As a side-note, I'm also a huge do-it-yourself person having built my own computers since I was a teen and having most recently tiled my bathroom floor after some intense research. I like learning about things and how to do things and instructions make that possible).

The biggest challenge with instructions is one of perspective—you often don't see a task that you're good at correctly. Think about starting a car and putting it into reverse or putting your key into your lock and unlocking your front door at your dwelling place. These are tasks that you do all the time, and as such you tend to internalize entire steps to muscle memory. It's kind of like when you start walking or driving somewhere and accidentally end up going to your normal destination when you meant to go somewhere else but managed to get a little absent minded. Instructions often suffer from this phenomenon because they internalize and omit steps that are essential to newbies.

The best thing you can do is to take a literal approach to your instructions when testing. If they don't say to do something, don't do it and see what happens. You may find quickly that you're overlooking key things like pressing the brake pedal when you shift from park to reverse when driving. This type of testing will get rid of your blind spots by forcing you to run into them.

The best thing you can do outside of personal testing is to find someone who truly doesn't understand what you're trying to explain. This can be hard with simple tasks, but if you can find a test subject or four you can find out quickly through various research methods what is going on and where things are breaking down. The final chapter of the text offers you a number of solutions.

Finally, remember that the best instructions offer a clear view of the process that is taking place and how each step comes together as part of that process. You'll find folks have an easier time with things when they know where they are going and what their progress is. In addition, useful illustrations and even things like color coding of steps and repeated processes can make things much easier for anyone actually using your work. Remember—instructions are used to do something. Make sure they are designed around that use!

## Manuals

If there ever was a genre that was the opposite of glamorous and exciting, I think manuals would be that genre. Manuals get a bad rap I think because they aren't designed for reading, and we tend to judge most large texts by their readability rather than other metrics like use. Manuals are a reference tool rather than a relaxing read to pore through while you sit in the hammock and sip

lemonade. They are designed to be searched to find information about a specific part of a process or system or procedure or to solve a particular problem.

Manuals should be judged by how they help you fix an issue or understand something, not by their capacity to entertain. For example, if you have a flat tire you'll reference your car's manual to find out where your spare is and where your jack is located (if you have one instead of a can of flat-fixing goop). You might also use a manual if you need to know how to format say, a television show when using Chicago style.

Like instructions, manuals can be annoying to use because they can be designed as an afterthought. We've almost trained ourselves in many circumstances to avoid manuals, and that can be a huge mistake! A good manual can be a powerful tool to help you through a complex process.

Practically speaking, think about a manual in a professional capacity as a barrier against having to do tech support of some type. A good manual helps folks understand systems and troubleshoot common problems without getting overwhelmed. A great manual does this in a clear, well-documented and illustrated way that allows easy identification of information that is helpful and avoidance of information that isn't helpful.

---

This page titled [5.2: Popular Genres in Technical Writing](#) is shared under a [CC BY-SA 4.0](#) license and was authored, remixed, and/or curated by [Adam Rex Pope](#) via [source content](#) that was edited to the style and standards of the LibreTexts platform.

## CHAPTER OVERVIEW

### 6: Managing a Project

[6.0: Introduction](#)

[6.1: Ideas, Audience, and Goals](#)

[6.2: Working with Others \(Inside and Outside the Team\)](#)

[6.3: Prototypes and Iteration](#)

[6.4: Rights and Images](#)

[6.5: Editing for Publication](#)

[6.6: Publication](#)

[6.7: Closing it Out](#)

---

This page titled [6: Managing a Project](#) is shared under a [CC BY-SA 4.0](#) license and was authored, remixed, and/or curated by [Adam Rex Pope](#) via [source content](#) that was edited to the style and standards of the LibreTexts platform.

## 6.0: Introduction

---

In our final cohesive chapter in the text (the final chapter is broken up into stand-alone discussions of method) we will be going through the process of planning and then delivering the final goods on a given technical writing project. As we go through this chapter, we'll draw on content from almost every chapter that has come before while also charting new ground in our discussions of things like idea generation, collaborating with folks inside and outside your team, prototyping and iterating, assessing and acquiring rights for materials, editing the final copy of your deliverable, and putting things into production and distribution. It's a lot, but we'll get through it!

In our discussion of each step along the way of getting a project out the door we'll be working through this tremendous task in phases. Just like with the writing process, these phases may be highly abbreviated in situations where you know what is going on and you're working with folks that you and your process. With that said, you will sometimes need to complete a major technical writing project from start to finish, from idea to final deliverable. In those situations, you need a plan and need a firm awareness of what is going to happen at each phase and when you need to move on. Take these phases as suggestions and guidance that can and should be tweaked situationally.

---

6.0: Introduction is shared under a [CC BY-SA 4.0](https://creativecommons.org/licenses/by-sa/4.0/) license and was authored, remixed, and/or curated by LibreTexts.

## 6.1: Ideas, Audience, and Goals

### Phase 1: Ideas, Audience, and Goal

Getting starting on any technical writing project, you need to have a firm awareness of what exactly you're doing and who you're creating your final deliverable for. When we think about projects, we want to think in terms of deliverables—what will you deliver to your client(s) at the end of the day? These clients may be your boss, they may be someone outside your organization, they might be your instructor or thesis or dissertation committee in an academic context. In any case, you need to know what you want to deliver, who's going to get it, and how you're going about all of that.

Deliverables and audiences and goals intertwine considerably—depending on what you want to do and who's going to be the target, what you want to create may change. For example, you might be creating content that you want to market to skateboarders for a ready reference. If you know much about skateboarders, you may know that in general they stereotypically love stickers, especially stickers that they can decorate their boards with. If you're trying to get awareness of say, concussion symptoms, to the broader community of skaters, a cool looking sticker might make a lot of sense. That deliverable fits that community.

### Sketching out Goals, Deliverables, and Audience

When you get started, you want to think horizontally across categories. Don't get trapped in audience, goals, or deliverables. Think about how each of these interact and the constraints that each puts on the rest. Using something like the chart below (which can be drawn easily on a whiteboard for collaboration), figure out what the constraints are for your project:

	Goals	Deliverables	Audience
Requirements			
Preferences			
Things to Avoid			
Things in Common			

**A TABLE FOR WORKING THROUGH GOALS, DELIVERABLES, AND AUDIENCE**

Think about each of these sections as being a supplement to or new way of thinking about the existing writing process that we've discussed previously. When you work with a project, you need a broader lens than the specific writing process you may have—your projects often will transcend boundaries that individual work won't come close to touching.

When you think about goals, think about your team's goals, your project's overall goals, and any goals that may exist outside of your particular team and project that may come into play (such as an organizational goal to reduce carbon emissions). For goals, think about what is going to be required, what would be preferred, and what should be avoided.

After thinking about goals, start thinking about audience—what will your audience require, what will they prefer, what will they want you to avoid (or should you avoid with this group) and what might they have in common with your goals/group? Again, this is part of the larger writing process, but you're trying to think long-term about a large-scale project.

When you assess deliverables, you are creating a space that will bridge your goals and your audience. The deliverables are a place where each group will impact what goes on, and in many ways the deliverable is the mediation of the audience and your team's goals. Each side has some say about what happens in this slot.

Don't take the above as the definitive version of what will be happening in your project—think about how the above can be used to think through the project you have, giving you something to work with as you advance to your ideas phase.


### The Idea Creation Process and Theming

Once you've got a handle on your goals, audience, and deliverables, you'll want to start to think about the format and form of these deliverables. Knowing that you want to create something doesn't tell you how to create that something. Just like the example we had previously of the wedding program, you often need to have an angle or a thematic that will guide what you're going to create. The idea creation phase of things, which can happen concurrently or after you've assessed the audience and deliverables and goals, tries to figure out what this project can/should look like and how it can all fit together. A lot of the ideas phase can be visual design work, but don't forget that visual design can also include the actual format and medium of your final deliverables. Large-scale projects like campaigns to build awareness for an event or issue often can contain documents of a variety of types and formats, but these documents tend to be bundled together using a cohesive theme. You see the same thing many times with university campaigns that will color the way a university presents itself for the duration of the campaign.

For example, you might be tasked with creating a public-awareness campaign about a new park that will be built in the center of town. To do this, you would need to create a variety of texts such as flyers, emails, radio spots, banners, and signage. The overall theme of your campaign would need to mesh with the visual identity of the city and attract the particular audience you're aiming to bring into the park. For example, if the park has a central venue for hosting local concerts, you might go with the theme that "West End Park Rocks," going with a rock-and-roll theme for all of the visuals you'll create. You'd then want to see what this theme filters out into—how do you express rock and roll visually? Do you use a guitar outline? Do you have a band silhouette? Do you adapt the visual conventions of classic concert posters and album art? You have to figure out what the theme does when it meets the deliverables and campaign you are working with.

First off, you need a theme that you can think through. To arrive at a theme, you want to think as broadly as possible. One thing that can be useful when you're creating a theme as a team is to find examples of content that you're required to incorporate as well as content that you like. Create a dropbox of sorts of your ideas and examples that you can use to collect data on what you might use as a theme. If you're designing a public information campaign like the example above, use your phone to take shots or screenshots of things that fall into that genre that have elements you like. Just like with visual conventions, you're looking for elements that you can blend together into your own cohesive whole, your own theme.

Themes can also work with feelings and ideas—you can think about what types of ideas and feelings are associated with your project. For this, instead of creating a repository of content, you may want to start brainstorming with something like a word map. What key terms make sense for your project? What are terms and adjectives that expand off of them? What theme might you create that could encompass all of these terms and thoughts? See the example below for what this might look like sketched out on a whiteboard:



With the above example, the word map begins with the term joy, and then expands in different directions. The team in the example goes in two primary directions—synonyms for joy and actions associated with joy. Then, you’ll see the connection built off of express and sharing towards community, two things that communities tend to do. The final result here might end up being a theme of “The Joys of Community,” based off the mapping and what meshes well.

Feelings and adjectives can also be associated with particular styles, so once you get into a concrete theme in this area like “The Joys of Community,” then you’d want to think about fonts and imagery that are associated with joy. This could be another place for the type of data collection and examples noted before where you create a makeshift dropbox for content that you can share to think through what the particular theme looks like when expressed horizontally across a campaign.

### Creating a Final Theme Style Guide

Regardless of your direction, the goal of this phase is to come up with a concrete theme that you can use for your deliverables and project. The end internal deliverable from all this work should be a concrete breakdown of what your theme will be and how that theme will impact your deliverables. The following items may be useful to build your theme into something that can be shared and used, the beginnings of a style guide (something we’ll get to in the next phase in more detail):

*Theme description:* What is your theme? How does it relate to your project’s goals and audience, and how does it impact the deliverables?

*Theme colors and imagery:* What colors and images are associated with this theme? Think categorically here.

*Theme fonts:* How does this theme translate into font choices? What fonts will be used, and where will they be used?

*Theme layouts:* What will be the various layouts/deliverable designs? How will they incorporate the theme to share information with your audience and to complete your goals?

Once you have all of this together, you’re in a good spot to start thinking about putting all of this into practice with a concrete style guide and some prototypes of your deliverables.

---

This page titled [6.1: Ideas, Audience, and Goals](#) is shared under a [CC BY-SA 4.0](#) license and was authored, remixed, and/or curated by [Adam Rex Pope](#) via [source content](#) that was edited to the style and standards of the LibreTexts platform.

## 6.2: Working with Others (Inside and Outside the Team)

### Phase 2: Working with Others (Inside & Outside the Team)

When you think about creating a major project, one of the major hurdles that you'll encounter is communication—how do you communicate with the folks you're going to be working with? What are going to be the ways you communicate and what rules will govern that communication?

Generally speaking, the idea that too many cooks can ruin things holds true for design projects. Too many goalposts and too many folks with power can make things get crazy. Because of that, you want to have a well-structured workflow that will solicit feedback from stakeholders in a productive way while allowing your team to get work done without being constantly second-guessed and overridden.

One major step you can take is to establish a concrete communication channel and a point person for each major group of stakeholders. Communication can be routed through this channel and these individuals, preventing chaos and overload. It can also help if your workspace for deliverables and other content isn't accessible to the stakeholders—you don't want something that you're not ready to share getting shared.

As far as file services and the like, take stock of what features you'd need and what is available and secure or preferred. For example, if you're doing something that is primarily text-based, you may want a service that allows real-time commenting and responses to comments with an editing interface. If you're doing something primarily graphical or that will be printed, you'll want to make sure your files can be shared easily and accessed quickly. Adapt to your situation.

Chat solutions like Slack and Teams can also be helpful, but be aware that you don't necessarily want an open channel between your team and the folks you're working for. The design process can be a messy and chaotic experience to those on the outside that don't understand what iteration looks like.

### Style Guides

One of the most powerful tools that you can leverage when working in multi-person teams is going to be the style guide, a document that allows you to decide what will be the canonical choices for any and all design and textual variations. Style guides are used for visual design as well as for editorial work, allowing you to put into writing your final decisions and preferred practices regarding the word choice and the visual look of a given project. They're immensely helpful, especially when a final deliverable is the product of a large team working for multiple stakeholders.


Style guides are usually formatted as reference materials and are designed to regulate what the communications of a given organization are going to look like and feel like. Having a cohesive visual style as well as a cohesive editorial style allows for regular information and consistent representation of the organization. For example, most universities have very particular ways that you can present a school or department with the university logo/wordmark. This is designed and guarded in such a way that when you see the particular official combination that is approved, it looks like an official university text. The same also holds true for how to abbreviate titles and positions.

In the corporate world, style guides are used for consistent brand imagery and for consistent internal and external communications. Starbucks is famous for their web style guide and Boeing is famous for never changing the name of a part, allowing mechanics to always know what they're talking about and working on. Practically speaking, a style guide lets you know what is going to be okay and not okay when working in an organization and it allows those in charge to put into place their desired design choices in a relatively transparent way for those in the organization doing communication work.

In some cases a style guide may reference an external system like the Chicago Manual of Style. A preferred dictionary might also be used, often the Merriam-Webster Dictionary in the US. In these cases, the organization is allying itself with a standard that is larger than one particular group or company. This can also be the case when an organization works primarily in an area where the style is dictated by formal groups associated with the work, such as legal teams using standard legal annotation.


When creating a style guide, you'll tailor the guide to the situation. A comprehensive guide will often cover official word marks, logos, color combinations and color codes, typographical choices, layouts and templates, as well as editorial choices such as abbreviations. More targeted guides may limit themselves to just visuals or just text.

Below is a brief one-page example of what a style guide might look like, especially if you go for a plain guide that focuses on getting information across quickly:



In the example guide, you have information on the feel/ mission of the company first off. The mission statement is often used to set a tone and goal for communications. This can also be true of projects and campaigns. Next you have the official type choices in a limited format, displaying the choices at the size and format recommended. Next you have the official presentation of the logo and the wordmark slogan. A wordmark is often a text-based representation of an organization without any extra graphical elements. From these examples, you can know exactly what choices you're going to need to use when you work for this organization.

In addition to missions and typography and logos/wordmark, you can also encounter colors and layouts in a style guide. For your own projects, these can be extremely helpful because they can be a way to quickly communicate your design ideas without getting into specifics. See the example here for what this might look like.




## STYLE GUIDE PAGE ON DESIGNS

In the example on the right, you'll see specific color swatches are presented, color combinations are suggested or required, and a little bit of information is given about color usage. This is the norm in many guides, and while this guide only includes RGB codes, many official guides would include CMYK to make sure colors are consistent across mediums. The templates that you see simply suggest the overall shape and form in this limited example, but they can get much more specific. The business card on the right is closest to a concrete example.

A style guide really should expand and contract in content and scope depending on how you want to use it. The goal here is that you can communicate to folks the specific ways that you want to share information and how you want to present your project/organization. In our case we could almost go all the way into a design brief, another classic type of project-oriented document, but for our purposes we'll stick to the style guide.

The final expression you may see that I'd like to show an example of is the editorial style guide, a guide that suggests that wording and textual choices that will show up in your documents. In group writing situations an editorial style guide can be useful to make sure you're keeping a consistent tone and word choice throughout. See the example on the next page:



## **STYLE GUIDE PAGE ON EDITORIAL STYLE**

In the above example, you see a discussion of tone, specific references for how to talk about members of the organization, and guidelines for discussions of outside groups and the current promotional campaign. The above is an abbreviated look at the ways that organizations often set particular guides for how official communications are worded and how specific groups and processes are referenced. Depending on the extent to which an organization is looking to create a readily-identifiable voice, the choices and power of an editorial style guide can be limited or extensive.

Think about the style guide as the place where you'll make the tough calls once. Decide as a group and with the input of stakeholders what your official colors, images, approach to text, and all other design choices is going to be and then standardize them in the guide. The guide becomes the place that decisions are made and recorded. This can be especially powerful in settings where you're the leader of a team of writers and need to exert control without the need to micromanage everyone and everything.

Your style guide may not be finalized by the end of Phase 2, but you should at least get one started. As you go, update the version of the style guide and make notes as to what has changed in each version—this will give you a clear idea of what has happened and why as your project has developed.

---

This page titled [6.2: Working with Others \(Inside and Outside the Team\)](#) is shared under a [CC BY-SA 4.0](#) license and was authored, remixed, and/or curated by [Adam Rex Pope](#) via [source content](#) that was edited to the style and standards of the LibreTexts platform.

## 6.3: Prototypes and Iteration

### Phase 3: Prototypes and Iteration

Once you've gotten to the point that you know your goals and have a concrete set of ideas for your audience that will be created with specific deliverables, you need to start prototyping and iterating. Having a style guide at this point can be valuable, but your guide can grow or come into being during this phase rather than before if your circumstances dictate that kind of workflow.

The goal of the prototyping phase is to get your deliverable created in a makeshift form that will let you test it and see how well it works and whether it is going to meet the expectations of those involved with your project. There is often something quite different between pitching an idea theoretically and holding that idea in front of you or seeing the idea on a screen in the case of a digital deliverable. By putting everything together, you get a clear sense of what your design will look like and work like.

Your prototyping phase should also include some testing, ideally. You'll want to see how your design works and whether you get the impact you actually planned for with use. You can do this using some of the methods discussed in the next chapter.

Once you've got your design tested, you'll want to iterate from the original design where needed. Don't be afraid to rework a design that isn't coming together or getting the reaction you were hoping for. The prototyping phase exists so that you can get a low-stakes reaction to your planned design without having to commit to a full production run of the deliverable. Much better to rework a prototype than to end up with finalized deliverable that just doesn't work out.

### Effective Time Usage and Templating vs. Tinkerating

One note that is of the utmost importance when you're working on prototypes and other designs: guard your time vigorously! You will need to guard your time, more often than not, from yourselves. That may sound weird, but bear with me. Often times when you're doing a design project, especially one with fancy elements, you can get caught up in the what-if's of it all. This gets even worse when you're building your templates and designs in the software you'll publish with final deliverable with. To avoid time wastage, there are a few things you need to keep in mind: the Cake Method and Templating vs. Tinkerating.

First, let's cover the Cake Method. It sounds silly, but it is the product of my having been involved in two birthday cake fiascos in a row in which a fondant-centered design was scrapped at midnight in exchange for cupcakes or something less amazing. It was also influenced by two student projects two years in a row that self-immolated due to 90% of the time on the project being spent on a design element that simply never came together. I'll explain.

When you are working on a major project, many times the fancy little bits get your attention. You end up trying to tweak the one cool idea that you have about the design, and that ends up taking all of your time. It might be a logo. It might be a cool graphical effect on a website. It could be a fancy infographic idea you have. It could be fancy animations and graphics on a Power Point or Prezi. In the end, the amount of impact that cool bit has on your final deliverable is fairly negligible, but it's just so darn cool that you spend a massive amount of time on it, resulting in a project that has a cool graphic but no real content. It's like someone asked you to make a cake and you brought them a custom sculpted or 3D printed cake topper and a box of cake mix.

The Cake Method attempts to help you work through your design woes by breaking up your time into chunks of content that mirror the construction of a cake, sorting the content into what has to be there and what would be nice to have. The base of a cake is the actual cake itself—you need cake for a cake, right? Next, you have the bare minimum of decoration, usually some sort of icing. After that, you might have decorative trim that really brings the cake into acceptable territory. Finally, you have additions that make the cake fancy such as various scenes that might be built on top like a construction site for a kid that loves heavy equipment.

The idea behind this breakdown is that you create tiers of importance with your content, tiers that align with the most basic cake versus the final tier of fancy decor. You organize your content into each of these tiers, and then you work through each one of them in order. You're not allowed to work on the fancy final stuff until you've finished everything underneath. That way, you don't end up with fancy decorations and no cake to put them on, metaphorically speaking. See below for a chart than can help with this breakdown:

Tier	Goals	Content	Time Spent
Base			
Essentials			
Expected Accents			
Final Polish			

### **A TABLE TO BE USED TO ASSES OBJECTIVES AND TIME ALLOTMENT**

To use the chart, you'll want to break down your project into four basic tiers, just like we broke the cake down into the bare minimums, the essential elements, the expected accent decor, and any final polish and fancy elements. The base tier is the absolute minimum for your document. This may well be the actual text elements that you need to generate to fill the text. This work isn't sexy, but it simply has to be done and can truly suffer if you rush it. Next, you have the essential elements that would be needed—this can vary from design to design. It might be a series of simple templates that arrange things differently in a large campaign, or in a large document it might be the chapter breakdowns and sections and sub-sections. Next you have the expected accents; this might be something like color-coded headings and things along those lines in a large document. Finally, you have the final polish tier that includes the fancy elements than can take a large amount of time. This might be something like a heavily designed logo element or a complex infographic-style graphic that doesn't have to be in the text but that makes the text more understandable.

The goal behind all of this is that you'll have a fully-functional document that you can add elements to gracefully by the time you get to the final polish stage. It also recognizes that the fancy elements that we often want to focus on can take an inordinate amount of time, time that is fine to spend if we have managed to complete our text. You can't build a text around a complex element that you may not be able to pull off. You build the text first and then see if you can pull off the extra element.


Sometimes your text is the fancy decorative element, or you have a design that is entirely driven by a fancy design. That's okay. In those cases, you spend more time on the design element. It is the cake in that case, not the final topping. The goal here is to arrange your steps in the project by their importance and to spend time on what has to be there before spending time on things that would be nice to have.

One additional tool that can be useful when managing time is making a distinction between Templating and Tinkerating. When you work on a project, you often need to come up with templates and designs that you can work through and design around. What I suggest, every single time, is to design your projects with pen, paper, and colored pencils first. Do not use a design-oriented program or code (in the case of the web). Do. Not. Do. This. You'll more likely than not end up wasting time.

The problem with designing with a design program is that you have an infinite amount of tools available to create your design, and you often end up playing with those tools rather than working on your template. I call this Tinkerating because you're going to be tinkering as much as you are doing anything else. Now, that isn't to say that playing with the design program is bad—that is one of the ways you get better at the program or at coding in the case of the web. But, with that said, you don't need to be playing in the program when you're thinking about a design. You can prototype a design much more quickly with paper and a pencil than doing the code or design work behind it. Finally, working with the design program encourages you to put in flashy elements and to spend time making things look nice when you're not even committed to the final design you're building! Think back to the Cake Method—this is not the way you want to spend your time!


When it comes to templating and thinking through designs, the fast route is almost always the best. A quick sketch can help you think through a design quickly without too much trouble. When I'm teaching or designing, I usually try to do lots of stuff like the

example here:



**AN EXAMPLE TEMPLATE SKETCH**

In the example on the right, I've got a brief template for the front page and the body of a newsletter. You have a colored heading on the first page, then two columns with an image in between. You also have a small element on the bottom corner. The main body is two major columns with the shared element in the bottom corner. This is a fairly simple design, and it helps me see issues with layout quickly. You may notice the image looks weird between the columns, so I need to rethink that. Drawing it out allows me to see spacing issues quickly without getting into the weeds. If I wanted to go a bit further, I could embellish this all with colors to get a better sense of what I'm doing:



**A SECOND TAKE ON THE TEMPLATE SKETCH**

Here you'll see I've colored in the top section to give a nice colored header, I've added in a title to show where that would be in black, and I've redone the images in the middle to better use the space and tried out using red for the bottom element and red

frames for the images. After seeing this, I'd likely switch to black for the images, but I like the red elements (though I might add another on the top on the second page for symmetry). Again, this has taken me just a minute or two and I'm already working through the design without having to worry about getting things lined up perfectly or getting the colors or something else right.

Use your time wisely—guard your time from the demands of others and from your own fancies. The best design is the one that gets finished and out the door, not the one with the fancy logo that never gets the polish it needs because all the time was wasted on the logo and not the actual contents of the deliverable. Use the Cake Method, avoid Tinkering, and do your templating work as quickly and directly as possible. Don't commit to spending real time on a design or layout until you're sure it's ready for that investment of time.

---

This page titled [6.3: Prototypes and Iteration](#) is shared under a [CC BY-SA 4.0](#) license and was authored, remixed, and/or curated by [Adam Rex Pope](#) via [source content](#) that was edited to the style and standards of the LibreTexts platform.

## 6.4: Rights and Images

---

### Phase 4: Rights and Images

When you get ready to move towards publication, you should make a check that you have the rights to all content and images used. In the case of content created outside of your group, realize that in the US that any content created by an author is immediately copyrighted at the point of creation. Without explicit permission, you cannot use that content commercially.

Usually the content that ends up requiring that you source rights will be images or music. In these situations you will need to identify who holds the rights to the content you need and get permission from them. The rights holder may not be the person who created the content originally, as in the case where the rights have been sold to another individual or organization.

If you need to get high-quality content for your deliverables but don't have resources available to create your own, you should investigate stock photo services that often have a range of photographs available to meet most generic project needs. In the case you need something specific, you may well need to generate content yourselves or pay someone to do the work professionally.

There are limited open-source and copyleft content sources that you can use to get free content, but as mentioned elsewhere in the text these sources can be sketchy at times and sometimes come with explicit limits on commercial use or with clauses that would then cause your own work to be open-access or copyleft. In a corporate environment especially, these types of constraints are dealbreakers.

---

This page titled [6.4: Rights and Images](#) is shared under a [CC BY-SA 4.0](#) license and was authored, remixed, and/or curated by [Adam Rex Pope](#) via [source content](#) that was edited to the style and standards of the LibreTexts platform.

## 6.5: Editing for Publication

---

### Phase 5: Editing for Publication

Before you start the publication process, you will need to get a final edit. The rule of thumb with this type of work is to always base this editing off of a final proof. You need to see the final proof and edit from that in order to get a full sense of what your text will look like and to identify errors that will have cropped up in the production process. This type of editing is different than the standard editing that might come into play when you're working through the prototyping and iteration phase. You will want to have a settled text that is ready for your final audience and publication when you start your final editing pass. The goal in this pass is to identify any missing content, any mismatches between your design and the final proof, and to catch any mistakes previous passes missed.

Remember that editing before production is a risk-mitigation strategy. Any errors you can catch before you go into final production will prevent costly and potentially embarrassing mistakes where you have a final run with glaring errors throughout. It costs much more money to pulp an entire print run than to reprint a proof.

In particular, focus on the colors, the quality of images, the location of content on the page, and other major features that can only be assessed once the deliverable has been put into its final form. You don't want to end up with images that are too pixelated or blurry or pages that are aligned too close to a margin for readability.

---

This page titled [6.5: Editing for Publication](#) is shared under a [CC BY-SA 4.0](#) license and was authored, remixed, and/or curated by [Adam Rex Pope](#) via [source content](#) that was edited to the style and standards of the LibreTexts platform.

## 6.6: Publication

---

### Phase 6: Publication

When you've reached the publication phase, your job is to make sure you get the quantity of deliverables you need to the folks who require them. As a team, make sure that you understand what has been requested and when. Having a great project doesn't matter if that great project doesn't get to the folks who are supposed to use it. Double-check your numbers, your delivery mechanisms, and your timeline.

Finally, take some time to look over the final deliverables. Even with a closely monitored proofing process, there can be errors that happen. Your partner for publication may have gotten colors wrong, used the wrong material, or cut things wrong in the case of a design with a bleed. Double-check all of this. Just because your proof was awesome does not mean that your final design will be awesome as well. Mistakes happen.

---

This page titled [6.6: Publication](#) is shared under a [CC BY-SA 4.0](#) license and was authored, remixed, and/or curated by [Adam Rex Pope](#) via [source content](#) that was edited to the style and standards of the LibreTexts platform.

## 6.7: Closing it Out

---

### Closing it Out

The above is just a framework that you can use to think through the process of getting a project from start to finish. You don't have to take my method as the Truth, but instead I offer it as a suggestion and a system that can help you guide a project. You'll want to come up with your own system that integrates the overall writing process that we've covered previously, the process of designing visuals and documents, and the project timeline to get things done.

When it comes to technical writing, we deal with people and conditions that change over time. The one constant is that things will change. In these situations, what can be useful is not a concrete way of doing something every single time, but instead a method of going about doing something. If you have a method of figuring out how to do something, that will serve you well when the thing you're doing changes and you're left figuring out how to adapt. Getting too wedded to a specific step-by-step specific implementation of how things are going to be can be dangerous because things do and will change. But, if your process is an open one that makes general moves and asks open questions rather than setting specifics, you'll find that you can work through changes with less stress because you're not tied to a specific way of doing things that is threatened when the context shifts.

---

This page titled [6.7: Closing it Out](#) is shared under a [CC BY-SA 4.0](#) license and was authored, remixed, and/or curated by [Adam Rex Pope](#) via [source content](#) that was edited to the style and standards of the LibreTexts platform.

## CHAPTER OVERVIEW

### 7: Research Methods for Technical Writing

[7.0: Introduction](#)

[7.1: Doing Research with People](#)

[7.2: Interviews](#)

[7.3: Talk-Aloud Protocols](#)

[7.4: Card Sorting](#)

[7.5: Participatory Design](#)

[7.6: Observation](#)

---

This page titled [7: Research Methods for Technical Writing](#) is shared under a [CC BY-SA 4.0](#) license and was authored, remixed, and/or curated by [Adam Rex Pope](#) via [source content](#) that was edited to the style and standards of the LibreTexts platform.

## 7.0: Introduction

---

Welcome to the end of the book. This is a weird sort of chapter, unlike any other chapter in this text. You may well have come here at my insistence from an earlier section, so let me explain how this all works.

In this chapter you'll find five or so different segments, each focused on giving you a loose understanding of a particular research methodology. In the first draft of this book in particular you'll find that these are general treatments rather than super-specific ones. The idea behind this design is that you'll be provided with the fundamental information you'll need to carry out these research methods within your technical writing classrooms, and that with the help of your instructor you can investigate these further, or you can research them further on your own.

Each one of the methods here could, and does, have entire books dedicated to their practice, so keep that in mind as you read. Additionally, I'm not offering by any means a definitive approach to any of these methods. Instead, I'm attempting to provide you with a general understanding of how you can use them to do original research for your technical writing projects.

In the following sections we'll cover Interviewing, Talk-Aloud Protocols, Card Sorting, Observation, and Participatory Design. To get a brief window into each, below you'll find a brief summary of what the method does and why you might use it:

### *Interviews*

Interviewing is about getting information from people by interacting with them. This can be on the phone, online, or face-to-face. The goal here is to talk your way into understanding a situation. Interviews can be useful to get a rich understanding of your audience or a situation, but take planning and direction to succeed.

### *Talk Aloud Protocols*

Talk Aloud Protocols, or TAP are used to get information from a user while they're using a system. They can be extremely helpful to identify when things break down during use, but they do create some artificial results from time to time. A bit of work is involved, depending on how you document things, but TAP can be essential in figuring out a breakdown in workflows.

### *Card Sorting*

Carding sorting is a powerful method where you use cards to create categories with your users. This sorting can be useful to help you build a system of categories or to test the effectiveness of an existing one.

### *Observation*

Observation is exactly what it sounds like, and differs from TAP in that you aren't going to necessarily be working with your users or even letting them know what is going on. You're observing and making notes from your own point of view.

### *Participatory Design*

Unlike the other approaches, participatory design is more of an overall approach rather than a specific method. Participatory design involves getting your users involved in the design process and giving them power and agency. We'll discuss some basic tips for this.

Going forward, you'll find each of these approaches has a write-up that will be helpful in guiding your work. You'll want to decide which one makes the most sense for your situation.

---

7.0: Introduction is shared under a [CC BY-SA 4.0](https://creativecommons.org/licenses/by-sa/4.0/) license and was authored, remixed, and/or curated by LibreTexts.

## 7.1: Doing Research with People

---

### Doing Research with People

Before we go further, I want to bring to your attention a crucial aspect of this work—you will be working with and researching people. Unlike doing scholarly work on existing texts and journals or even chemicals, working with living subjects, and people in particular, is tightly controlled at the university level. Your university likely has an IRB, an institutional review board, that will govern your official inquiry to create new scholarly knowledge. The goal behind these processes is to protect the folks you're researching from harm.

In the private sector, there aren't as many controls on researching with people, and so the primary goal that you should strive for in your research in these cases is consent and transparency. You need to make sure folks know what is going on and what you're doing and that they agree with you and your goals and methods. Research should help you out, yes, but it should also at the very least do no harm to those you work with. If you're researching folks, they need to know and they need to consent. Anything less is unethical. Yes, you may need to hide specifics about which particular design they're working with, but they need to understand what is happening and what you're going to do.

In particular, you need to guard personal information—anything you collect needs to be anonymous and needs to be impossible to trace back to your participants in a way that could cause them harm. This is your duty to the folks you research in private settings. In addition, you need to make them aware of how you're taking notes/recording content and how you'll store that data and anonymize it as needed.

---

This page titled [7.1: Doing Research with People](#) is shared under a [CC BY-SA 4.0](#) license and was authored, remixed, and/or curated by [Adam Rex Pope](#) via [source content](#) that was edited to the style and standards of the LibreTexts platform.

## 7.2: Interviews

---

### Interviews

One of the most basic approaches to doing user research is the interview. Interviewing may very well be the most difficult of these approaches to research because you need to prepare fully and act with purpose in an interview if you plan to get any sort of useful data out of your time. In this section we'll cover the goals of an interview, strategies for carrying out an interview, and approaches to recording data from interviews.

#### Goals of the Interview

When you do an interview, you are getting an unique chance to hear from someone in their own words what they think about a given subject. With that said, the person you're interviewing also knows this, and sometimes will self-edit to present what they think you'll want to hear or what sounds like the best choice for a given situation. So, interviews are not without their risks and potholes to avoid.

When you plan an interview, you need to know what you're hoping to get out of the process. You can't simply go into an interview and let things develop—you're going to waste your own time and that of your subject(s). Instead, think about what you want to know. Do you want to know about a specific experience or a particular text? Do you want a broad overview of how a workplace functions? Carefully consider your goals and your scope of questioning. One interview shouldn't do too much or too little.

Time and timeliness also comes into play with interviews. For example, email interviews are notorious for dragging out into infinity with folks simply ignoring or putting off the interview and questions to spend their time elsewhere. Think about how much time you have and what your schedule looks like. Align the type of interview you want with your goals and your timeline realistically.

#### Strategies for Carrying Out an Interview

Interviews require a strategy on your part to be effective. Not every interview subject will have the same level of comfort and willingness to share. At the same time, they may not even understand your questions if you pose them in a way that is foreign to their own terminology and understanding.

First and foremost, you want your subject to feel comfortable talking with you. Many times this is a matter of preparing the proper location and the proper setting. Doing an interview in someone's workplace or workspace in particular can be challenging because the bustle of daily work can interfere with your work and intrude or shorten your interview. Your demeanor and your dress also come into play—you don't want to be too dressy or too casual compared to your subject. Ideally, you'll be in the same ballpark or slightly more dressed up on a scale of casual to formal.

Besides location and your demeanor and dress, you'll also want to consider the way you ask questions as it relates to subject comfort. Your questions shouldn't be too accusatory or aggressive if you're wanting to keep your subject comfortable. At the same time, they should not be too personal or sensitive. Many times folks will say more than perhaps they even meant to in an interview setting, and you want to guard against asking questions that prompt them to share things that are too private for the setting. (The same advice usually goes out to teachers who ask for personal essays).

Next, you want to consider your questions and goals. When you ask someone a question in an interview, the question should be crafted to get the information you need. Close-ended questions that terminate with a simple yes or no answer can be self-defeating in this arena because you're not going to get the valuable insight and elaboration from your subject that you need. Interviews are valuable because you're getting a very specific set of information about a subject, and a series of yes and no answers is not that.

When crafting questions, try to prompt discussion by your respondent with some direction. You can vary the level of specificity as needed and to keep things fresh. You might ask some entirely open-ended questions like, "What do you think about this document?". You could also ask fairly specific questions like, "How effective are the headings and subheadings in this document, and how might you change or improve them—if you would change anything at all?"

Remember with questioning that your goal is to get information from the person you're working with to help you with a particular technical writing project. Write questions with that project in mind and your goals in mind. Don't waste your time and your interviewees' time with anything off topic or irrelevant.

Finally, set some standards for your interview from the get-go. Let your subject know what you're going to discuss, the types of things you're going to ask, and the length you're aiming for. That way, they don't spend their time second-guessing what is coming next or looking at the clock. By being upfront about all of this information you set yourself up for success by making the process itself less of a worry to the person(s) involved.

### Approaches to Recording Interviews

It is worth noting that the way you decide to approach an interview's recording can impact the feel and the response of the interview. You'll want to make sure your interviewee understands they are being recorded if you make use of any mechanical means to record the conversation. Often you may find that video cameras have a tendency to make folks uncomfortable in a way that an audio recorder does not. In cases where you can't make use of either of these, you will want to transcribe yourself, noting important information.

If you opt to take your own interview notes, please realize that this is a skill that is built over time. You need to have a real sense of what is important and what is not, as well as a good system for shortening what you need to write down. Practice more than a little before trying this with an actual interview you're running.

Be aware that if you take the time to note something that happens in the interview and you make notes as if that something is important, you can skew the rest of the interview. Everything you do will impact the way the other party experiences the conversation.

Finally, if you are going to be using anonymous data, you will need to transcribe the interview recordings and anonymize them and then destroy the originals. Voice recordings or video are not anonymous and if you've promised that to those you're working with, you'll need to make sure to honor that promise.

---

This page titled [7.2: Interviews](#) is shared under a [CC BY-SA 4.0](#) license and was authored, remixed, and/or curated by [Adam Rex Pope](#) via [source content](#) that was edited to the style and standards of the LibreTexts platform.

## 7.3: Talk-Aloud Protocols

---

### Talk-Aloud Protocols

Talk-Aloud Protocols, or TAP as we'll refer to them in this section, are a useful way to get a window into what is happening when someone is using a service or document. In the protocol, you ask a user to perform a given task while talking aloud their thought process. The TAP focuses on figuring out how folks interpret what is in front of them and the strategies they use to navigate through a document or service. There is some element of artificiality to TAP because of the self-filtering that happens when your participants talk aloud, and there is also a level of hyper-focus that wouldn't exist otherwise. With that said, the approach can be extremely useful to figure out how well folks can find a particular bit of information or operate with a document or website or service.

#### Structure

Usually a talk aloud protocol happens in a controlled environment where there are recording tools available. Using a PC, you can often make use of a webcam to track the focus of your participant while they are looking through the text that you've chosen or a website. Using a TAP is very common in testing websites in particular.

The TAP is oriented around a series of tasks that you have chosen for your participant(s). You might ask them to find a bit of information in a website or document. You might ask them to finish a task like registering for a course or event. You could even ask them to locate an item in a store. The task will depend on what you're hoping to find out.

As the participant performs the task, you'll ask that they verbalize their thought process. You may find it useful to model this for them first. The goal is that as they're searching through a site or document that they'll explain the rationale behind where they are looking and what they are doing. This type of talking can be useful because it can at times provide a window into the way your audience perceives your text or site and allows you a window into the framework they use for navigation and value making.

In general, you'll want to allow your participant to do their own work, though you may need to prompt them with the next step of your protocol as you're going through, or you may need to assist them if they get frustrated and stuck. The goal here is to keep getting information from your participant, not to make them hate the process and experience.

#### Technology

When you're carrying out a TAP, you'll be able to use any number of technologies to assist. Some suits of software are specifically designed for TAP work, including Silverback for Macs. You may also use screen recording tools to track what is going on, or screen casting software to capture both the screen and the participant. In remote research you can often use services like Skype with video chat and screen sharing to see both the participant and your target text as they navigate it. You can also record someone in a physical space if they are navigating a place or a printed text. This relatively flexibility via technology makes TAP work a great choice whenever you need to know how someone would use your text or site or when you need to figure out why folks are getting to the wrong place.

#### Interpretation

When you're watching a TAP or reviewing the TAP after the fact, you can interpret data from any number of sources. First, you can simply watch the eyes and progress of your participant for valuable information. Where do they look first? What is their natural first choice to solve an issue? Is this the same first choice you'd assumed they would make? Second, you can listen to what they're putting forward as their logic of navigation. Ideally, they'll explain where they are looking and why. You can see if this logic matches up with the logic of your text and whether there needs to be a change in the text to match up with or defeat their logic's appropriateness. (For example, someone might misread a term on your site and use faulty logic from that misreading to take them down the wrong path. In that case you might want to alter the terms on your site so you don't accidentally mislead folks with terms they interpret differently than you intended).

---

This page titled [7.3: Talk-Aloud Protocols](#) is shared under a [CC BY-SA 4.0](#) license and was authored, remixed, and/or curated by [Adam Rex Pope](#) via [source content](#) that was edited to the style and standards of the LibreTexts platform.

## 7.4: Card Sorting

---

### Card Sorting

Card sorting is a fascinating approach that you can use with minimal technology to figure out how your participants use terms and group them together. The approach can also be a powerful tool for sorting in situations where you need to think collectively, but we'll primarily focus this discussion on using card sorting as a testing method. Card sorting is fairly literal in its meaning—you use notecards or something equivalent while asking users to sort those cards into various stacks that go together. The goal is to figure out how folks sort, and you may even go further to ask them why.

Card sorting can be guided or unguided, meaning that you can create your own categories to allow folks to put content into, or you can give them a stack of cards and ask them to create their own categories for the content/terms that each card represents. Each approach has value and gives you a different insight into what is going on with your terms/categories.

### Structure

Usually a card sort is structured around a stack of terms. The source of the terms can vary, depending on what you're hoping to find out. For example, if you have a menu system for a website and you want to know how folks would categorize your pages, you can use a card sort to figure out how they'd lump content together in their own categories. You can also use card sorting to figure out if your existing system makes sense, having folks place each item in your menu system into the top-level menu headings, testing to see if they follow your logic or another logic.

A card sort can be entirely focused around sorting, or you can include a component of explanation. You may simply want folks to organize cards, but you can also include the ability to name stacks when this is happening in an unguided sort, giving folks the ability to create their own categories rather than just stacking content in the same pile. In addition, you can ask folks to explain the choices that they've made once the sort is over, which may give you additional insight into the logic they used to make their choices.

Face-to-face card sorts are the norm, but you can also use electronic services to carry out a card sort. There are any number of services online that will allow you to create card sorts, and you can create your own ad hoc sort using a database program like Excel or the equivalent. In that type of scenario you would simply list your terms and ask folks to put them into columns using copy/paste.

In any scenario, it is incredibly valuable to get the actual feedback from the user after they've done the sort, so whenever possible try to get your users to explain after they're done why they've sorted the way they did. It may be best to ask them this after rather than during—you don't want to push them to overthink their work.

### Interpretation

The interpretation of a card sort closely follows the way you've set it up what you hope to learn. If you're giving folks a set of subjects and asking them to place them in an existing set of chapter headings, you'll likely want to try and see what is different between the logic the user makes use of and your own logic. This can be helpful when you're trying to build a table of contents for a manual or other document that will be useful for reference. In scenarios where you're attempting to make groupings, you'll want to see how folks place the content, and you'll want to pay special attention to content that doesn't seem to fit anywhere at all. This can be a sign that your content is misnamed or doesn't belong in the existing framework; it might also mean that your users simply don't find much value in that content or really understand what it means or why it is there.

Again, you'll want to think through your card sorting as a way to find out how folks view categories and terms. This can identify terms that are misunderstood, terms that folks see as belonging together, and generally help you get a better handle on the taxonomy of a given project. Design a sort around something you want to learn; you'll find you get better results with a goal than simply performing a card sort to perform a card sort.

---

This page titled [7.4: Card Sorting](#) is shared under a [CC BY-SA 4.0](#) license and was authored, remixed, and/or curated by [Adam Rex Pope](#) via [source content](#) that was edited to the style and standards of the LibreTexts platform.

## 7.5: Participatory Design

---

### Participatory Design

Rather than a particular method, participatory design is an overall approach to the idea of document design and composition. Instead of creating something and then bringing users in to test what you've created, participatory design as an approach asks that you bring users into the very act of creation. This is a highly complex approach and one that has supported decades of research from any number of technical writing and usability experts. As such, don't take this section in our text to be definitive by any means, but rather as a very basic introduction to some ways you might want to begin to think about bringing folks in to participate in the design of projects that impact them.

Rather than a particular method, participatory design is an overall approach to the idea of document design and composition. Instead of creating something and then bringing users in to test what you've created, participatory design as an approach asks that you bring users into the very act of creation. This is a highly complex approach and one that has supported decades of research from any number of technical writing and usability experts. As such, don't take this section in our text to be definitive by any means, but rather as a very basic introduction to some ways you might want to begin to think about bringing folks in to participate in the design of projects that impact them.

### Structure

With participatory design, your goal is to bring someone into the design process so that they can influence it. The idea here is that the folks who actually do the work, who actually are working in a situation you're designing documents around, that these folks know the process and the variables better than anyone else might. They know what blind spots exist and what existing documents fail to do well or simply get wrong. As such, you want to bring them in at an early phase, allowing them to shape the fundamental conception of what the text does and why.

One strategy can be to start with the existing document and simply ask folks to tell you what it does well, what it doesn't do well, and what it simply gets wrong or omits. This can be a useful space for incremental change because you're starting with an existing deliverable that can be altered as needed to fit the needs of the folks actually working with it on a daily basis. This can also be a useful task to bring to folks that use a document that has been created elsewhere, such as folks creating financial reports from documents not created by their team. Documents can cause issues for the folks creating them or the folks using them.

Another strategy that can be helpful is to simply start from scratch and ask the folks you're working with what they do and how documentation can assist them in the work they do. What do they need to record? What do they need to pass on to others? This can at times be useful to discuss when you have multiple levels of folks in the same room, allowing them to see how different folks in the same organization need different things from documentation and from the workflow of others in the same company or group. Things that seem arbitrary at one level can be crucial at the next, and learning about the importance of data to folks at other levels of an organization can be helpful to those who generate text that seems meaningless to them.

At the end of the day, there are innumerable approaches to creating participatory structures for document design and service design. The above are two simple approaches that you can start with in your own work, but they are simply suggestions. There is a massive body of research out there that I would encourage you to pursue if you find yourself drawn to this research paradigm.

### Interpretation

When interpreting participatory design, please be aware that different users have different values that they give to documents and information. Depending on where someone is in an organization they may undervalue or overvalue information, or simply ignore it or not know it exists. Expertise within an organization can be hidden by existing documentation and ways of doing work. As a technical writer, you need to be aware of these issues and tread carefully. In some cases there can be valuable work that is getting done that documentation doesn't capture—you can help make that visible. In other cases, there can be work done for no reason and you can bring that to folks' attention.

Be aware that when you work participatory projects that everyone has a political agenda to push and that you need to keep the overall power structure of the organization and your role in mind when you interpret data. Don't do stuff that will get folks in

trouble, and keep in mind that entire organizations are built around document workflows and that emphasizing one group at the expense of another can create tiffs and rifts.

### Technology and Recording

Be extremely sensitive when using technology and recording tools with participatory design. Realize that all of the conversations you have are part of larger power structures that can get those who participate into trouble if the information they volunteer isn't well received or is taken out of context by those above (or below) them in the power structure.

---

This page titled [7.5: Participatory Design](#) is shared under a [CC BY-SA 4.0](#) license and was authored, remixed, and/or curated by [Adam Rex Pope](#) via [source content](#) that was edited to the style and standards of the LibreTexts platform.

## 7.6: Observation

---

### Observation

The final research method that I will share is observation, one of the simplest and most awkward of all research methods, depending on the implementation. Observation is simply that, observing folks using documents or working in a given workplace. Sometimes bordering on ethnographic research, observation can be a tool that you use to figure out how folks are working and using systems and texts without intruding into their workflow. You simply sit back and observe the situation, taking notes of things as they happen.

In public scenarios, observation can be extremely unobtrusive in that you can sometimes simply blend into the background. You may, for example, want to see how folks navigate the signage in the campus cafeteria. You could simply park yourself near the front of that cafeteria and observe patterns and when folks stop to interpret things. Obviously this would be more useful when you have large groups of folks using these facilities for the first time, such as during orientation week or when a visiting group are present.

In more closed scenarios, observation can involve permission to simply sit around and record what is going on. You will likely want to keep your recording to written notes, and you may need to get your notes checked with those that you're working with before you use them or take them out of the location, especially when sensitive information can be involved.

### Interpretation

Observation excels at helping you understand how a process or system actually works when folks work through it in a natural way. By casually observing a situation, you can see how folks navigate a space or document and when they become frustrated and at what rate. In private situations, you get a better sense of how work pulses and flows in a given location and the types of interactions and work that happens in a given space. Each type of information can be valuable for you as a technical writer because it gives you even more information to take into account when you consider the choices you make in your own designs and documents.

### Recording and Technology

As noted above, be aware that sensitive information can be relayed in a workplace or even in certain public venues. Take care that you're not going to be recording in a way that will disrupt workplaces or violate privacy. You may be asked to leave a room during a private observation, and you may need to ignore anything you hear in a more public venue if the content that is being shared would be embarrassing or otherwise troublesome to record and share. As I mentioned previously, you may want to default to written notes with observation, allowing you the chance to be your own editor as far as what is recorded and what is not. In addition, you should check with those you will be observing to see what types of sensitive information you should go to great pains to ignore or not record.

---

This page titled [7.6: Observation](#) is shared under a [CC BY-SA 4.0](#) license and was authored, remixed, and/or curated by [Adam Rex Pope](#) via [source content](#) that was edited to the style and standards of the LibreTexts platform.

## CHAPTER OVERVIEW

Front Matter

## Index

---

D

dire



## Detailed Licensing

---

### Overview

**Title:** [Open Technical Writing - An Open-Access Text for Instruction in Technical and Professional Writing \(Pope\)](#)

**Webpages:** 63

#### All licenses found:

- [CC BY-SA 4.0](#): 93.7% (59 pages)
- [Undeclared](#): 6.3% (4 pages)

### By Page

- [Open Technical Writing - An Open-Access Text for Instruction in Technical and Professional Writing \(Pope\) - CC BY-SA 4.0](#)
  - [Front Matter - CC BY-SA 4.0](#)
    - [TitlePage - CC BY-SA 4.0](#)
    - [InfoPage - CC BY-SA 4.0](#)
    - [Table of Contents - Undeclared](#)
    - [Licensing - Undeclared](#)
  - [1: What is Technical Writing? - CC BY-SA 4.0](#)
    - [1.0: What is Technical Writing? - CC BY-SA 4.0](#)
    - [1.1: Ethical Stakes in Technical Writing - CC BY-SA 4.0](#)
    - [1.2: Professional Voice and Technical Communication - CC BY-SA 4.0](#)
    - [1.3: Signposting and Taxonomy - CC BY-SA 4.0](#)
  - [2: The User - CC BY-SA 4.0](#)
    - [2.0: Introduction - CC BY-SA 4.0](#)
    - [2.1: Technical Writing and the Audience - CC BY-SA 4.0](#)
    - [2.2: Users and the Drafting Process - CC BY-SA 4.0](#)
    - [2.3: Technical Writing Research and Writing Process - CC BY-SA 4.0](#)
    - [2.4: Usability, Use, and Participatory Design - CC BY-SA 4.0](#)
    - [2.5: Institutional Writing - CC BY-SA 4.0](#)
  - [3: Visual Communication and Technical Writing - CC BY-SA 4.0](#)
    - [3.0: Introduction - CC BY-SA 4.0](#)
    - [3.1: How does visual communication work? - CC BY-SA 4.0](#)
    - [3.2: Using visual conventions - CC BY-SA 4.0](#)
    - [3.3: Signs, Safety, and Visual Rhetoric - CC BY-SA 4.0](#)
    - [3.4: Data Visualization and Infographics - CC BY-SA 4.0](#)
  - [4: Document Design in Technical Writing - CC BY-SA 4.0](#)
    - [4.0: Introduction - CC BY-SA 4.0](#)
    - [4.1: Document Design Essentials is Essential - CC BY-SA 4.0](#)
    - [4.2: Layout and Document Design - CC BY-SA 4.0](#)
    - [4.3: Typography - CC BY-SA 4.0](#)
    - [4.4: Attributes of Fonts - CC BY-SA 4.0](#)
    - [4.5: Font Availability and Ethics - CC BY-SA 4.0](#)
    - [4.6: Remembering those signposts - CC BY-SA 4.0](#)
  - [5: Writing in Genres - CC BY-SA 4.0](#)
    - [5.0: Introduction - CC BY-SA 4.0](#)
    - [5.1: Genre Research - CC BY-SA 4.0](#)
    - [5.2: Popular Genres in Technical Writing - CC BY-SA 4.0](#)
  - [6: Managing a Project - CC BY-SA 4.0](#)
    - [6.0: Introduction - CC BY-SA 4.0](#)
    - [6.1: Ideas, Audience, and Goals - CC BY-SA 4.0](#)
    - [6.2: Working with Others \(Inside and Outside the Team\) - CC BY-SA 4.0](#)
    - [6.3: Prototypes and Iteration - CC BY-SA 4.0](#)
    - [6.4: Rights and Images - CC BY-SA 4.0](#)
    - [6.5: Editing for Publication - CC BY-SA 4.0](#)
    - [6.6: Publication - CC BY-SA 4.0](#)
    - [6.7: Closing it Out - CC BY-SA 4.0](#)
  - [7: Research Methods for Technical Writing - CC BY-SA 4.0](#)
    - [7.0: Introduction - CC BY-SA 4.0](#)
    - [7.1: Doing Research with People - CC BY-SA 4.0](#)
    - [7.2: Interviews - CC BY-SA 4.0](#)
    - [7.3: Talk-Aloud Protocols - CC BY-SA 4.0](#)
    - [7.4: Card Sorting - CC BY-SA 4.0](#)
    - [7.5: Participatory Design - CC BY-SA 4.0](#)
    - [7.6: Observation - CC BY-SA 4.0](#)
  - [Back Matter - CC BY-SA 4.0](#)
    - [Front Matter - CC BY-SA 4.0](#)

- [TitlePage](#) - *CC BY-SA 4.0*
- [InfoPage](#) - *CC BY-SA 4.0*
- [Index](#) - *CC BY-SA 4.0*
- [Glossary](#) - *Undeclared*
- [Detailed Licensing](#) - *Undeclared*
- [Sources](#) - *CC BY-SA 4.0*
- [Back Matter](#) - *CC BY-SA 4.0*
  - [Index](#) - *CC BY-SA 4.0*

## Sources

---

Unless noted below, all images and charts and other multimedia components of this text are created by the author and authorized for this text. Scholarly and popular press sources specifically referenced and cited in the current version are as follows:

Kostelnick, C., & Hassett, M. (2003). *Shaping information: The rhetoric of visual conventions*. Carbondale: Southern Illinois University Press

## CHAPTER OVERVIEW

Back Matter